




**US Army Corps  
of Engineers**

Hydrologic Engineering Center

---



GENERALIZED COMPUTER PROGRAM

**HEC-5**

# **Simulation of Flood Control and Conservation Systems**

Appendix on Water Quality Analysis

September 1986

19961018 081

DTIC QUALITY INSPECTED 3

# DISCLAIMER NOTICE



**THIS DOCUMENT IS BEST  
QUALITY AVAILABLE. THE  
COPY FURNISHED TO DTIC  
CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO  
NOT REPRODUCE LEGIBLY.**

REPORT DOCUMENTATION PAGE				Form Approved OMB No. 0704-0188	
1a. REPORT SECURITY CLASSIFICATION <b>UNCLASSIFIED</b>			1b. RESTRICTIVE MARKINGS		
2a. SECURITY CLASSIFICATION AUTHORITY			3. DISTRIBUTION / AVAILABILITY OF REPORT <b>DISTRIBUTION IS UNLIMITED.</b>		
2b. DECLASSIFICATION / DOWNGRADING SCHEDULE					
4. PERFORMING ORGANIZATION REPORT NUMBER(S) <b>COMPUTER PROGRAM DOCUMENT NO. 5Q (CPD-5Q)</b>			5. MONITORING ORGANIZATION REPORT NUMBER(S)		
6a. NAME OF PERFORMING ORGANIZATION <b>USA CORPS OF ENGINEERS WATER RESOURCES SUPPORT CENTER HYDROLOGIC ENGINEERING CENTER</b>		6b. OFFICE SYMBOL (if applicable) <b>CEWRC-HEC</b>	7a. NAME OF MONITORING ORGANIZATION <b>USA CORPS OF ENGINEERS WATER RESOURCES SUPPORT CENTER</b>		
6c. ADDRESS (City, State, and ZIP Code) <b>609 SECOND STREET DAVIS, CA 95616</b>		7b. ADDRESS (City, State, and ZIP Code) <b>7701 TELEGRAPH ROAD ALEXANDRIA, VA 22310-3868</b>			
8a. NAME OF FUNDING / SPONSORING ORGANIZATION		8b. OFFICE SYMBOL (if applicable)	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER		
8c. ADDRESS (City, State, and ZIP Code)		10. SOURCE OF FUNDING NUMBERS			
		PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.	WORK UNIT ACCESSION NO.
11. TITLE (Include Security Classification) <b>HEC-5. Simulation of Flood Control and Conservation Systems, Appendix on Water Quality Analysis</b>					
12. PERSONAL AUTHOR(S)					
13a. TYPE OF REPORT <b>Computer Program Document</b>		13b. TIME COVERED FROM _____ TO _____		14. DATE OF REPORT (Year, Month, Day) <b>1986 September</b>	
15. PAGE COUNT <b>347</b>					
16. SUPPLEMENTARY NOTATION <b>Approved for Public Release.</b>					
17. COSATI CODES			18. SUBJECT TERMS (Continue on reverse if necessary and identify by block number) <b>environmental impacts, hydrology, management, planning, reservoir operation, reservoirs, rivers, streams, temperature, oxygenation, water quality, water resources.</b>		
FIELD	GROUP	SUB-GROUP			
19. ABSTRACT (Continue on reverse if necessary and identify by block number)  This program simulates the sequential operation of reservoir systems for flood control and conservation purposes. Water quality analysis includes water temperature, three conservative and three non-conservative constituents, dissolved oxygen and a phytoplankton option. The flows to be released are determined by the program to meet at-site and downstream control point requirements. Twenty reservoirs, forty control points and any length of study period can be simulated on hourly, daily, or monthly intervals.  Reservoir inflow and quality are routed through the reservoir and the minimum allowable discharge for all downstream needs is computed. The discharge and all intervening local inflow are routed to all control points downstream of the reservoir. The thermal simulation of the reservoir and river system uses the equilibrium temperature approach. Violations of control point water quality requirements are minimized by mixing reservoir discharges from the different vertical levels allowed at the intake structure. This program is a direct expansion, in subroutine form, of the water quantity portion of computer program HEC-5.					
20. DISTRIBUTION / AVAILABILITY OF ABSTRACT <input checked="" type="checkbox"/> UNCLASSIFIED/UNLIMITED <input type="checkbox"/> SAME AS RPT. <input type="checkbox"/> DTIC USERS			21. ABSTRACT SECURITY CLASSIFICATION <b>UNCLASSIFIED</b>		
22a. NAME OF RESPONSIBLE INDIVIDUAL <b>DARRYL W. DAVIS</b>			22b. TELEPHONE (Include Area Code) <b>(916) 756-1104</b>		22c. OFFICE SYMBOL <b>CEWRC-HEC</b>

## FOREWORD

The model described in this appendix is the result of a four year project to expand the capability of the "Simulation of Flood Control and Conservation Systems" model, HEC-5, to include water quality analysis.

This document and the associated computer program are the final products of this project. The model will regulate a ten-reservoir system for water quality control, in addition to the HEC-5 objectives of conservation and flood control regulation. The model has the capability to satisfy control point objectives for temperature, three conservative constituents, three non-conservative constituents and dissolved oxygen for combinations of either tandem or parallel impoundments.

Funding for this model was provided by the Environmental and Water Quality Operational Studies (EWQOS) program, sponsored by the Office, Chief of Engineers, and managed by the U. S. Army Corps of Engineers Waterways Experiment Station, Vicksburg, Mississippi. The model has been developed by contract under the project administration of Mr. R.G. Willey.

This appendix is a supplement to the April 1982, HEC-5 Users Manual (and Exhibit 8 from March 1985), and any references to HEC-5, within the document, refer to the program for quantity regulation. Information regarding error corrections can be given to or obtained from the Hydrologic Engineering Center by contacting Mr. R.G. Willey at (916) 551-1748.



HEC-5  
SIMULATION OF FLOOD CONTROL AND CONSERVATION SYSTEMS

APPENDIX ON WATER QUALITY ANALYSIS  
TABLE OF CONTENTS

<u>PARAGRAPH</u>	<u>PAGE</u>
1 INTRODUCTION	
1.1 ORIGIN OF PROGRAM	1
1.2 PURPOSE OF PROGRAM	1
1.3 HARDWARE AND SOFTWARE REQUIREMENTS	2
2 WATER QUALITY SIMULATION MODULE CONCEPTS	
2.1 GENERAL CAPABILITIES AND LIMITATIONS	3
2.2 RESERVOIR HYDRAULICS	4
2.2.1 WES WITHDRAWAL ALLOCATION METHOD	6
2.2.2 ALLOCATION OF INFLOW	9
2.2.3 VERTICAL ADVECTION	10
2.2.4 EFFECTIVE DIFFUSION	10
2.3 STREAM HYDRAULICS	14
2.4 THERMAL ANALYSIS	13
2.5 WATER QUALITY ANALYSIS	18
2.5.1 PHYSICAL AND CHEMICAL CONSTITUENTS	18
2.5.2 PHYTOPLANKTON ANALYSIS	19
2.6 SOLUTION TECHNIQUES	20
2.6.1 RESERVOIR	20
2.6.2 STREAM	25
2.6.3 GATE SELECTION	31
2.6.4 FLOW ALTERATION ROUTINE	36
3 INPUT STRUCTURE	
3.1 ORGANIZATION OF INPUT	38
3.2 TYPE OF INPUT RECORDS	38
4 OUTPUT	39
REFERENCES	42
EXHIBITS	
1 TEST PROBLEMS	
2 DESCRIPTION OF PROGRAM INPUT	
3 JULIAN CALENDAR	
4 PROGRAM WEATHER USERS MANUAL	
5 THERMAL SIMULATION OF LAKES USERS MANUAL	
6 GEDA PROGRAM DESCRIPTION	

HEC-5  
SIMULATION OF FLOOD CONTROL AND CONSERVATION SYSTEMS

APPENDIX ON WATER QUALITY ANALYSIS  
TABLE OF CONTENTS  
Continued

<u>FIGURES</u>	<u>PAGE</u>
1 GEOMETRIC REPRESENTATION OF A STRATIFIED RESERVOIR AND MASS TRANSPORT MECHANISMS	5
2 DEFINITION SKETCH OF VARIABLES FOR ORIFICE FLOW	7
3 LOG OF EFFECTIVE DIFFUSION VERSUS LOG OF DENSITY GRADIENT	11
4 EFFECTIVE DIFFUSION COEFFICIENTS VS. DEPTH FOR STABILITY METHOD	13
5 DIFFUSION COEFFICIENT VS. DEPTH FOR WIND METHOD	13
6 GEOMETRIC REPRESENTATION OF STREAM SYSTEM AND MASS TRANSPORT MECHANISMS	15
7 RATE COEFFICIENT TEMPERATURE ADJUSTMENT FUNCTION	21
8 PHYSICAL MASS TRANSFERS BETWEEN ELEMENTS	22
9 STRUCTURE OF $ A $ MATRIX FOR TWO TANDEM RESERVOIR, FOUR CONTROL POINT SYSTEM WITH $m$ VOLUME ELEMENTS	29
10 RELATIONSHIP BETWEEN THE DEVIATION FROM THE RELEASE TARGET QUALITY AND THE SUBOPTIMIZATION FUNCTION FOR THE COEFFICIENTS PRESENTED IN TABLE 2	35

## HEC-5

### SIMULATION OF FLOOD CONTROL AND CONSERVATION SYSTEMS

#### APPENDIX ON WATER QUALITY ANALYSIS

##### 1. INTRODUCTION

###### 1.1 Origin of Program

The flow simulation capability of this program (i.e., flow simulation module or HEC-5) was developed at The Hydrologic Engineering Center (HEC) by Mr. Bill S. Eichert. The initial version was written for flood control operation of a single flood event and was released as HEC-5, "Reservoir System Operation for Flood Control," in May 1973. The flow simulation module was then expanded to include operation for conservation purposes and for period-of-record routings. This revised program was referred to as HEC-5C up to the February 1978 version. Further revisions to the flow simulation module were made and the revised program was referred to as the June 1979 version of HEC-5 [HEC 1979].

In March 1979, the HEC contracted with Resource Management Associates, Inc. to add to the HEC-5 program the capability of simulating temperature in a single reservoir (i.e., temperature simulation module or HEC-5Q).

In November 1979, the HEC contracted with Dr. James H. Duke, Jr. to add the capability to simulate conservative and non-conservative constituents, including dissolved oxygen, in a two-reservoir system and its associated downstream river reaches. These modifications were added to the temperature simulation module and the module was structured to interact with the HEC-5 program to change flow releases if such a change would improve water quality in the downstream reaches.

In February 1982, the HEC contracted with Resource Management Associates, Inc. (RMA) and Dr. James H. Duke, Jr., to extend the November 1979 version of the model to ten reservoirs of an arbitrary tandem and parallel configuration and to perform additional modifications. The capabilities of the total model, that have resulted from all of these modifications, are documented herein.

###### 1.2 Purpose of Program

The flow simulation module was developed to assist in planning studies for evaluating proposed reservoirs in a system and to assist in sizing the flood control and conservation storage requirements for each project recommended for the system. The program can also be useful for selecting proper reservoir operational releases for hydropower, water supply, and flood control.

The water quality simulation module was developed so that temperature and selected conservative and non-conservative constituents, including dissolved oxygen, could be readily included as a consideration in planning studies. The water quality simulation module accepts system flows generated by the flow simulation module and computes the vertical distribution of temperature and other constituents in the reservoirs and the water quality in the associated downstream reaches.

The water quality simulation module also selects the gate openings for reservoir selective withdrawal structures to meet user-specified water quality objectives at downstream control points. If the objectives cannot be satisfied, the model will compute the increase in flow (if any) necessary to satisfy the downstream objective.

With these capabilities, the planner may evaluate the effects on water quality of proposed reservoir-stream system modifications and determine how a reservoir intake structure should be operated to achieve desired water quality objectives within the system.

The water quality simulation module will operate in any of three modes: a calibration mode, an annual simulation mode and a long-term mode. In the calibration mode, historical flow, water quality and reservoir operations are furnished so that simulations can be made to determine the necessary values of module parameters such as decay rates and dispersion coefficients.

In the annual simulation mode, the model is executed on a daily basis to determine the effects of reservoir operations on reservoir water quality and the water quality in the associated downstream reaches. The long-term simulation mode provides simulations similar to the annual simulation mode except that the time steps are longer, generally thirty days, so that the effects of reservoir operations on water quality can be examined over a long planning horizon of ten years or more.

### 1.3 Hardware and Software Requirements

The program, now written in FORTRAN77, was developed on the CDC Cyber 205, PRIME 550 and HARRIS 500 computer systems. The storage requirements are 68,387K words of memory on 64 bit computers (i.e., CDC) and 1000K words of memory on 24 bit computers (i.e., HARRIS). A current version of the program is maintained for Corps use on the CDC and HARRIS computer systems.

The water quality simulation module is an integral part of the flow simulation module and is not designed to be run independently of the flow module. Twelve data and scratch files are required for water quality simulation module operation, in addition to the files required for the flow simulation module. A total of 31 data and scratch files are required for operation of both the flow and water quality modules.

## 2. WATER QUALITY SIMULATION MODULE CONCEPTS

### 2.1 General Capabilities and Limitations

The water quality simulation module is currently limited to a system containing no more than ten reservoirs which may be in either tandem or parallel configuration. The most upstream point, or points, of any system must be defined by reservoirs. The total stream reservoir system may contain a total of thirty control points. These control points may be placed at any desirable location provided that the following guidelines are followed:

- a. The most downstream point in the system must be defined by a control point.
- b. The confluence of the two streams, on which parallel reservoirs are located, must be defined by a control point.
- c. The end of the stream reach above tandem reservoirs must be defined by a control point.

The quality simulation may be performed on only a portion of the total system simulated by the flow simulation module; however, the quality simulation portion must begin at the upstream limits of the total system and cannot be fragmented.

The water quality simulation module uses flow data from the flow simulation module and the specification of these data must match the mode in which the water quality simulation module is operating. For the calibration and annual simulation modes, flow data must be furnished at intervals of one day and simulations are limited to periods contained in one calendar year. For the long term mode, flow data must be furnished at longer intervals (generally 30 days) and the period of simulation is unlimited.

Reservoir dimension limitations include the following:

- (1) 50 volume elements<sup>1</sup> per reservoir
- (2) One flood control outlet
- (3) One uncontrolled spillway
- (4) A selective withdrawal system composed of two wet wells containing up to eight ports each

---

<sup>1</sup>The number of volume elements is controlled by the total depth and the element thickness in the reservoir.

Stream dimension limitations include the following:

- (1) 300 volume elements<sup>1</sup>
- (2) 3 locations between adjacent control points for allocating local flows

Water quality capabilities include two alternative simulation options. With option number one, the variable constituents include:

- (1) Water temperature which must always be simulated
- (2) Up to 3 conservative constituents
- (3) Up to 3 non-conservative constituents may be simulated with the following restrictions:
  - (a) A maximum of two oxygen consuming constituents may be simulated
  - (b) Only one non-conservative constituent not connected with the dissolved oxygen cycle may be simulated
- (4) Dissolved oxygen may be simulated within the following restriction:

At least one oxygen consuming constituent must be simulated as a non-conservative constituent

The second water quality option, referred to as the phytoplankton option, requires the following eight constituents.

- (1) Water temperature
- (2) Total dissolved solids
- (3) Nitrate nitrogen
- (4) Phosphate phosphorus
- (5) Phytoplankton
- (6) Carbonaceous BOD
- (7) Ammonia nitrogen
- (8) Dissolved oxygen

None of these constituents may be omitted. The phytoplankton option is designed to provide a more realistic representation of the lake environment and the forces affecting dissolved oxygen.

## 2.2 Reservoir Hydraulics


The reservoirs are represented conceptually by a series of one-dimensional horizontal slices such as those shown in Figure 1. Each horizontal slice or layered volume element is characterized by an area, thickness and volume. In the aggregate the assemblage of layered volume elements is a geometric representation, in discretized form, of the prototype reservoir. This one-dimensional representation has been shown to adequately represent water quality conditions in many reservoirs by Eiker [Corps 1974], Baca [1977], and WRE [1968, 1969a, 1969b].

---

<sup>1</sup>The number of volume elements is controlled by the total stream length and the element length in the stream.

FIGURE 1

Geometric Representation of a Stratified Reservoir and  
Mass Transport Mechanisms



Within each element, the water is assumed to be fully mixed. This implies that only the vertical dimension is retained during the computation. Each horizontal layer is assumed to be completely homogeneous with all isopleths parallel to the water surface both laterally and longitudinally. External inflows and withdrawals occur as sources or sinks within each layer are instantaneously dispersed and homogeneously mixed throughout each element from the headwaters of the impoundment to the dam. It is not possible, therefore, to look at longitudinal variations in water quality constituents in a reservoir. Module results are most representative of conditions in the main reservoir body.

Vertical advection is governed by the location of inflow to, and outflow from, the reservoir. Thus the computation of the zones of distribution and withdrawal for inflows and outflows are of considerable significance in operation of the model. The WES withdrawal method is used for determining the allocation of outflow. The Debler inflow allocation method is used for the placement of inflows. These methods are described in the following sections.

### 2.2.1 WES Withdrawal Allocation Method

The outflow component of the model incorporates the selective withdrawal techniques developed by Bohan [1973]. Laboratory investigations were conducted to determine the withdrawal zone characteristics created in a randomly density-stratified impoundment by releasing flow through a submerged orifice. From these investigations generalized relationships were developed for describing the vertical limits of the withdrawal zone and the vertical velocity distribution within the zone.

A definition sketch of variables for orifice flow is shown in Figure 2. The following transcendental equation defines the zero velocity limits of the withdrawal zone.

$$V_o = \frac{Z^2}{A_o} \sqrt{\left( \frac{\Delta \rho'}{\rho_o} \right) g Z} \quad (1)$$

where:

- $V_o$  = average velocity through the orifice in m/sec
- $Z$  = vertical distance from the elevation of the orifice center line to the upper or lower limit of the zone of withdrawal in meters
- $A_o$  = area of the orifice opening in  $m^2$
- $\Delta \rho'$  = density of fluid between the elevations of the orifice center line and the upper or lower limit of the zone of withdrawal in  $kg/m^3$ \*
- $\rho_o$  = fluid density of the elevation of the orifice center line in  $kg/m^3$
- $g$  = acceleration due to gravity in  $m/sec^2$

---

\*All water densities in the water quality simulation module are computed solely as a function of water temperature.



### Definition Sketch of Variables for Orifice Flow



With knowledge of the withdrawal limits, the velocity profile due to outflow can be determined. First, the location of the maximum velocity is determined by:

$$\frac{Y_1}{H} = [\sin (1.57 \frac{Z_1}{H})]^2 \quad (2)$$

where:

- $Y_1$  = vertical distance from the elevation of the maximum velocity  $V$  to the lower limit of the zone of withdrawal in meters
- $H$  = thickness of the withdrawal zone in meters
- $Z_1$  = vertical distance from the elevation of the orifice center line to the lower limit of the zone of withdrawal in meters

The distribution of velocities within the withdrawal zone is then determined by:

$$\frac{v}{V} = (1 - \frac{y\Delta\rho}{Y\Delta\rho_m})^2 \quad (3)$$

where:

- $v$  = local normalized velocity in the zone of withdrawal at a distance  $y$  from the elevation of the maximum velocity  $V$
- $V$  = maximum velocity in the zone of withdrawal in m/sec
- $y$  = vertical distance from the elevation of the maximum velocity  $V$  to that of the corresponding local velocity  $v$  in meters
- $Y$  = vertical distance from the elevation of the maximum velocity  $V$  to the limit of the zone of withdrawal in meters
- $\Delta\rho$  = density difference of fluid between the elevation of the maximum velocity  $V$  and the corresponding local velocity  $V$  in  $\text{kg/m}^3$
- $\Delta\rho_m$  = density difference of fluid between the elevation of the maximum velocity  $V$  and the limit of the zone of withdrawal in  $\text{kg/m}^3$

This equation can be used to describe both the upper and lower sections of a velocity distribution using the elevation of the maximum velocity  $V$  as the reference elevation, except for conditions in which the withdrawal zone is limited by either the free surface or the bottom boundary. For conditions where the free surface and bottom boundary limit the withdrawal zone, the velocity distribution is computed by:

$$\frac{v}{V} = 1 - (\frac{y\Delta\rho}{Y\Delta\rho_m})^2 \quad (4)$$

For a situation in which only one limit (upper or lower) is affected by a boundary (free surface or bottom boundary), equation (3) can be used to determine the velocity distribution from the elevation of maximum velocity  $V$  to the limit unaffected by a boundary, and equation (4) can be used to determine the velocity distribution from the elevation of maximum velocity  $V$  to the limit affected by a boundary. The flow from each layer is then the product of the velocity in the layer, the width of the layer and the thickness of the layer. A flow-weighted average is applied to water quality profiles to determine the value of the release content of each constituent for each time step.

### 2.2.2 Allocation of Inflow

The allocation of inflows is based on the assumption that the inflow water will seek a level of like density within the lake. If the inflow water density is outside the range of densities found within the lake, the inflow is deposited at either the surface or the bottom depending on whether the inflow water density is less than the minimum or greater than the maximum water density found within the lake.

Once the entry level is established, the inflow water is allocated to the individual elements by one of two methods. If the inflow enters a zone of convective mixing, the inflow is distributed uniformly throughout the convectively mixed zone. If the inflow enters a stratified region of the lake, the inflow is distributed uniformly within a flow field, the thickness of which is determined by Debler's criteria [1959].

The thickness of the flow field is determined by:

$$D = 2.88 \left( \frac{Q}{W} \times \frac{\rho}{g\beta} \right)^{1/2} \quad (5)$$

where:

- $D$  = thickness of the flow field in meters
- $Q$  = inflow rate in  $\text{m}^3/\text{sec}$
- $W$  = effective width\* of reservoir at the inflow level in meters
- $\beta$  = density gradient at the withdrawal location in  $\text{kg}/\text{m}^4$
- $g$  = acceleration due to gravity in  $\text{m}/\text{sec}^2$
- $\rho$  = water density at the outlet location in  $\text{kg}/\text{m}^3$

Once the thickness of the flow field is established, the water is deposited to the elements about the entry level assuming a uniform velocity distribution.

---

\*The effective width of the flow field is defined as the reservoir area at the entry level divided by the effective reservoir length at the inflow location.

### 2.2.3 Vertical Advection

Vertical advection is the net interelement flow and is one of two transport mechanisms used in the module to transport water quality constituents between elements. The vertical advection is defined as the interelement flows which result in a continuity of flow in all elements. Beginning with the lowermost element, the vertical advection is calculated by algebraically summing the inflows and outflows. Any flow imbalance is accounted for by vertical advection into or out of the element above. This process is repeated for all remaining elements taking into account the vertical advection from or to the element below. Any resulting flow imbalance in the surface element is accounted for by an increase or decrease in the lake volume.

### 2.2.4 Effective Diffusion

Effective diffusion is the other transport mechanism used in the module to transport water quality constituents between elements. The effective diffusion is composed of molecular and turbulent diffusion and convective mixing.

Wind- and flow-induced turbulent diffusion and convective mixing are the dominant components of effective diffusion in the epilimnion of most reservoirs. In quiescent, well-stratified reservoirs, molecular diffusion may be a significant component in the metalimnion and hypolimnion. For deep, well-stratified reservoirs with significant inflows to or withdrawals from the hypolimnion, flow-induced turbulence in the hypolimnion dominates. For weakly stratified reservoirs, wind-induced or wind- and flow-induced turbulent diffusion will be the dominant component of the effective diffusion throughout the reservoir.

One of two methods may be selected by the user to calculate effective diffusion coefficients: the stability method or the wind method.

- (1) Stability Method - The stability method of computing the effective diffusion coefficients is appropriate for most deep, well stratified reservoirs and shallower reservoirs where wind mixing is not the dominant turbulent mixing force. This method is based on the assumption that mixing will be at a minimum when the density gradient or water column stability is at a maximum.


The relationship between stability and the effective diffusion is shown graphically in Figure 3. This figure shows the range of effective diffusion coefficients reported by WRE [1969b] and were deduced from data collected in reservoirs of the Pacific Northwest. Effective diffusion coefficients for reservoirs in other regions may fall below the lower envelope of values shown on Figure 3. The relationship between effective diffusion and stability is shown below.

$$D_c = A_1 \quad \text{when } E \leq E_{\text{crit}} \quad (6)$$

$$D_c = A_2 E^{A_3} \quad \text{when } E > E_{\text{crit}} \quad (7)$$

FIGURE 3

Log of Effective Diffusion Versus Log of Density Gradient



where:

$D_c$  = effective diffusion coefficient in  $m^2/sec$   
 $A_1$  = maximum effective diffusion coefficient in  $m^2/sec$

$$E = \frac{1}{\rho} \times \frac{\partial \rho}{\partial z}$$

$E$  = water column stability or normalized density gradient in 1/meter

$E_{crit}$  = water column critical stability in 1/meter

$A_2, A_3$  = empirical constants

A typical density profile for a stratified reservoir and the resulting effective diffusion coefficient distribution are shown in Figure 4.

- (2) Wind Method - The wind method for computing effective diffusion coefficients is appropriate for reservoirs in which wind mixing appears to be the dominant component of turbulent diffusion. This method assumes that wind-induced mixing is greater at the surface and diminishes exponentially with depth. The following empirical expression which is a combination of wind-induced diffusion and a minimum diffusion term representing the combined effects of all other mixing phenomena is used to calculate the effective diffusion coefficient:

$$D_c = D_{min} + A_1 V_w e^{-kd} \quad (8)$$

where:

$D_{min}$  = minimum effective diffusion coefficient in  $m^2/sec$   
 $A_1$  = empirical coefficient in meters  
 $V_w$  = wind speed in m/sec  
 $k$  =  $A_2/d_t$   
 $A_2$  = empirical coefficient  
 $d_t$  = depth of the thermocline in meters or six meters during unstratified conditions  
 $d$  = depth of specific layer in meters

Typical values reported by Baca [1977] for the minimum effective diffusion coefficient and the empirical coefficients required by equation (8) are presented in Table 1. Within the model the actual diffusion coefficient,  $D_c$ , is constrained by a maximum  $D_{max}$ , which is usually about  $5 \times 10^{-4}$ . The shape of the diffusion coefficient as a function of depth is shown in Figure 5 for two different cases.

FIGURE 4

Effective Diffusion Coefficients vs. Depth for Stability Method




FIGURE 5

Diffusion Coefficient vs. Depth for Wind Method




TABLE 1

Minimum Effective Diffusion Coefficient and  
Empirical Coefficient for Wind Mixing Method

<u>Coefficient</u>	<u>Well-Mixed Reservoirs</u>	<u>Stratified Reservoirs</u>
Minimum Effective Diffusion Coeff ( $D_{\min}$ )	$1 \times 10^{-5}$ to $5 \times 10^{-5}$	$1 \times 10^{-6}$ to $1 \times 10^{-7}$
Empirical Coeff ( $A_1$ )	$1 \times 10^{-4}$ to $2 \times 10^{-4}$	$1 \times 10^{-5}$ to $5 \times 10^{-5}$
Empirical Coeff ( $A_2$ )	4.6	4.6

### 2.3 Stream Hydraulics

The stream system is represented conceptually as a linear network of segments or volume elements. Each element is characterized by length, width, cross section area, hydraulic radius, Manning's  $n$  and the relationship between flow and depth (see Figure 6).

Flow rates at stream control points are calculated within the flow simulation module by using one of the hydrologic routing methods. Within the flow simulation module, incremental local flows (i.e., inflow between adjacent control points) are assumed to be deposited at the control point. Within the water quality simulation module, the incremental local flow may be divided into components and placed at different locations within the stream reach (i.e., that portion of the stream bounded by the two control points). A flow balance is used to determine the flow rate at element boundaries. Any flow imbalance (i.e., flow at upstream control point plus the increment local flow not equal to the flow at the downstream control point) is distributed uniformly to the flows at each element boundary. Once interelement flows are established, the depth, surface width and cross section area are computed at each element boundary (assuming normal flow).

All additional stream hydraulic data required to represent the mass transfers needed to simulate stream water quality can be calculated using these three relationships and the input channel geometry.


### 2.4 Thermal Analysis

Both the streams and reservoirs are represented by an assemblage of fluid elements linked together by interelement flow and diffusion (stream diffusion is assumed near zero). The interelement mass transports and the fundamental principle of conservation of heat can be represented by the following differential equation model for the dynamics of temperature within each fluid element.



FIGURE 6

Geometric Representation of Stream System and  
Mass Transport Mechanisms



$$V \frac{\partial T}{\partial t} = \Delta z \cdot Q_z \frac{\partial T}{\partial t} + \Delta z \cdot A_z \cdot D_z \frac{\partial^2 T}{\partial z^2} + Q_i \cdot T_i - Q_o \cdot T \frac{A_h H}{\rho \cdot c} - T \frac{\partial V}{\partial t} \quad (9)$$

where:

- T = temperature in degrees Celsius
- V = volume of the fluid element in m<sup>3</sup>
- t = time in seconds
- z = space coordinate in meters (vertical for the reservoir and horizontal for the stream)
- Q<sub>z</sub> = interelement flow in m<sup>3</sup>/sec
- A<sub>z</sub> = element surface area normal to the direction of flow in m<sup>2</sup>
- D<sub>z</sub> = effective diffusion coefficient in m<sup>2</sup>/sec
- Q<sub>i</sub> = lateral inflow in m<sup>3</sup>/sec
- T<sub>i</sub> = inflow water temperature in degrees Celsius
- Q<sub>o</sub> = lateral outflow in m<sup>3</sup>/sec
- A<sub>h</sub> = element surface area in m<sup>2</sup>
- H = external heat sources and sinks in kcal/m<sup>2</sup>/sec
- ρ = water density in kg/m<sup>3</sup>
- c = specific heat of water in kcal/kg/°C

This equation represents the dynamics of heat within the fluid element. The set of equations for all elements within the reservoir or stream system represents the dynamics of heat within that system. All of the terms on the right side of equation (9) represent physical heat transfers including the external heat sources and sinks.

The external heat sources and sinks that are considered in the module are assumed to occur at the air-water interface. The rate of heat transfer per unit of surface area can be expressed as the sum of the following heat exchange components:

$$H_n = H_s - H_{sr} + H_a - H_{ar} \pm H_c - H_{br} - H_e \quad (10)$$

where:

- H<sub>n</sub> = the net heat transfer
- H<sub>s</sub> = the short wave solar radiation arriving at the water surface
- H<sub>sr</sub> = the reflected short wave radiation
- H<sub>a</sub> = the long wave atmospheric radiation
- H<sub>ar</sub> = the reflected long wave radiation
- H<sub>c</sub> = the heat transfer due to conduction
- H<sub>br</sub> = the back radiation from the water surface
- H<sub>e</sub> = the heat loss due to evaporation

All units are in kcal/m<sup>2</sup>/sec

Complete discussions of the individual terms have been presented by Anderson [1954] and by the Tennessee Valley Authority [1972].

The method used in the module to evaluate the net rate of heat transfer at the air-water interface has been developed by Edinger and Geyer [1965]. Their method utilizes the concepts of equilibrium temperature and coefficient of surface heat exchange. The equilibrium temperature is defined as the water temperature at which the net rate of heat exchange between a water surface and the atmosphere is zero. The coefficient of surface heat exchange is the rate at which the heat transfer process proceeds. The equation describing this relationship is:

$$H_n = K_e (T_e - T_s) \quad (11)$$

where:

$H_n$  = net rate of heat transfer in kcal/m<sup>2</sup>/sec  
 $K_e$  = coefficient of surface heat exchange in kcal/m<sup>2</sup>/sec/°C  
 $T_e$  = equilibrium temperature in degrees Celsius  
 $T_s$  = surface temperature in degrees Celsius

A Heat Exchange Program which computes these terms is available at the HEC [Corps 1974].

All heat transfer mechanisms, except short wave solar radiation, apply at the water surface. Short wave radiation penetrates the water surface and may affect water temperatures several meters below the surface. The depth of penetration is a function of adsorption and scattering properties of the water [Hutchinson 1957]. This phenomenon is unimportant in the stream routines since elements are assumed vertically mixed.

In the reservoir routines, however, the short wave solar radiation may penetrate several elements. The amount of heat which reaches each element is determined by:

$$I = (1 - \beta) I_0 e^{-kz} \quad (12)$$

where:

$I$  = light energy at any depth in kcal/m<sup>2</sup>/sec  
 $\beta$  = fraction of the radiation absorbed in the top foot of depth  
 $I_0$  = light energy at the water surface in kcal/m<sup>2</sup>/sec  
 $k$  = light extinction coefficient in 1/meter  
 $z$  = depth in meters

Combining equations (11) and (12) for the reservoir surface element, the external heat source and sink term becomes:

$$H = K_e (T_e - T_s) - (1 - \beta) I_0 e^{-k\Delta z} \quad (13)$$

and the external heat source for all remaining reservoir elements becomes:

$$I = I_z (1 - e^{-k\Delta z}) \quad (14)$$

where:

$I_z$  = the light intensity at the top of the element in kcal/m<sup>2</sup>/sec

## 2.5 WATER QUALITY ANALYSIS

### 2.5.1 Physical and Chemical Constituents

Water quality constituents other than temperature are represented by equation (9) with minor modifications:

- a. The definition of the variable T is generalized to represent the concentration of any water quality constituent.
- b. The distributed heat gain/loss term  $\frac{A_h H}{\rho \cdot c}$  is:
  - (1) Eliminated for conservative constituents
  - (2) Replaced by a first order kinetic decay formulation,  $-K_1 T$ , for non-conservative constituents where  $K_1$  is the decay rate in 1/day.
  - (3) Replaced by a first order reaeration term,  $A_s \cdot K_2 (DO^* - DO) - S_O$ , for dissolved oxygen where  $A_s$  is the element surface area,  $K_2$  is the reaeration rate,  $DO^*$  is the dissolved oxygen saturation concentration at the ambient temperature,  $DO$  is the existing dissolved oxygen concentration, and  $S_O$  is the benthic uptake rate.

The reservoir reaeration rate is computed as follows:

$$K_2 = (a + bW^2) / \Delta z \quad (15)$$

where:

- $K_2$  = reaeration rate in 1/day at 20°C  
 $a, b$  = empirical coefficients derived by curve fit from Kanwisher [1963] to be 0.50 and 0.025, respectively.  
 $W$  = wind speed in meters per second  
 $\Delta z$  = surface element thickness in meters

The stream reaeration rate is computed using the O'Connor-Dobbins [1958] method:

$$K_2 = \frac{(D_m U)^{0.5}}{D^{1.5}} \quad (16)$$

where:

- $K_2$  = reaeration rate in 1/day at 20°C  
 $D_m$  = molecular diffusion coefficient in  $\text{meters}^2/\text{day}$   
 $U$  = flow velocity in  $\text{meters}/\text{second}$   
 $D$  = average stream depth in meters

The rates at which chemical and biological processes take place are normally a function of temperature. To account for this temperature dependence, all first order kinetic rates are adjusted for local ambient temperatures using a multiplicative correction factor:

$$\theta = T_c^{(T-20)} \quad (17)$$

where:

$\theta$  = reaeration rate multiplicative correction factor  
 $T_c$  = empirically determined temperature correction factor  
 $T$  = local ambient water temperature in °C

## 2.5.2 Phytoplankton Analysis

When the phytoplankton option is selected, the distributed heat gain/loss term is replaced by:

$$\text{Nitrate Nitrogen} \dots + V \cdot \text{KNH}_3 \cdot \text{NH}_3 - V \cdot \text{KB} \cdot \text{PN} \cdot \text{P} \cdot \text{PG} (1 - \text{FN}) \quad (18)$$

where:

$\text{KNH}_3$  = ammonia decay rate adjusted to ambient temperature  
 $\text{NH}_3$  = ammonia concentration  
 $\text{KB}$  = phytoplankton activity rate at ambient temperature  
 $\text{PN}$  = nitrogen fraction of phytoplankton ( $\text{PN}=0.08$ )  
 $\text{PG}$  = phytoplankton growth rate  
 $\text{P}$  = phytoplankton concentration  
 $\text{FN}$  = ammonia fraction of available nitrogen

$$\text{Phosphate Phosphorous} \dots + V \cdot \text{KB} \cdot \text{PP} \cdot \text{P} (\text{PR} + \text{PM} - \text{PG}) + \text{SP} \quad (19)$$

where:

$\text{PP}$  = phosphorus fraction of phytoplankton ( $\text{PP}=0.012$ )  
 $\text{PR}$  = phytoplankton respiration rate  
 $\text{PM}$  = phytoplankton mortality rate  
 $\text{SP}$  = benthic source rate for phosphorus

$$\text{Phytoplankton} \dots + V \cdot \text{KB} \cdot \text{P} (\text{PG} - \text{PR} - \text{PM}) - \frac{\partial}{\partial z} (\text{P} \cdot \text{A}_z) \cdot \text{PS} \quad (20)$$

where:

$\text{PG}$  = phytoplankton growth rate

$$= P_{\max} \left| \frac{C}{C_2 + C} \right| \min \quad (21)$$

$P_{\max}$  = maximum phytoplankton growth rate  
 $C$  = nutrient concentration or light intensity  
 $C_2$  = half saturation constant for phytoplankton utilizing nutrients or light  
 $\text{PS}$  = phytoplankton settling rate

$$\text{Ammonia Nitrogen} \dots + V \cdot K_B \cdot P_N \cdot P (PR + PM - PG \cdot FN) + SN \quad (22)$$

where:

SN = benthic source rate for ammonia nitrogen

$$\begin{aligned} \text{Dissolved Oxygen} \dots + A_s \cdot K_2 (DO^* - DO) - V \cdot K_L \cdot L - V \cdot K_B \cdot P (PR \cdot O2R + PM \cdot \\ O2R - PG \cdot O2G) - V \cdot K_{NH_3} \cdot NH_3 \cdot O2N - S_O \end{aligned} \quad (23)$$

where:

KL = BOD decay rate at ambient temperature

O2R = ratio between oxygen consumed and phytoplankton respiration and decay  
(O2R = 1.6)

O2G = ratio between oxygen produced and phytoplankton growth (O2G = 1.6)

O2N = ratio between oxygen consumed and ammonia decay (O2N = 4.6)

Computation of the reaeration rate for dissolved oxygen and the first order rate adjustment for the ambient temperature is the same as for the non-phytoplankton option except for the temperature adjustment for phytoplankton growth and respiration. The ambient temperature adjustment factors for phytoplankton growth utilizes the temperature limit approach which assumes that the rate at which a reaction takes place is a function of two exponential expressions similar to those depicted in Figure 7. The temperature tolerances define the functions used to modify the growth and respiration rates. The temperatures T1 and T4 are the lower and upper tolerance limits, respectively, for growth, and T2 and T3 define the optimum range at which the growth is a maximum. The upper range of the optimum temperature T3 and the upper tolerance limit T4 for phytoplankton respiration and mortality processes are assumed outside the range of normal prototype temperatures.

## 2.6 SOLUTION TECHNIQUES

### 2.6.1 Reservoir

A Gaussian reduction scheme is used for solving the differential equations which represent the response of the water quality constituents within the reservoirs. Equation (9) is rewritten in a form where a "forward time and central difference" scheme is used to describe all the derivative processes. For element i adjacent to elements i-1 and i+1 (see Figure 8), the general mass balance equation becomes:

$$\begin{aligned} V_i \left[ \frac{\delta T}{\delta t} \right]_i = T_{i-1} \left\{ \left[ \frac{A_z D_z}{\Delta z} \right]_i + Q_{u_i} \right\} - T_i \left\{ \left[ \frac{A_z D_z}{\Delta z} \right]_i + \left[ \frac{A_z D_z}{\Delta z} \right]_{i+1} + Q_{d_i} + Q_{u_{i+1}} + Q_w + \frac{\delta V}{\delta t} \right\} \\ + T_{i+1} \left\{ \left[ \frac{A_z D_z}{\Delta z} \right]_{i+1} + Q_{d_{i+1}} \right\} + \sum Q_x T_x + \frac{H}{\rho c} \end{aligned} \quad (24)$$

FIGURE 7

RATE COEFFICIENT TEMPERATURE  
ADJUSTMENT FUNCTION





FIGURE 8

Physical Mass Transfers Between Elements





where:

subscripts i, i-1, i+1 denote element numbers

$V$  = volume of the fluid element in  $m^3$   
 $T$  = temperature in degrees Celsius or water quality constituent concentration, milligrams/liter  
 $t$  = computation time step in seconds  
 $A_z$  = element area at the fluid element boundary in  $m^2$   
 $D_z$  = effective diffusion coefficient in  $m^2/sec$   
 $\Delta z$  = element thickness (length is stream) in meters  
 $Q_u$  = upward advective flow (stream flow) between elements in  $m^3/sec$   
 $Q_d$  = downward advective flow between elements in  $m^3/sec$   
 $Q_w$  = rate of flow removal from the element in  $m^3/sec$   
 $Q_x$  = rate of inflow to the element in  $m^3/sec$   
 $T_x$  = inflow water temperature in degrees Celsius or constituent concentration in milligrams/liter  
 $H$  = external sources and sinks of heat in kcal/sec  
 $\rho$  = water density in  $kg/m^3$   
 $c$  = specific heat of water in kcal/kg/°C

Recall that the  $\frac{H}{\rho \cdot c}$  term is replaced by  $-k_1 T$  or  $k_2(0^* - 0)$  for

nonconservative water quality constituents and dissolved oxygen respectively. A finite difference equation of this type is formed for each element and integrated with respect to time. The system of finite difference mass balance equations represents the response of water quality within the entire reservoir, and with the aid of a numerical integration technique, the equations are solved with respect to time.

The heat or mass balance at any element, i, can take the form:

$$v_i \dot{c}_i = c_{i-1} s_{i-1} - c_i s_i + c_{i+1} s_{i+1} + p_i \quad (25)$$

where:

$v_i$  = volume of element i  
 $\dot{c}_i$  = time rate of temperature or water quality constituent concentration in element i  
 $c_i$  = temperature or constituent concentration in element i  
 $s_i$  = the bracketed terms of the mass balance equations (i.e., advection, diffusion and change of volume)  
 $p_i$  = the constant term for each element i (i.e., sources and sinks)

The complete system of mass balance equations for the n elements can be written in the matrix form:

$$[v] \{\dot{c}\} = [s] \{c\} + \{p\} \quad (26)$$

where:

- [v] = an n x n matrix with the element volumes on the diagonal and zeroes elsewhere
- $\{\dot{c}\}$  = a column matrix of the rates of change for temperature or constituent concentrations in each of the n elements
- [s] = an n x n matrix of the coefficients which multiply the temperature or constituent concentrations
- {c} = a column matrix of the temperature or constituent concentrations in each segment
- {p} = a column matrix of the constant terms for each segment

To integrate the basic equation over time, the following numerical approximation for each element is made.

$$c_{t+\Delta t} = c_t + \frac{\Delta t}{2} (\dot{c}_t + \dot{c}_{t+\Delta t}) \quad (27)$$

where:

- $c_t, c_{t+\Delta t}$  = temperature or constituent concentration at the beginning and end of an integration interval, respectively
- $\dot{c}_t, \dot{c}_{t+\Delta t}$  = rate of change of temperature or constituent concentration at the beginning and end of an integration interval, respectively
- $\Delta t$  = the length of an integration interval

At any point in time  $c_t$  and  $\dot{c}_t$  are known, thus the expression becomes:

$$c_{t+\Delta t} = B + \frac{\Delta t}{2} \dot{c}_{t+\Delta t} \quad (28)$$

where:

$$B = c_t + \frac{\Delta t}{2} \dot{c}_t$$

Equation (27) rewritten in matrix form is:

$$\{c\} = \{B\} + \frac{\Delta t}{2} \{\dot{c}\} \quad (29)$$

where:

- {c} = a column matrix of temperatures or constituent concentrations at the end of the time interval
- {B} = a column matrix of the terms defined in Equation (28)
- $\{\dot{c}\}$  = a column matrix of the time rate of change in temperature or constituent concentrations

Substituting Equation (29) into Equation (26):

$$[v] \{c\} = [s] \{B\} + \frac{\Delta t}{2} [s] \{\dot{c}\} + \{p\} \quad (30)$$

or:

$$[s^*] \{\dot{c}\} = \{p^*\} \quad (31)$$

where:

$$[s^*] = [v] - \frac{\Delta t}{2} [s]$$

$$\{p^*\} = [s] \{B\} + \{p\}$$

Equation (31) forms the basis for a solution, as there is only one unknown in the equation (i.e.,  $\{\dot{c}\}$ ). The following recursive scheme can be used for the numerical solution of equation (31).

1. Form the vector  $\{B\}$  from the initial condition or the solution just completed.
2. Form the known hydraulic solution and known boundary conditions; define the conditions which will exist at the end of the interval.
3. With known values of  $[v]$ ,  $[s]$ , and  $\{p\}$ , form  $[s^*]$  and  $\{p^*\}$ .
4. Solve for  $\{\dot{c}\}$  at time  $(t + \Delta t)$ .
5. Compute  $\{c\}$  by substitution in equation (29).

The above recursive scheme is that used in many computer codes and has proven to be very stable.

### 2.6.2 Stream

A linear programming algorithm is used to solve a fully implicit backward difference in space, forward difference in time, and finite difference approximation of equation (24). This approximation has the general form:

$$a_{i,i-1}C_{i-1}^{t+1} + a_{i,i}C_i^{t+1} + a_{i,i+1}C_{i+1}^{t+1} - C_i^t = b_i \quad (32)$$

where the "a" terms are coefficients formed from the area, dispersion coefficients, flows, lengths of the computational elements, and time step for each volume element; the "C" terms are the unknown temperatures and constituent concentrations in each volume element; the "b" terms are constants formed from initial conditions or previously computed conditions, tributary inputs of heat or mass loads and, depending upon the context (see below), the reservoir releases.

Two matrix formats are used in the stream water quality simulation module. The first can be used to solve for temperature and constituent concentrations given all external input. This format is

$$|A|_{\vec{c}} = \vec{b} \quad (33)$$

where  $|A|$  is the matrix of coefficient;  $\vec{c}$  is the vector of unknown temperatures or constituent concentrations; and  $\vec{b}$  is the vector of constants. Expanding the notation yields:

[illegible]

$$\vec{c} = \begin{bmatrix} c_1 \\ c_2 \\ \vdots \\ c_m \end{bmatrix} \qquad \vec{b} = \begin{bmatrix} b_1 \\ b_2 \\ \vdots \\ b_m \end{bmatrix}$$

In this format, the  $\mathbf{A}$  matrix is a tri-diagonal matrix consisting of  $m \times m$  elements, where  $m$  is the number of stream elements. The vectors  $\vec{c}$  and  $\vec{b}$  both consist of  $m$  elements.

The  $|A|$  matrix will not necessarily be tri-diagonal in a given application of the stream water quality simulation module to a particular stream system but the matrix will be symmetrical about the principal diagonal and will always be a square matrix.

This format is used in the water quality simulation module to compute the final results after all reservoir operations have been completed. In effect, the linear programming algorithm is used simply as a matrix solver for a simulation model.

The second, and more complex, matrix format used in the water quality simulation module is for determining the temperature and constituent concentrations that must come from the reservoirs to satisfy all water quality targets in the stream system. In effect then, the second format is used to (1) determine which control point controls the release for each constituent and (2) determine the reservoir release water quality that most closely satisfies the targets at the controlling points.

This decision making capability is achieved by (1) transforming the constituent concentrations at each control point into a specification of the target and the deviation of the concentration above or below the target and (2) making the concentrations in the reservoir releases unknown so that they can be computed.

The transformation used at control points to specify the target is:

$$C_i^{t+1} = C_{oi} + C_{+i}^{t+1} - C_{-i}^{t+1} \quad (35)$$

where:

- $C_i^{t+1}$  = temperature in degrees Celsius or constituent concentration in milligrams/liter
- $C_{oi}$  = target temperature in degrees Celsius or constituent concentration in milligrams/liter
- $C_{+i}^{t+1}$  = deviation of simulated temperature or constituent concentration above the control point target
- $C_{-i}^{t+1}$  = deviation of simulated temperature or constituent concentration below the control point target

This transformation is substituted into equation (32) to yield the following equation which is applied to those volume elements that are located at control points:

$$a_{i,i-1}C_{i-1}^{t+1} + a_{i,i}C_{+i}^{t+1} - a_{i,i}C_{-i}^{t+1} + a_{i,i+1}C_{i+1}^{t+1} - C_i^t = b_i - a_{i,i}C_{oi} \quad (36)$$

where the  $(a_{i,i}C_{oi})$  term has been moved to the right hand side of the equation since it is known. Thus, the  $m \times m$  simulation matrix has now been transposed into a  $m \times n$  rectangular matrix, where  $n = m + \text{NCP}$  and NCP is the number of control points.

Equation (36) is the general form of the equation used for all volume elements in formulating decision making problems. It includes, as variables, the constituent concentrations in the reservoir releases, although the inclusion is not obvious. For those volume elements that are just below reservoirs, the  $C_{i-1}^{t+1}$  concentrations represent the constituent concentrations in the reservoir releases. In the simulation model, where the reservoir release constituent concentrations are known, the  $a_{i,i-1}C_{i-1}^{t+1}$  terms were included in the  $\vec{b}$  vector for those volume elements just below reservoirs. For the decision making model, the  $a_{i,i-1}C_{i-1}^{t+1}$  terms are included as unknowns. Thus the  $m \times n$  simulation matrix has been made even more elongated in variables and  $n$  is now  $m + \text{NCP} + \text{NRES}$ , where NRES is the number of reservoirs in the system.

One additional set of equations is included in the water quality simulation module to ensure that realistic results are obtained in computing reservoir release water quality. These equations are applied to define the range of constituent concentrations that may be released from the reservoirs. Normally the range is defined by two inequalities:

$$C_r^{t+1} \geq C_{\min}^{t+1} \quad (37)$$

$$C_r^{t+1} \leq C_{\max}^{t+1} \quad (38)$$

where:

$C_{\min}^{t+1}$  = minimum temperature or constituent concentration in reservoir water quality profile  
 $C_{\max}^{t+1}$  = maximum temperature or constituent concentration in reservoir water quality profile  
 $C_r^{t+1}$  = final computed temperature or constituent concentration in reservoir release

In practice, these inequalities are written as equalities by adding slack and surplus variables.

$$C_r - X_{\text{surplus}}^{t+1} = C_{\min}^{t+1} \quad (39)$$

$$C_r + X_{\text{slack}}^{t+1} = C_{\max}^{t+1} \quad (40)$$

Although the slack and surplus variables have meaning, in the water quality simulation routine they are added as a computational necessity.

With the problem so formulated, the  $|A|$  matrix of equation (34) consists of  $(m + 2 * \text{NRES})$  rows and  $(m + \text{NCP} + \text{NRES})$  unknowns, and the  $b$  vector consists of  $(m + 2 * \text{NRES})$  constants. The  $|A|$  matrix may be conceptually partitioned as shown in Figure 9, where it is assumed that reservoirs are above volume elements 1 and 3, that these reservoirs are in tandem and that volume elements 1, 3, 7 and  $m$  are control points.

	Stream Water Constituent Concentration Variables*	Variables for Negative Deviations at Control Points	Reservoir Release Variables	Slack and Surplus Variables
Element Numbers	$a_{11}$ $a_{12}$	$-a_{11}$	$a_{0,1}$	
	$a_{21}$ $a_{22}$	$-a_{21}$		
	$a_{33}$ $a_{34}$	$-a_{33}$	$a_{2,3}$	
	$a_{43}$ $a_{44}$ $a_{45}$	$-a_{43}$		
	$\cdot$ $\cdot$ $\cdot$			
	$a_{65}$ $a_{66}$ $a_{67}$	$-a_{67}$		
	$a_{76}$ $a_{77}$ $a_{78}$	$-a_{77}$		
	$a_{87}$ $a_{88}$ $a_{89}$	$-a_{87}$		
	$\cdot$ $\cdot$ $\cdot$	$-a_{m-1,m}$		
	$a_{m-1,m}$ $a_{mm}$	$-a_{m,m}$		
Inequality Statements			$+1$	$-1$
			$+1$	$+1$
			$+1$	$-1$
			$+1$	$+1$

\* Variables 1, 3, 7 and m are expressed as deviations from target concentrations at the respective control points.

FIGURE 9

Structure of  $|A|$  Matrix for Two Tandem Reservoir, Four Control Point System with m Volume Elements

There are a number of solutions that will satisfy a matrix that is not square (i.e.,  $m \times m$ ). The purpose of using a linear programming solution is to select the solution that best satisfies the objectives of the reservoir operation on downstream water quality. However, it is known that one class of solutions will never appear: at no time will the variables that describe the positive and the negative deviations from the control point target constituent concentrations appear simultaneously in the solution. At all times, one or the other deviation will appear, but not both. It is also known that the reservoir release constituent concentrations will always appear in the final solution. Thus, selecting the solution that best satisfies the objectives of the reservoir operation on downstream water quality reduces to selecting which control point deviation variable appears in the final solution and the numerical value attached to that variable. Once this numerical value is known, it is known that the deviation of the opposite sign is zero so that the actual control point constituent concentration can be computed using equation (35).

The objective function is used in a linear programming formulation to quantitatively describe the desirability of any given solution to a formulated problem. In the water quality simulation module, a minimization routine is used which is expressed as:

$$\text{minimize } z = \vec{p} \cdot \vec{c} \quad (41)$$

The actual value of  $z$  is immaterial to the water quality simulation module; it is just an index by which the desirability of the solution is determined. The vector  $\vec{c}$  is the same vector  $\vec{c}$  in equation (33) except that, as previously described, it includes the variables representing:

1. The deviations from the control point targets for those volume elements that represent control points
2. The constituent concentrations in all other volume elements
3. The constituent concentrations in the reservoir releases.

The vector  $\vec{p}$  represents the penalty associated with the appearance of a given variable in the final solution. Logically, the penalties in  $\vec{p}$  are nonzero only at control points and are applied only for the variables that represent deviations from the target.

The water quality simulation module is structured flexibly so that different penalties can be assigned for each control point, for each constituent and for each deviation, above and below. The magnitude of the penalty is unimportant, as long as it is nonzero where necessary and realistically represents the desired policy. For instance, for a temperature target expressed as "the temperature at control point I shall not exceed 20°C, or

$$T_I \leq 20,$$



the penalty for the positive deviation at control point I could be set to 1.0, and the penalty for the negative deviation could be set to 0.0. Obviously, when trying to minimize  $z$ , as shown in equation (41), the linear programming algorithm would try to ensure that the variable representing the negative deviation would appear in the final solution since a lower value of the index  $z$  would result.

If it was twice as important that the target temperature at control point I be maintained than at another control point, say J, then the penalty associated with a positive deviation from the target at I could be set to 2.0, and the penalty associated with a similar positive deviation at J could be set to 1.0. Of course, the penalties associated with negative deviations at both I and J would be set to 0.0.

Similar logic is used for setting penalties for constituents that must always exceed a target value, such as dissolved oxygen. The nonzero penalties are applied to the variables representing negative deviations, and the variables that represent positive deviations are given penalties of 0.

In specifying the penalties for violating control point targets, the relative importance of one unit of measure for the various constituents must be considered. As an example, the importance of a one mg/l violation of a total dissolved solids target value would normally be much less than a one mg/l violation of a dissolved oxygen target; therefore, the penalties for violating dissolved oxygen targets would normally be much greater than those for total dissolved solids.

### 2.6.3 Gate Selection

The port selection algorithm serves to determine which ports should be open and what flow rate should pass through each open port in order to maximize a function of the downstream water quality concentrations. Solution of this problem is accomplished by using mathematical optimization techniques. The objective function is related to meeting downstream target qualities subject to various hydraulic constraints on the individual ports.

Kaplan [1974] solved a similar, although more difficult, problem by including in the constraint set upper and lower bounds on the release concentration of each water quality constituent. Kaplan also considered as part of his objective function the reservoir water quality that resulted from any particular operation strategy. A penalty function approach was used to incorporate the many constraints into the objective function, which could then be solved as an unconstrained nonlinear problem. For the problem of interest with respect to HEC-5Q, with appropriate transformations it is possible to formulate a quadratic objective function with linear constraints. Mathematical optimization techniques are available to exploit the special structure of this problem and to solve it efficiently.

The hydraulic structure under consideration is composed of two wet wells, containing up to eight ports each, and a flood control outlet. It is assumed that releases through any of these ports (including the flood control outlet) leave the reservoir through a common pipe. At any given time, only one port in either wet well and the flood control outlet may be operated. Hence, the algorithm provides flows through three ports at most.

The HEC-5 model also provides for releases through an uncontrolled spillway. These releases are not a part of the gate selection algorithm, but the water quality of the spillway releases are considered by the gate selection algorithm.

The algorithm proceeds by considering a sequence of problems, each representing a different combination of open ports. For each combination, the optimal allocation of total flow to ports is determined. The combination of open ports with the highest water quality index defines the optimal operation strategy for the time period under consideration.

There are four different types of combinations of open ports. For one-port problems all of the flow is taken from a single port, and the water quality index is computed. For two-port problems combinations of one port in each wet well and combinations of each port with the flood gate are considered. For three-port problems combinations of one port in each wet well and the floodgate are considered. The total flow to be released downstream is specified external to the port selection module, but if the flow alteration option is selected, then the flow can be treated as an additional decision variable; and the flow for which the water quality index is maximized is also determined.

For each combination of open ports, a sequence of flow allocation strategies is generated using a gradient method, a gradient projection method, or a Newton projection method as appropriate. The value of any flow allocation strategy is determined by evaluation of a water quality index subject to the hydraulic constraints of the system. The sequence converges to the optimal allocation strategy for the particular combination of open ports.

To evaluate the water quality index for a feasible flow allocation strategy, first the release concentration for every water quality constituent is computed.

$$R_c = \frac{\sum_{p=1}^{N_p} (\Phi_{cp} Q_p)}{\sum_{p=1}^{N_p} Q_p} ; c=1, N_c \quad (42)$$

where:

$R_c$  = release concentration for constituent  $c$   
 $c$  = index for constituents  
 $p$  = index for open ports  
 $N_p$  = number of open ports  
 $\Phi_{cp}$  = concentration of constituent  $c$  at port  $p$   
 $Q_p$  = flow rate through port  $p$   
 $N_c$  = number of constituents under consideration

The deviation of release qualities from downstream target qualities can be computed.

$$D_c = R_c - T_c ; \quad c = 1, N_c \quad (43)$$

where:

$D_c$  = deviation of constituent C

$T_c$  = downstream target quality for constituent C

The subindex  $S_c$  for each constituent can be determined by:

$$S_c = f(D_c); \quad c = 1, N_c \quad (44)$$

Where the function  $f$  takes the form of the sixth order polynomial:

$$f(D_c) = a + bD_c + cD_c^2 + dD_c^3 + eD_c^4 + fD_c^5 \quad (45)$$

In selecting these coefficients, the magnitude and importance of the water quality parameter should be considered. To aid in the coefficient selection process, Table 2, Figure 10 and the following discussion are provided.

TABLE 2. Typical Coefficients in Constituent Suboptimization Function

Curve Number	Coefficient					
	a*	b	c	d	e	f
1	100	0.0	- 0.1	0.0	0.000	0
2	100	0.0	- 2.0	0.0	0.000	0
3	100	0.0	- 10.0	0.0	0.000	0
4	100	- 3.2	- 0.7	- 0.1	- 0.005	0
5	100	3.2	- 0.7	0.1	- 0.005	0

\*a should always equal 100

Curves 1 through 3 are functions where equal weight is given to deviation on either side of the target concentration. Under normal conditions, this type of function should be used.

Curve number 1 would be used for a quality parameter such as TDS since wide variations from the target are normally allowable. For a parameter such as nitrate where the concentration is low, curve number 3 would be appropriate. Curve number 2 might be used for temperature or other parameters where the concentration range is 5 to 25.

Curves number 4 and 5 are functions where deviations about the target are not weighted equally. Curve number 4 could be used for a toxic parameter where the lowest discharge concentration would be desirable, conversely, curve 5 could be used for a parameter where a higher concentration is always desirable. Curve 5 might be appropriate for dissolved oxygen in some applications.

In summary, almost any shape of function can be developed (a curve fit routine will be very helpful) using the sixth order polynomial function. In developing these functions, the importance of the parameter and the normal

anticipated concentration magnitude are the major considerations. Keep in mind that the weighting factor can be set to zero if the quality parameter is unimportant.

Finally, the scalar water quality index can be determined by:

$$Z = \sum_{c=1}^{N_c} W_c S_c \quad (46)$$

where:

$Z$  = water quality index  
 $W_c$  = weighting factor for constituent  $c$   
 $S_c$  = subindex for constituent  $c$  and:

$$\sum_{c=1}^{N_c} W_c = 1 \quad (47)$$

In summary, the problem of determining the optimal allocation of flows to ports for a particular combination of open ports and for a specified total flow rate  $Q$  can be expressed as follows:

$$\begin{array}{cc} \text{MAX} & \\ Q_p & \left( \sum_{c=1}^{N_c} W_c S_c \right) \end{array} \quad (48)$$

Subject to:

$$\sum_{p=1}^{N_p} Q_p = Q$$

$$F_{\min,p} \leq Q_p \leq F_{\max,p} ; p=1, N_p$$

where  $F_{\min}$  and  $F_{\max}$  are the minimum and maximum acceptable flow rates through a port.

When an acceptable flow range  $Q_{\text{lower}}$  to  $Q_{\text{upper}}$  is specified, then the problem is written as:

$$\begin{array}{cc} \text{MAX} & \\ Q_p & \left( \sum_{c=1}^{N_c} W_c S_c \right) \end{array}$$

Subject to:

$$Q_{\text{lower}} \leq \sum_{p=1}^{N_p} Q_p \leq Q_{\text{upper}}$$

$$F_{\min,p} \leq Q_p \leq F_{\max,p} ; p=1, N_p$$





FIGURE 10. Relationship Between the Deivation from the Release Target Quality and the Suboptimization Function for the Coefficients Presented in Table 2

These problems are solved very efficiently by using mathematical optimization techniques that take advantage of the problem structure, namely a quadratic objective function with linear constraints.

#### 2.6.4 Flow Alteration Routine

The flow alteration routine is designed to change the reservoir releases, computed by the flow simulation module, to better satisfy the stream control point water quality objectives. There are two flow alteration routines contained in HEC-5Q. The first is contained in the selective withdrawal algorithm and is described in Section 2.6.3, Gate Selection. Flows are increased in the gate selection algorithm if increasing the flow will result in releases that better meet the reservoir release targets called for by the stream linear programming algorithm.

The second flow alteration routine computes increases in reservoir releases to ensure that control point targets are met insofar as is possible. The routine is designed about a mass balance for all reservoir releases and all control points affected by those releases. Tributary inflows and other flow changes are included. Second order effects, such as reaeration and external heating due to increased or decreased stream surface area, are not included.

The procedure is as follows:

1. The relative mass that needs to be added in the flow at the control point (for those constituents below the target) or reduced in the flow at the control point (for those constituents above the target) is computed using:

$$\Delta M = Q_{cp} (C_o - C_{cp}) \quad (49)$$

where:

$Q_{cp}$  = flow at the control point as determined by the flow simulation module

$C_o$  = target constituent concentration at the control point

$C_{cp}$  = computed constituent concentration at the control point

2. The average reservoir release concentration is computed for all reservoirs for which the constituent concentration in the releases is greater than the target concentration at the control point of interest (for those constituents below the target) or for which the constituent concentration in the releases is less than the target at the control point of interest (for those constituents above the target). Thus:

$$\bar{C}_R = \sum_{i=1}^n Q_{Ri} C_i / \sum_{i=1}^n Q_{Ri} \quad (50)$$

where:

$\bar{C}_R$  = average constituent concentration in reservoir releases for only those reservoirs releasing flow with constituent concentrations adequate to dilute the control point concentration and bring it to the target

$Q_{Ri}$  = flow release from reservoir i

$C_i$  = constituent concentration in release from reservoir i

n = number of reservoirs

The sums are taken only over those reservoirs i that are capable of diluting the control point constituent concentration that is of poorer quality than the target concentration.

3. The total dilution flow requirement is then computed by the following quotient:

$$Q_A = \frac{\Delta M}{\bar{C}_R} \quad (51)$$

where  $Q_A$  is the total flow release needed to bring the constituent concentration at the control point of interest to the target.

4. The flow  $Q_A$  is then apportioned to the reservoirs capable of bringing the control point constituent concentration to the target in proportion to the flows originally computed for those reservoirs by the flow simulation module.

Thus the flow augmentation requirement can be computed for each control point and for each constituent. The various computed flow rates are then combined by using the coefficients of the linear programming objective function and the deviation of the respective constituent concentrations from the target concentrations at each respective control point as follows:

$$Q_k = \frac{1}{\sum_{i=1}^{N_{cp}} \sum_{j=1}^{N_{cc}} P_{ij} (C_{ij} - C_{io})} \sum_{i=1}^{N_{cp}} \sum_{j=1}^{N_{cc}} Q_k \cdot P_{ij} (C_{ij} - C_{io}) \quad (52)$$

where:

$Q_k$  = flow release from reservoir k

$N_{cp}$  = number of control points affected by both reservoirs

$N_{cc}$  = number of constituents

$P_{ij}$  = linear programming objective function coefficient for constituent j at control point i.

$C_{ij}$  = computed concentration of constituent j at control point i

$C_{io}$  = target concentration of constituent i

Once the  $Q_k$  is determined, using equation (51), the flow simulation module is recalled, and the daily computations for flow and water quality are solved again for the final results.

### 3 INPUT STRUCTURE

#### 3.1 Organization of Input

The input structure is designed to be flexible with respect to specifying characteristics of the reservoir system and other inputs to the system. Each input record is described in detail in Exhibit 3. The last two pages of the exhibit are a "Summary of Input Records." The summary shows the order in which the records should be placed.

#### 3.2 Type of Input Records

The various types of records used are identified by two characters in columns 1 and 2. These characters are read by the computer to identify the record. Types of records are as follows:

- a. Title Records - TI. Three title records are required.
- b. Job Control Records - JA. This record is required and specifies length of simulation, number of control points, and water temperature units.
- c. Water Quality Constituent Records - QC. This record identifies which water quality constituents will be modeled. It provides control over the number of records to be read.
- d. Reservoir Records - L1 through CR. These records are used to control the reservoir simulation and describe the characteristics of the reservoir. All records except L5, L6 and L7 are required. Required records define the printout interval (L1 record), miscellaneous physical constants (L2 record), effective reservoir length (LR record), effective diffusion coefficients (L3 and L4 records), effective reservoir width (L8 records), initial reservoir temperature and water quality profiles (L9 - SC records), and various modeling coefficients (K1 - CR records). Optional records (L5, L6 and L7) define the characteristics of the flood control outlet, the uncontrolled spillway and the wet wells. These records are optional to the extent that the reservoir is not required to have all outlet options. Records TQ, C1 - SC, and K1 - CR are optional in that they are not required if only temperature is simulated.
- e. Stream Records - S1 through CT. All stream records are required. These records define printout controls and the amount of channel geometry data (S1 record), reach limits and local inflow locations (S2 cards), reaeration controls (SR and SK records), channel cross section geometry data (S3 records), typical energy grade line elevations (S4 records), nonconservative constituent decay rates (KR records) and water quality objectives (CT records).
- f. Local Inflow Temperature - I1 through I4. Record I1 is required to define the period of the inflow. Each tributary inflow point requires an I2 record plus sets of either I3 or I4 records (but not both) to define water quality over the period of record.



- g. Water Surface Heat Exchange - EZ and ET. One EZ record identifies the station for the ET records which follow. One ET record defining surface heat exchange characteristics is required for each day of simulation.
- h. Optimization Objective Functions and Relative Weights - PL and WT. These records define the shape of the objective function for each constituent (water quality index) and the relative weight between constituents.
- i. Gate Operations - G1 and G2. These records define the operation schedule for the wet wells, flood control outlet and uncontrolled spillway. The values can be actual flows or relative weightings.

#### 4. OUTPUT

Options to control output from the water quality simulation module are limited to omitting the printout of channel cross section geometry and defining the frequency (in time and space) at which temperature and water quality simulation results are printed. These options are specified by use of the L1 and S1 records.

The sequence of printout from the water quality simulation module is: (a) miscellaneous information transferred from the flow simulation module, (b) job titles and simulation control data, (c) reservoir related input data, (d) stream related input data, (e) input water quality objectives at control points, (f) results of the reservoir water quality simulation, and (g) results of the stream water quality simulation. Items (a) through (e) are printed at the beginning of the run prior to the actual water quality analysis. Items (f) and (g) are printed during each simulation iteration. During the simulation and in-between the printed reservoir and stream results, selected data transferred from the flow simulation module to the water quality module may be printed. A detailed description of these items that appear in the output is provided below.

- a. Flow Simulation Module Geometry and Flow Data. The geometry and flow data transferred from the flow simulation module to the water quality simulation module includes:
  - (1) Job titles
  - (2) Miscellaneous reservoir and stream channel discharge control data and routing information.
  - (3) The elevation versus storage versus surface area tables defining the reservoir geometry.

The printout of some of the above data may be suppressed at the users option (JA card, Field 7).

- b. Job Titles and Simulation Controls. Selected information from data records TI through TQ are printed. Simulation controls include the length of simulation, input units, and identification of water quality constituents to be simulated.

- c. Reservoir Related Input Data. The reservoir related data include data from records L1 through CR, I1 through I4, and data transferred from the flow simulation module. These data include:
- (1) Miscellaneous geometric data, reservoir light attenuation characteristics and diffusion coefficients.
  - (2) Outlet characteristics of the flood control outlet, uncontrolled spillway and the wet wells of the reservoir's selective withdrawal structure.
  - (3) Table of reservoir geometry data and initial temperature and water quality data which includes both the input data and interpolated data for each fluid element. The geometry data includes elevation, area, volume and width at the dam.
  - (4) Reservoir inflow water quality data.
- d. Stream Related Input Data. The stream related data include data from the S1 through I4 records. These data include:
- (1) Miscellaneous print and read controls.
  - (2) Control point locations, fluid element lengths, location of local inflows and the fraction of the incremental local inflow discharged at the various locations.
  - (3) Stream channel cross section geometry tables. These tables define the relationship between elevation and area, hydraulic radius to the two-thirds power, width, Manning's n and flow. The printout of these geometry tables may be suppressed at the users option.
  - (4) Tributary inflow water quality data.
- e. Water Quality Objectives at Control Points. The water quality objectives include data input on the CT records. These data include the control point objectives and the objective function parameters.
- f. Results of the Reservoir Simulation. The results of the reservoir simulation are printed at intervals specified by the user. This output is printed during the appropriate simulation iteration and includes:
- (1) Equilibrium temperature, heat exchange rates, short wave solar radiation and wind speed. (These data are input via the ET records.)
  - (2) The reservoir inflow rate, outflow rates through the various outlets, mean outflow temperature and water quality, outflow temperature and water quality objectives and the reservoir elevation, surface area and volume.
  - (3) Computed reservoir temperature and water quality profiles.

g. Results of the Stream Simulation. The results of the stream simulation are printed at intervals specified by the user. This output is printed during the appropriate simulation iteration and includes:

- (1) Equilibrium temperature, heat exchange rates, short wave solar radiation and wind speed. (These data are input via the ET records.)
- (2) Reservoir outflow rates, temperature and water quality.
- (3) Local inflow rates, temperature and water quality.
- (4) Computed stream temperature and water quality distributions.
- (5) Stream temperature and water quality targets.

An example of the output from this module is provided in Test Problem 1 of Exhibit 1.

## REFERENCES

- Anderson, E.R., "Water Loss Investigations: Lake Hefner Studies," Technical Report, Project Paper 269, Geological Survey, U.S. Department of Interior, Washington, D.C., 1954.
- Baca, R.G., A.F. Gasperino, A. Brandstetter and M.S. Annette, "Water Quality Models for Municipal Water Supply Reservoirs," a report prepared for the Engineering and Water Supply Department, Adelaide, South Australia, January 1977.
- Bohan, J.P. and J.L. Grace, Jr., "Selective Withdrawal from Man-made Lakes; Hydraulic Laboratory Investigation," Technical Report H-73-4, U.S. Army Engineer Waterways Experiment Station, CE, Vicksburg, MS, March 1973.
- Corps of Engineers, Baltimore District, "Thermal Simulation of Lakes, User's Manual," August 1974.
- Debler, W.R., "Stratified Flow into a Line Sink," ASCE Journal of Engineering Mechanics Division, Vol. 85, EM3, July 1959.
- Edinger, J.E. and J.C. Geyer, "Heat Exchange in the Environment," Department of Sanitary Engineering and Water Resources, Research Project No. 49, The John Hopkins University, Baltimore, Maryland, June 1965.
- Hutchinson, G.E., "A Treatise on Limnology," Volume I, Geography, Physics and Chemistry, John Wiley and Sons, Inc., New York, 1957.
- Hydrologic Engineering Center, "Geometric Elements from Cross Section Coordinates", Computer Program Description, Davis, CA, October 1981.
- Hydrologic Engineering Center, "HEC-5, Simulation of Flood Control and Conservation Systems, User's Manual", Davis, CA, June 1979.
- Hydrologic Engineering Center, "WEATHER", Users Manual, Davis, CA, January 1986.
- Kanwisher, J., "On the Exchange of Gases Between the Atmosphere and Sea," Deep Sea Research, Vol. 10, pp. 195-207, 1963.
- Kaplan, E., "Reservoir Optimization for Water Quality Control", a PH.D dissertation, University of Pennsylvania, April 1974.
- O'Conner, D.J. and W.E. Dobbins, "Mechanism of Reaeration in Natural Streams," Transactions, American Society of Civil Engineers, Volume 123, 1958.
- Tennessee Valley Authority, "Heat and Mass Transfer Between a Water Surface and the Atmosphere," Report No. 14, April 1972.
- Water Resources Engineers, "Prediction of Thermal Energy Distribution in Streams and Reservoirs," Report to Department of Fish and Game, State of California, August 1968.

Water Resources Engineers, "The Thermal Simulation of Applegate Reservoir to Evaluate the Effect of Outlet Placement and Discharge on Downstream Temperature," report to Corps of Engineers, Portland District, May 1969a.

Water Resources Engineers, "Mathematical Models for the Prediction of Thermal Energy Changes in Impoundments," report to the Environmental Protection Agency, December 1969b.

EXHIBIT 1  
TEST PROBLEMS

HEC-5  
SIMULATION OF FLOOD CONTROL AND CONSERVATION SYSTEMS

APPENDIX ON WATER QUALITY ANALYSIS

TABLE OF CONTENTS  
EXHIBIT 1  
TEST PROBLEMS

1. INTRODUCTION
2. TEST PROBLEM 1 - Standard Parallel Reservoir Case
3. TEST PROBLEM 2 - Standard Tandem Reservoir Case
4. TEST PROBLEM 3 - Parallel Reservoirs with Calibration Option
5. TEST PROBLEM 4 - Tandem Reservoirs with Phytoplankton Option
6. TEST PROBLEM 5 - Tandem Reservoirs with Steady State Option
7. TEST PROBLEM 6 - Tandem Reservoirs with Steady State Option and Flow Augmentation

EXHIBIT 1  
TEST PROBLEMS

INTRODUCTION

Input for six water quality test problems are shown in this exhibit along with a general description of each. Output for Test Problem 1 is also shown as an illustration of typical output.

TEST PROBLEM 1 - Standard Parallel Reservoir Case

- a. The system simulated in this test of the water quality simulation module consists of two parallel reservoirs and the downstream system. The system diagram is shown on the following page.
- b. The reservoir characteristics are:

	<u>Baker Reservoir</u>	<u>Smith Reservoir</u>
Reservoir depth	250 ft	115 ft
Reservoir capacity	1,688,00 ac-ft	1,130 ac-ft
Flood control outlet	Yes	No
Uncontrolled Spillway	No	Yes
Number of wet wells	2	2
Gates per wet well	4	4

- c. The stream system consists of a 5.5 mile stretch from Baker Reservoir to the confluence with the stream on which the Smith Reservoir is located. Smith Reservoir is 4.7 miles above the confluence. The energy grade line (EGL) slope from Baker reservoir to the confluence is 0.00065. The EGL slope from the Smith reservoir to the confluence is 0.0014. From the confluence (CP #30) to CP #40, the EGL slope is 0.00057 and from CP #40 to river mile 30.4 the EGL slope is 0.00065. Below river mile 30.4, to the end of the system, the EGL slope is 0.000076.
- d. Tributary inflows are input to the stream system at two points, RM 45 and RM 30.
- e. Temperature, total dissolved solids (TDS), carbonaceous BOD and dissolved oxygen are simulated. Local inflow temperature values for both of the two reservoirs and for the stream system are furnished as departures from the equilibrium temperature. Similarly, carbonaceous BOD is furnished as five-day values and a factor of 1.463, based on a bottle BOD decay rate of 0.23 per day, is used to convert the five-day values to ultimate values. TDS and dissolved oxygen concentrations were furnished in mg/l.




f. The water quality objectives for the control points are expressed as follows:

1. Temperature: less than or equal to the specified value
2. TDS: less than or equal to the specified value
3. Carbonaceous BOD: less than or equal to the specified value
4. Dissolved oxygen: greater than or equal to the specified value.

Different weights are place on each constituent at each control point (see CT cards in input data listing).

g. The recommended weights and objective parameters were used for the gate selection routine (see WT and PL cards).

A complete listing of the input data file follows. Following the data listing, selected simulation results are presented as an illustration of example output. The simulation results that have been omitted are the repetitive printed tables that show simulated stream and reservoir water quality on days after day 130. A complete output listing is included with the computer source code distribution.



**EXAMPLE PARALLEL RESERVOIR PROBLEM**

T1	TESTING HEC5Q WATER QUALITY SIMULATION CAPABILITY									
T2	PARALLEL RIVER SYSTEM									
T3	TEST PROBLEM 1									
J1	0	5	5	3	4	2	0	0		
J2	36	0	0	0	0	0	0	0		
J9										
RL	10	1200000	0	100000	200000	1500000	1600000			
RO	3	30	40	50						
RS	7	100	6300	31300	88000	188000	563000	1688000		
RQ	7	0	20000	30000	40000	50000	50000	50000		
RA	7	10	500	1500	3000	5000	10000	20000		
RE	7	800	825	850	870	900	950	1030		
R3	2	2	2	2	99	99	99	99	99	99
R3	99	99								
CP	10	20000	300	200						
IDCP10-BAKER DAM										
RT	10	30	2.2	.25	12	0				
RL	20	550000	0	2000	550000	952000	1130000			
RO	3	30	40	50						
RS	8	2000	20000	52000	113000	209000	320000	550000	800000	1130000
RQ	8	0	5680	5680	5680	5680	5680	29180	59680	104980
RA	8	150	2100	4500	7600	11800	17000	22400	28600	37200
RE	8	892	910	920	930	940	950	962.5	970	980
R3	2	2	2	2	99	99	99	99	99	99
R3	99	99								
CP	20	20000	30	20						
IDCP20-SMITH DAM										
RT	20	30	2.2	.25	12	0				
CP	30	30000	300	200						
IDCP30-CONF RM60										
RT	30	40	2.2	.25	12	0				
CP	40	30000	300	200						
ID CP40 ** RM 40										
RT	40	50	2.2	.25	12	0				
CP	50	50000	300	200						
IDCP50 ** RM24.2										
RT	50	0	0	0	0	0				
ED										
BF	0	120	0	074050100	120	24				
NOLIST										
IN	10	1MAY74	2059	1814	2125	2243	1947	1836	1735	1587
IN	1549	1509	1413	4584	7520	5061	3549	2931	2801	3866
IN	2752	2293	1962	1793	2476	2528	1958	1650	1462	1344
IN	1810	3581	3367	7629	5501	3699	3057	2603	2294	2073
IN	1894	1750	1596	1423	1313	1251	1052	1312	2547	2301
IN	1803	1360	1185	1200	1456	2434	4601	3121	2769	2230
IN	1846	2107	1918	15259	7046	4185	3113	3167	2814	2295
IN	1910	1606	1448	1535	1368	1196	1039	1032	1013	940
IN	890	890	865	826	783	826	928	847	788	829
IN	804	806	945	801	712	751	914	911	935	792
IN	747	717	823	1416	997	806	759	732	683	653
IN	633	639	621	644	604	598	598	596	601	642
IN	662	838	756	1130	1138	1202	1774	2727	2659	1566

IN	20	1MAY74	430	816	668	1979	1523	1195	1065	847
IN	698	569	455	402	472	424	415	956	613	510
IN	434	381	361	327	289	338	758	355	262	202
IN	169	133	163	192	203	181	166	212	1017	639
IN	639	366	255	194	236	596	432	284	251	745
IN	348	226	179	198	198	164	155	159	177	888
IN	348	386	197	133	134	141	181	407	212	145
IN	126	122	112	108	89	80	87	80	69	68
IN	64	58	47	53	49	39	43	46	60	60
IN	56	50	49	41	43	39	39	43	39	39
IN	47	47	49	43	47	96	151	112	473	212
IN	297	405	201	128	100	79	64	89	102	90
IN	88	165	95	83	184	1167	463	601	676	665
IN	40	1MAY74	645	588	561	488	452	440	425	405
IN	406	398	380	923	1207	1171	1161	1075	1190	1601
IN	1685	1941	1849	1752	1784	1322	645	397	366	458
IN	669	1011	1113	1740	1529	1352	1273	1219	1171	908
IN	575	431	407	375	357	348	243	231	469	598
IN	671	585	369	237	288	360	546	768	900	874
IN	829	712	549	2648	1733	1751	1617	1671	1565	1433
IN	922	465	361	384	353	328	298	305	296	285
IN	279	235	143	142	139	150	226	282	276	191
IN	106	139	183	220	269	268	278	283	311	249
IN	178	172	162	177	135	119	117	117	130	164
IN	161	166	160	117	61	42	51	141	142	108
IN	87	235	418	701	621	790	976	1222	1532	1570
IN	50	1MAY74	3317	3816	3333	3150	2843	2861	2976	2831
IN	3011	3250	3265	4695	13438	10915	9154	8282	7643	7539
IN	6757	6013	4768	3744	3530	3463	3178	2914	2592	2150
IN	1941	1852	1735	1747	1903	2065	1847	1399	1148	1035
IN	978	844	714	809	784	873	969	816	1405	1972
IN	2159	1563	1308	1482	1621	1469	1155	1353	975	1469
IN	1483	1761	1469	4196	7637	5846	5734	4803	4285	3660
IN	3314	2783	1990	1912	1651	1441	937	893	1209	1028
IN	980	990	1160	785	550	695	679	705	701	786
IN	566	627	774	742	696	661	613	578	630	914
IN	930	930	918	981	1006	881	924	829	857	780
IN	684	606	637	670	578	562	558	486	458	440
IN	621	825	1619	2200	2012	1742	1687	2852	4965	4311
QA	10	1MAY74	1270	1320	1360	1410	1440	1470	1480	1480
QA	1480	1480	1790	2190	2480	3480	4490	4420	4300	4210
QA	4130	3960	3720	3370	2470	1910	1950	1940	1890	1570
QA	1270	1680	2210	2480	4000	5510	5350	4400	2930	1970
QA	1570	1570	1570	1560	1560	1530	1510	1480	1830	2690
QA	3120	2840	1640	819	854	900	1540	2750	3250	2860
QA	2100	2030	2030	3600	9280	11000	7280	4130	3250	2180
QA	1750	1470	1210	1290	1320	1320	1290	1270	1230	948
QA	570	600	610	610	621	631	642	707	764	753
QA	741	730	730	741	730	719	707	707	775	775
QA	819	786	494	819	865	654	865	831	797	764
QA	719	685	494	631	580	521	346	540	486	486
QA	521	600	438	797	1410	2000	2050	2130	3460	4590

QA	20	1MAY74	1236	521	387	405	442	949	1602	1572
QA	1528	1040	600	593	590	488	390	497	600	600
QA	597	495	310	220	220	220	226	325	420	417
QA	403	400	286	165	110	110	110	110	275	540
QA	637	627	518	420	420	420	420	320	227	330
QA	430	423	226	110	110	110	110	105	316	440
QA	440	437	430	226	110	110	110	110	110	110
QA	110	105	110	110	110	110	110	110	110	110
QA	110	110	110	110	110	110	75	35	35	35
QA	35	35	35	35	35	35	35	35	35	35
QA	35	35	35	35	36	38	62	85	105	125
QA	182	240	240	240	235	230	178	125	125	125
QA	125	125	125	125	285	463	601	676	665	655

EJ

TI FICTICIOUS PARALLEL RIVER BASIN TEST OF HEC-5Q WITH WATER QUALITY  
 TI RESERVOIRS ARE FICTICIOUS ALSO \*\* C.P. OF 10, 20, 30, 40 AND 50  
 TI CONSTITUENTS ARE TEMPERATURE, TDS, CARBONACEOUS BOD AND OXYGEN

JA 740501 740831 5 2 F 1

EZ

ET	116	67.59	105.5	2350.0	8.53
ET	117	75.54	75.0	2350.5	5.56
ET	118	72.51	155.0	2250.2	11.54
ET	119	73.50	195.0	2250.1	13.59
ET	120	74.51	125.5	2250.3	8.54
ET	121	64.56	135.8	2350.6	12.55
ET	122	62.54	115.4	2450.1	10.51
ET	123	65.54	125.3	2350.9	10.50
ET	124	60.56	105.7	2450.1	10.54
ET	125	63.56	105.6	2450.1	9.55
ET	126	57.50	125.1	2450.3	12.50
ET	127	58.55	85.7	2550.6	8.58
ET	128	66.56	95.8	2450.1	7.52
ET	129	66.56	135.3	2450.0	11.58
ET	130	67.58	95.1	2450.6	7.55
ET	131	70.53	135.1	2450.9	10.59
ET	132	66.58	145.4	2450.1	12.51
ET	133	62.56	145.1	2550.4	13.50
ET	134	72.50	145.0	2450.1	11.53
ET	135	71.59	175.2	2450.3	13.52
ET	136	74.51	135.5	2450.6	9.56
ET	137	78.51	175.4	2450.2	10.55
ET	138	75.56	125.7	2450.3	8.59
ET	139	72.54	135.9	2550.7	9.50
ET	140	73.53	115.8	2550.2	8.55
ET	141	81.53	95.9	2550.9	5.56
ET	142	77.55	145.0	2450.5	8.58
ET	143	73.54	145.7	2550.6	10.51
ET	144	68.59	155.9	2550.9	12.51
ET	145	67.54	95.2	2650.1	8.51
ET	146	69.55	95.3	2650.0	7.52
ET	147	64.59	115.9	2650.5	10.56
ET	148	71.57	95.5	2650.2	7.57
ET	149	73.54	145.0	2550.2	10.52

ET	150	80.54	105.4	2550.5	6.51
ET	151	77.53	135.9	2550.9	8.54
ET	152	70.57	135.4	2550.9	10.59
ET	153	72.59	125.6	2650.7	9.56
ET	154	78.51	85.5	2650.4	5.50
ET	155	79.57	95.9	2550.9	6.59
ET	156	76.56	135.5	2550.6	8.53
ET	157	77.55	135.5	2550.1	8.50
ET	158	75.53	175.0	2550.3	11.53
ET	159	78.50	135.6	2550.9	8.54
ET	160	82.50	135.6	2550.4	7.57
ET	161	77.57	215.1	2550.9	13.52
ET	162	69.53	175.9	2650.5	13.57
ET	163	71.57	115.4	2650.6	8.58
ET	164	73.56	105.8	2650.3	7.56
ET	165	79.58	95.8	2650.5	5.55
ET	166	72.52	155.5	2650.4	10.55
ET	167	71.52	145.3	2650.1	10.52
ET	168	71.56	115.0	2650.7	8.54
ET	169	73.53	125.3	2650.5	8.58
ET	170	77.59	125.1	2650.1	8.51
ET	171	82.54	145.8	2550.0	8.55
ET	172	77.57	195.4	2550.1	12.54
ET	173	81.55	105.0	2550.8	6.52
ET	174	72.52	145.9	2650.9	10.51
ET	175	71.55	155.0	2650.8	11.52
ET	176	71.52	125.3	2650.1	9.50
ET	177	77.58	95.6	2650.1	6.53
ET	178	75.59	125.3	2650.7	8.53
ET	179	74.59	125.5	2650.1	8.58
ET	180	74.58	135.1	2650.1	8.54
ET	181	74.58	215.0	2550.0	14.58
ET	182	80.55	135.6	2550.8	8.51
ET	183	80.59	185.1	2550.8	10.57
ET	184	83.54	205.0	2450.3	10.56
ET	185	83.50	205.2	2450.8	10.56
ET	186	82.50	145.0	2550.8	7.58
ET	187	83.57	105.5	2550.4	5.57
ET	188	89.50	85.1	2550.7	4.54
ET	189	89.52	105.4	2550.9	4.52
ET	190	86.57	145.1	2450.9	6.55
ET	191	82.55	165.3	2450.5	8.57
ET	192	77.54	165.3	2550.5	10.55
ET	193	79.50	105.1	2550.9	6.58
ET	194	87.51	85.2	2550.5	4.50
ET	195	82.50	165.8	2450.9	9.56
ET	196	78.59	165.8	2450.7	10.53
ET	197	76.58	145.4	2550.0	9.58
ET	198	85.58	95.6	2550.9	4.59
ET	199	83.50	145.6	2450.7	7.57
ET	200	81.54	205.3	2450.6	11.50
ET	201	77.55	145.3	2450.5	9.51
ET	202	77.58	125.0	2550.5	8.50

ET	203	82.52	105.7	2450.6	6.52
ET	204	79.54	125.5	2450.3	7.59
ET	205	80.52	115.4	2450.2	6.55
ET	206	84.59	85.9	2450.7	4.50
ET	207	89.54	85.8	2450.1	3.51
ET	208	88.57	95.9	2350.6	4.55
ET	209	82.58	135.1	2350.5	7.58
ET	210	78.56	155.3	2350.3	8.53
ET	211	77.51	155.5	2350.2	9.52
ET	212	79.53	125.3	2350.3	7.57
ET	213	83.59	105.3	2350.8	5.55
ET	214	84.54	115.8	2350.0	5.58
ET	215	79.54	175.7	2250.5	10.54
ET	216	76.56	175.7	2350.9	10.55
ET	217	75.50	115.1	2350.3	7.56
ET	218	79.52	105.2	2350.8	6.59
ET	219	84.54	95.9	2250.2	4.57
ET	220	83.50	105.5	2250.9	5.59
ET	221	83.53	95.9	2250.4	5.58
ET	222	78.55	135.9	2250.7	8.59
ET	223	78.58	165.9	2250.5	9.54
ET	224	83.56	115.8	2150.0	5.58
ET	225	82.54	125.9	2150.5	6.55
ET	226	79.58	135.4	2250.7	7.56
ET	227	81.59	95.2	2250.6	5.55
ET	228	85.58	85.2	2150.8	4.55
ET	229	79.57	155.6	2150.0	8.57
ET	230	87.54	75.6	2150.9	3.52
ET	231	86.54	75.1	2150.0	3.57
ET	232	90.50	65.8	2150.1	2.53
ET	233	85.53	85.0	2150.1	4.58
ET	234	85.52	85.0	2150.5	4.53
ET	235	84.58	95.2	2050.7	4.57
ET	236	82.52	115.2	2050.5	5.58
ET	237	87.52	75.2	2050.9	3.52
ET	238	86.52	85.3	2050.6	4.51
ET	239	80.53	155.8	2050.4	8.58
ET	240	79.58	145.3	2050.1	8.59
ET	241	79.51	145.2	1950.7	8.58
ET	242	80.52	125.7	1950.4	6.59
ET	243	77.59	155.1	1950.6	9.56
ET	244	76.55	115.8	1950.0	6.50
ET	245	73.52	115.2	1950.1	7.54
ET	246	65.54	145.9	2050.9	12.50
ET	247	67.58	105.8	2050.9	8.55
ET	248	69.56	85.2	1950.8	6.50
ET	249	70.57	95.1	1950.5	7.55
ET	250	78.58	75.3	1950.2	4.55
ET	251	84.57	55.1	1850.7	2.51
ET	252	86.58	55.5	1850.6	2.57
ET	253	82.51	65.2	1850.6	3.59
ET	254	78.58	95.0	1850.5	5.50
ET	255	77.58	155.8	1750.7	8.58

ET	256	76.50	155.9	1750.1	9.56
ET	257	68.51	105.2	1850.9	7.57
ET	258	68.50	95.7	1850.5	6.59
ET	259	71.50	85.1	1750.5	5.54
ET	260	70.58	115.5	1750.5	8.51
ET	261	71.53	105.1	1750.1	7.54
ET	262	74.53	85.9	1750.1	5.51
ET	263	73.53	115.4	1650.7	7.55
ET	264	64.59	105.9	1750.2	8.58
ET	265	60.57	105.2	1750.1	9.53
ET	266	57.50	75.9	1750.6	7.54
ET	267	59.59	75.2	1750.0	6.51
ET	268	62.56	115.1	1650.1	9.54
ET	269	65.51	115.0	1650.5	9.52
ET	270	70.54	85.4	1550.5	5.53
ET	271	72.54	125.1	1550.2	8.53
ET	272	63.56	165.7	1550.3	13.51
ET	273	56.54	115.4	1550.0	11.53
ET	-274	53.71	104.9	1568.0	10.72
EZ	-2				
ET	116	67.19	100.5	2335.0	8.43
ET	117	75.04	77.0	2331.5	5.26
ET	118	72.91	155.0	2291.2	11.34
ET	119	73.40	196.0	2278.1	13.89
ET	120	74.01	127.5	2294.3	8.64
ET	121	64.06	138.8	2385.6	12.35
ET	122	62.44	111.4	2409.1	10.31
ET	123	65.44	126.3	2385.9	10.60
ET	124	60.66	107.7	2456.1	10.34
ET	125	63.36	102.6	2457.1	9.35
ET	126	57.60	124.1	2466.3	12.60
ET	127	58.75	89.7	2507.6	8.88
ET	128	66.16	90.8	2484.1	7.72
ET	129	66.36	138.3	2446.0	11.48
ET	130	67.68	96.1	2494.6	7.85
ET	131	70.23	130.1	2473.9	10.09
ET	132	66.18	147.4	2470.1	12.21
ET	133	62.56	144.1	2518.4	13.40
ET	134	72.00	149.0	2492.1	11.23
ET	135	71.49	175.2	2472.3	13.02
ET	136	74.91	133.5	2480.6	9.06
ET	137	78.21	176.4	2413.2	10.65
ET	138	75.06	127.7	2486.3	8.59
ET	139	72.84	131.9	2525.7	9.60
ET	140	73.33	118.8	2544.2	8.55
ET	141	81.63	95.9	2508.9	5.46
ET	142	77.95	142.0	2476.5	8.68
ET	143	73.94	148.7	2521.6	10.31
ET	144	68.99	151.9	2563.9	12.01
ET	145	67.24	99.2	2614.1	8.21
ET	146	69.55	97.3	2617.0	7.72
ET	147	64.69	119.9	2640.5	10.76
ET	148	71.17	97.5	2626.2	7.47
ET	149	73.54	145.0	2558.2	10.02



ET	150	80.04	107.4	2543.5	6.31
ET	151	77.13	137.9	2528.9	8.64
ET	152	70.47	132.4	2598.9	10.09
ET	153	72.09	120.6	2629.7	9.06
ET	154	78.21	86.5	2621.4	5.50
ET	155	79.57	99.9	2598.9	6.09
ET	156	76.06	133.5	2597.6	8.93
ET	157	77.65	133.5	2579.1	8.50
ET	158	75.63	175.0	2568.3	11.63
ET	159	78.80	137.6	2562.9	8.34
ET	160	82.00	138.6	2539.4	7.67
ET	161	77.77	212.1	2535.9	13.02
ET	162	69.73	170.9	2626.5	13.27
ET	163	71.67	119.4	2644.6	8.88
ET	164	73.76	105.8	2658.3	7.56
ET	165	79.68	93.8	2632.5	5.75
ET	166	72.72	153.5	2601.4	10.85
ET	167	71.62	145.3	2627.1	10.72
ET	168	71.26	110.0	2663.7	8.34
ET	169	73.63	124.3	2646.5	8.88
ET	170	77.79	129.1	2600.1	8.21
ET	171	82.04	144.8	2542.0	8.05
ET	172	77.67	199.4	2553.1	12.44
ET	173	81.25	107.0	2592.8	6.22
ET	174	72.32	143.9	2625.9	10.51
ET	175	71.35	151.0	2647.8	11.52
ET	176	71.62	129.3	2649.1	9.80
ET	177	77.68	96.6	2622.1	6.13
ET	178	75.09	129.3	2628.7	8.93
ET	179	74.39	127.5	2615.1	8.88
ET	180	74.98	130.1	2601.1	8.84
ET	181	74.88	210.0	2568.0	14.18
ET	182	80.55	135.6	2566.8	8.01
ET	183	80.89	185.1	2524.8	10.67
ET	184	83.64	204.0	2486.3	10.76
ET	185	83.70	200.2	2483.8	10.56
ET	186	82.60	140.0	2503.8	7.58
ET	187	83.17	106.5	2566.4	5.97
ET	188	89.10	87.1	2546.7	4.14
ET	189	89.42	102.4	2502.9	4.72
ET	190	86.77	141.1	2467.9	6.85
ET	191	82.85	165.3	2461.5	8.77
ET	192	77.04	165.3	2538.5	10.65
ET	193	79.90	105.1	2557.9	6.38
ET	194	87.21	86.2	2531.5	4.30
ET	195	82.40	168.8	2466.9	9.26
ET	196	78.49	168.8	2498.7	10.43
ET	197	76.98	140.4	2528.0	9.08
ET	198	85.08	91.6	2508.9	4.79
ET	199	83.80	141.6	2436.7	7.47
ET	200	81.34	201.3	2425.6	11.30
ET	201	77.05	147.3	2496.5	9.51
ET	202	77.18	127.0	2509.5	8.30

ET	203	82.02	109.7	2467.6	6.22
ET	204	79.34	124.5	2445.3	7.29
ET	205	80.82	119.4	2435.2	6.85
ET	206	84.99	86.9	2450.7	4.50
ET	207	89.44	81.8	2408.1	3.71
ET	208	88.47	90.9	2398.6	4.25
ET	209	82.58	133.1	2372.5	7.18
ET	210	78.96	151.3	2377.3	8.93
ET	211	77.41	150.5	2393.2	9.42
ET	212	79.23	127.3	2391.3	7.67
ET	213	83.59	103.3	2373.8	5.55
ET	214	84.94	111.8	2329.0	5.68
ET	215	79.84	175.7	2297.5	10.04
ET	216	76.86	172.7	2324.9	10.85
ET	217	75.70	118.1	2364.3	7.76
ET	218	79.32	102.2	2340.8	6.09
ET	219	84.34	95.9	2296.2	4.97
ET	220	83.50	107.5	2261.9	5.59
ET	221	83.93	98.9	2259.4	5.08
ET	222	78.15	134.9	2266.7	8.19
ET	223	78.78	161.9	2230.5	9.64
ET	224	83.66	114.8	2198.0	5.88
ET	225	82.54	122.9	2195.5	6.55
ET	226	79.68	132.4	2210.7	7.76
ET	227	81.79	96.2	2219.6	5.35
ET	228	85.68	86.2	2188.8	4.25
ET	229	79.77	152.6	2150.0	8.77
ET	230	87.04	73.6	2159.9	3.42
ET	231	86.54	73.1	2158.0	3.47
ET	232	90.10	67.8	2142.1	2.93
ET	233	85.53	89.0	2121.1	4.38
ET	234	85.12	89.0	2106.5	4.43
ET	235	84.78	95.2	2088.7	4.77
ET	236	82.42	110.2	2072.5	5.88
ET	237	87.62	71.2	2069.9	3.22
ET	238	86.02	88.3	2042.6	4.21
ET	239	80.53	159.8	2012.4	8.88
ET	240	79.48	145.3	2004.1	8.19
ET	241	79.11	149.2	1979.7	8.48
ET	242	80.02	122.7	1985.4	6.89
ET	243	77.29	150.1	1973.6	9.06
ET	244	76.95	112.8	1979.0	6.80
ET	245	73.62	110.2	1992.1	7.34
ET	246	65.34	149.9	2008.9	12.30
ET	247	67.48	102.8	2007.9	8.05
ET	248	69.66	89.2	1996.8	6.60
ET	249	70.47	99.1	1948.5	7.05
ET	250	78.08	71.3	1920.2	4.05
ET	251	84.67	58.1	1888.7	2.71
ET	252	86.58	50.5	1870.6	2.17
ET	253	82.51	63.2	1844.6	3.09
ET	254	78.78	98.0	1817.5	5.50
ET	255	77.58	150.8	1779.7	8.88

ET	256	76.30	152.9	1764.1	9.26			
ET	257	68.81	104.2	1823.9	7.67			
ET	258	68.40	92.7	1819.5	6.89			
ET	259	71.20	85.1	1791.5	5.84			
ET	260	70.88	113.5	1763.5	8.01			
ET	261	71.83	105.1	1738.1	7.14			
ET	262	74.23	83.9	1717.1	5.21			
ET	263	73.63	110.4	1677.7	7.05			
ET	264	64.69	107.9	1709.2	8.68			
ET	265	60.17	102.2	1716.1	9.13			
ET	266	57.00	77.9	1727.6	7.34			
ET	267	59.29	71.2	1705.0	6.31			
ET	268	62.06	114.1	1649.1	9.84			
ET	269	65.01	115.0	1620.5	9.22			
ET	270	70.84	87.4	1585.5	5.93			
ET	271	72.84	129.1	1529.2	8.43			
ET	272	63.36	163.7	1549.3	13.71			
ET	273	56.34	119.4	1576.0	11.63			
ET	-274	53.71	104.9	1568.0	10.72			
QC	1	0	0	0	1	0	1	
TQ	TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY							
TQ	CARBONACEOUS BOD IN MG/L							
TQ	DISSOLVED OXYGEN IN MG/L L1							
L2	10	5	10	.4	1	2		
LR	2	10000	1	5000				
L3		.01	1.-6	1.-4	0	-.7		
L5	50	50000	825					
L7	10	2000	820	860	900	940		
L7	10	2000	840	880	920	960		
L8		200	400	800	1400	2000	3000	5000
PL	0.25	100		-4.00				
PL	0.05	100		-0.20				
PL	0.20	100		-8.00				
PL	0.25	100	3.2	-0.70	0.10	-0.05		
L9		40	41	42	43	45	48	60
C1		120.	120.	120.	120.	120.	180.	180.
C5		0.5	0.5	0.5	0.5	0.5	0.5	0.5
C7		9.1	9.1	9.1	9.1	9.1	9.1	9.1
SA		100	100	100	100	100	100	100
DK			0.1	1.463				
L2	20	2		5	.4	1	1	
LR	3	60000.						
L3		.01	1.-6	1.-4	0	-.7		
L5	1	10	895.5					
L6	870	99300	962.5					
L7	7.9	2840	895.5	909.5	923.5	937.5		
L7	7.9	2840	902.5	916.5	930.5	944.5		
L8		410	460	500	550	600	650	700 750
PL	0.25	100		-4.00				
PL	0.05	100		-0.20				
PL	0.20	100		-8.00				
PL	0.25	100	3.2	-0.70	0.10	-0.05		
L9		54	55	57	57	57	57	57

C1		160	190	190	190	190	190	190	190
C5		.3	.3	.3	.3	.3	.3	.3	.3
C7		8.4	8.7	9.2	9.2	9.2	9.2	9.2	9.2
SA		100	100	100	100	100	100	100	100
DK			.2		1.463				
CR		1.047	1.047	1.047	1.0159				
S1		10	1	0	10	20	1		
S2	10	65.5	30	60	1.5				
S2	20	4.7	30	0.	1.5				
S2	30	60	40	40	2	45	3		
S2	40	40	50	24.2	1.975	30	4		
SR	10	30	2	7					
SK		1.	1.	1.	1.	1.	1.	1.	1.
SR	20	30	1	2					
SR	-30	50	1	4					
S3	10	65.5	844.0	0.	0.	0.	.050		
S3			844.2	0.	.21	5.0	.050		
S3			844.6	4.0	.35	20.0	.050		
S3			845.0	14.0	.61	29.0	.050		
S3			846.0	54.0	1.04	50.0	.050		
S3			847.0	114.0	1.40	67.0	.050		
S3			848.0	194.0	1.55	99.0	.050		
S3			849.0	305.0	1.84	121.0	.050		
S3			850.0	440.0	2.02	152.0	.050		
S3			851.0	605.0	2.20	185.0	.050		
S3			852.0	827.0	2.17	264.0	.050		
S3			853.0	1100.0	2.52	279.0	.050		
S3			854.0	1384.0	2.87	288.0	.050		
S3			855.0	1677.0	3.15	301.0	.050		
S3			856.0	1985.0	3.40	316.0	.050		
S3			857.0	2308.0	3.67	326.0	.050		
S3			858.0	2634.0	3.99	326.0	.050		
S3			859.0	2960.0	4.30	326.0	.050		
S3			861.0	3612.0	4.88	326.0	.050		
S3			863.0	4264.0	5.41	326.0	.050		
S3	30	60.	825.4	0.	0.	0.	.050		
S3			825.6	1.0	.22	9.0	.050		
S3			826.0	10.0	.43	33.0	.050		
S3			826.4	27.0	.64	52.0	.050		
S3			827.4	92.0	1.13	77.0	.050		
S3			828.4	179.0	1.51	96.0	.050		
S3			829.4	287.0	1.79	119.0	.050		
S3			830.4	418.0	2.08	138.0	.050		
S3			831.4	563.0	2.38	152.0	.050		
S3			832.4	723.0	2.65	166.0	.050		
S3			833.4	893.0	2.95	174.0	.050		
S3			834.4	1071.0	3.23	183.0	.050		
S3			835.4	1258.0	3.48	191.0	.050		
S3			836.4	1455.0	3.64	207.0	.050		
S3			837.4	1675.0	3.68	234.0	.050		
S3			838.4	1922.0	3.83	253.0	.050		
S3			839.4	2175.0	4.16	253.0	.050		
S3			840.4	2428.0	4.48	253.0	.050		

S3			842.4	2934.0	5.08	253.0	.050
S3			844.4	3440.0	5.65	253.0	.050
S3	20	4.7	859.6	0.	0.	0.	0.050
S3			859.8	1.5	0.16	24.	0.050
S3			860.2	22.0	0.46	70.	0.050
S3			860.6	56.1	0.73	104.	0.050
S3			861.6	178.2	1.28	128.	0.050
S3			862.6	307.7	1.82	134.	0.050
S3			863.6	442.8	2.28	140.	0.050
S3			864.6	583.8	2.57	142.	0.050
S3			865.6	729.1	2.97	147.	0.050
S3			866.6	878.1	3.19	149.	0.050
S3			867.6	1030.6	3.49	156.	0.050
S3			868.6	1186.8	3.78	162.	0.050
S3			869.6	1346.6	4.06	168.	0.050
S3			870.6	1510.1	4.32	174.	0.050
S3			871.6	1677.2	4.57	180.	0.050
S3			872.6	1848.0	4.81	186.	0.050
S3			873.6	2022.4	5.04	192.	0.050
S3			874.6	2200.5	5.27	198.	0.050
S3			876.6	2567.5	5.69	210.	0.050
S3			878.6	2949.1	6.10	222.	0.050
S3	30	0.	825.4	0.	0.	0.	.050
S3			825.6	1.0	.22	9.0	.050
S3			826.0	10.0	.43	33.0	.050
S3			826.4	27.0	.64	52.0	.050
S3			827.4	92.0	1.13	77.0	.050
S3			828.4	179.0	1.51	96.0	.050
S3			829.4	287.0	1.79	119.0	.050
S3			830.4	418.0	2.08	138.0	.050
S3			831.4	563.0	2.38	152.0	.050
S3			832.4	723.0	2.65	166.0	.050
S3			833.4	893.0	2.95	174.0	.050
S3			834.4	1071.0	3.23	183.0	.050
S3			835.4	1258.0	3.48	191.0	.050
S3			836.4	1455.0	3.64	207.0	.050
S3			837.4	1675.0	3.68	234.0	.050
S3			838.4	1922.0	3.83	253.0	.050
S3			839.4	2175.0	4.16	253.0	.050
S3			840.4	2428.0	4.48	253.0	.050
S3			842.4	2934.0	5.08	253.0	.050
S3			844.4	3440.0	5.65	253.0	.050
S3	40	40.0	765.0	0.	0.	0.	.050
S3			765.2	1.0	.22	9.0	.050
S3			765.6	10.0	.43	33.0	.050
S3			766.0	27.0	.64	52.0	.050
S3			767.0	92.0	1.13	77.0	.050
S3			768.0	179.0	1.51	96.0	.050
S3			769.0	287.0	1.79	119.0	.050
S3			770.0	418.0	2.08	138.0	.050
S3			771.0	563.0	2.38	152.0	.050
S3			772.0	723.0	2.65	166.0	.050
S3			773.0	893.0	2.95	174.0	.050
S3			774.0	1071.0	3.23	183.0	.050

S3			775.0	1258.0	3.48	191.0	.050
S3			776.0	1455.0	3.64	207.0	.050
S3			777.0	1675.0	3.68	234.0	.050
S3			778.0	1922.0	3.83	253.0	.050
S3			779.0	2175.0	4.16	253.0	.050
S3			780.0	2428.0	4.48	253.0	.050
S3			782.0	2934.0	5.08	253.0	.050
S3			784.0	3440.0	5.65	253.0	.050
S3	50	32.0	730.6	0.	0.	0.	.050
S3			730.8	0.	.21	2.0	.050
S3			731.2	2.0	.44	6.0	.050
S3			731.6	6.0	.45	19.0	.050
S3			732.6	74.0	.84	96.0	.050
S3			733.6	177.0	1.37	109.0	.050
S3			734.6	291.0	1.80	120.0	.050
S3			735.6	421.0	2.12	135.0	.050
S3			736.6	565.0	2.44	147.0	.050
S3			737.6	715.0	2.74	155.0	.050
S3			738.6	878.0	2.99	168.0	.050
S3			739.6	1050.0	3.26	176.0	.050
S3			740.6	1230.0	3.51	184.0	.050
S3			741.6	1418.0	3.74	193.0	.050
S3			742.6	1618.0	3.83	212.0	.050
S3			743.6	1844.0	3.86	239.0	.050
S3			744.6	2094.0	4.05	253.0	.050
S3			745.6	2347.0	4.37	253.0	.050
S3			747.6	2853.0	4.98	253.0	.050
S3			749.6	3359.0	5.55	253.0	.050
S3	50	30.4	722.9	0.	0.	0.	.030
S3			723.1	2.0	.22	15.0	.030
S3			723.5	14.0	.45	45.0	.030
S3			723.9	37.0	.64	74.0	.030
S3			724.9	130.0	1.12	111.0	.030
S3			725.9	271.0	1.43	167.0	.030
S3			726.9	462.0	1.72	218.0	.030
S3			727.9	701.0	2.04	257.0	.030
S3			728.9	978.0	2.34	287.0	.030
S3			729.9	1275.0	2.59	310.0	.030
S3			730.9	1599.0	2.79	337.0	.030
S3			731.9	1964.0	2.71	418.0	.030
S3			732.9	2394.0	2.98	444.0	.030
S3			733.9	2851.0	3.24	469.0	.030
S3			734.9	3342.0	3.39	518.0	.030
S3			735.9	3887.0	3.54	571.0	.030
S3			736.9	4482.0	3.74	610.0	.030
S3			737.9	5100.0	4.01	627.0	.030
S3			739.9	6390.0	4.49	662.0	.030
S3			741.9	7745.0	4.96	692.0	.030
S3	50	28.4	725.3	0.	0.	0.	.030
S3			725.5	4.0	.23	30.0	.030
S3			725.9	22.0	.48	59.0	.030
S3			726.3	51.0	.67	90.0	.030
S3			727.3	167.0	1.13	139.0	.030

S3			728.3	375.0	1.37	249.0	.030
S3			729.3	644.0	1.75	289.0	.030
S3			730.3	946.0	2.13	313.0	.030
S3			731.3	1271.0	2.46	336.0	.030
S3			732.3	1617.0	2.76	357.0	.030
S3			733.3	1985.0	3.03	379.0	.030
S3			734.3	2387.0	3.20	428.0	.030
S3			735.3	2831.0	3.41	463.0	.030
S3			736.3	3311.0	3.55	497.0	.030
S3			737.3	3824.0	3.73	527.0	.030
S3			738.3	4370.0	3.86	575.0	.030
S3			739.3	4985.0	3.99	634.0	.030
S3			740.3	5632.0	4.20	659.0	.030
S3			742.3	7002.0	4.58	709.0	.030
S3			744.3	8458.0	5.02	742.0	.030
S3	50	26.3	722.7	0.	0.	0.	.030
S3			722.8	1.0	.22	9.0	.030
S3			723.2	8.0	.45	26.0	.030
S3			723.7	22.0	.62	45.0	.030
S3			724.7	92.0	1.00	94.0	.030
S3			725.7	219.0	1.22	167.0	.030
S3			726.7	436.0	1.38	265.0	.030
S3			727.7	751.0	1.58	365.0	.030
S3			728.7	1158.0	1.86	441.0	.030
S3			729.7	1628.0	2.17	496.0	.030
S3			730.7	2254.0	2.19	729.0	.030
S3			731.7	3038.0	2.44	809.0	.030
S3			732.7	3867.0	2.74	858.0	.030
S3			733.7	4756.0	3.00	913.0	.030
S3			734.7	5699.0	3.23	981.0	.030
S3			735.7	6697.0	3.45	1022.0	.030
S3			736.7	7750.0	3.68	1067.0	.030
S3			737.7	8825.0	3.97	1083.0	.030
S3			739.7	11032.0	4.51	1117.0	.030
S3			741.7	13278.0	5.08	1129.0	.030
S3	50	24.2	721.6	0.	0.	0.	.030
S3			721.8	6.0	.22	56.0	.030
S3			722.2	50.0	.47	150.0	.030
S3			722.6	118.0	.69	190.0	.030
S3			723.6	354.0	1.13	270.0	.030
S3			724.6	656.0	1.41	358.0	.030
S3			725.6	1079.0	1.60	484.0	.030
S3			726.6	1606.0	1.88	568.0	.030
S3			727.6	2215.0	2.16	648.0	.030
S3			728.6	2903.0	2.41	730.0	.030
S3			729.6	3687.0	2.62	834.0	.030
S3			730.6	4563.0	2.87	914.0	.030
S3			731.6	5511.0	3.10	994.0	.030
S3			732.6	6555.0	3.32	1081.0	.030
S3			733.6	7684.0	3.50	1191.0	.030
S3			734.6	8885.0	3.80	1211.0	.030
S3			735.6	10105.0	4.09	1229.0	.030
S3			736.6	11341.0	4.38	1242.0	.030

S3			738.6	13849.0	4.93	1266.0	.030			
S3			740.6	16405.0	5.45	1289.0	.030			
S4		854	835	870	835	775	743	742	741	740
S4		739.5								
KR			0.10		1.463					
KR			0.15		1.463					
KR			0.20		1.463					
KR			0.25		1.463					
CT	10	740101	40.	3.	0.					
CT		740318	45.	3.	0.					
CT		740723	50.	3.	0.					
CT		741017	45.	3.	0.					
CT		741206	40.	3.	0.					
CT		-741231	40.	3.	0.					
CT		740101	150.	1.	0.					
CT		-741231	150.	1.	0.					
CT		740101	0.1	1.	0.					
CT		-741231	0.1	1.	0.					
CT		740101	5.	0.	30.					
CT		-741231	5.	0.	30.					
CT	20	740101	45	4	0					
CT		740318	50	4	0					
CT		740723	55	4	0					
CT		741017	50	4	0					
CT		741206	45	4	0					
CT		-741231	42	4	0					
CT		740101	160	.8	0					
CT		-741231	160	.8	0					
CT		740101	.05	.15	0					
CT		-741231	.05	.15	0					
CT		740101	4	0	50					
CT		-741231	4	0	50					
CT	30	740101	45.	3.	0.	10	20			
CT		740510	50.	3.	0.					
CT		740531	60.	3.	0.					
CT		741001	55.	3.	0.					
CT		-741231	45.	3.	0.					
CT		740101	160.	1.	0.					
CT		-741231	160.	1.	0.					
CT		740101	.15	4.	0.					
CT		-741231	.15	4.	0.					
CT		740101	4.5	4.	0.					
CT		-741231	4.5	4.	0.					
CT	40	740101	45.	3.	0.	10	20			
CT		740504	50.	3.	0.					
CT		740514	55.	3.	0.					
CT		740515	60.	3.	0.					
CT		741005	55.	3.	0.					
CT		741109	50.	3.	0.					
CT		741214	45.	3.	0.					
CT		-741231	45.	3.	0.					
CT		740101	170.	1.	0.					
CT		-741231	170.	1.	0.					



CT	740101	0.2	1.	0.			
CT	-741231	0.2	1.	0.			
CT	740101	5.5	0.	30.			
CT	-741231	5.5	0.	30.			
CT	50 740101	50.	3.	0.	10	20	
CT	740506	55.	3.	0.			
CT	740510	60.	3.	0.			
CT	740515	65.	3.	0.			
CT	740708	70.	3.	0.			
CT	740924	65.	3.	0.			
CT	741018	60.	3.	0.			
CT	741112	55.	3.	0.			
CT	741206	50.	3.	0.			
CT	-741231	50.	3.	0.			
CT	740101	190.	1.	0.			
CT	-741231	190.	1.	0.			
CT	740101	0.3	1.	0.			
CT	-741231	0.3	1.	0.			
CT	740101	6.0	0.	30.			
CT	-741231	6.0	0.	30.			
I1	740101	741231					
I2		0	TRIB 1 ...	LEFT INFLOW RATE ...	RES # 1		
I4	740101	-0.5	740408	-0.5	740422	-0.7	740708 -0.3
I4	740826	-0.3	741231	-0.5	-1		
I2	2	0	TRIB 1 ...	LEFT INFLOW TEMPERATURE			
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0	TRIB 1 ...	LEFT INFLOW - TOTAL DISSOLVED SOLIDS			
I4	740101	105.	741231	105.	-1		
I2		0	TRIB 1 ...	LEFT INFLOW - CARBONACEOUS BOD			
I4	740101	0.5	741231	0.5	-1		
I2		0	TRIB 1 ...	LEFT INFLOW - DISSOLVED OXYGEN			
I4	740101	12.8	740115	13.1	740215	12.4	740315 11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715 8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115 11.0
I4	741215	12.4	741231	12.8	-1		
I2		0	TRIB 2 ...	RIGHT INFLOW RATE ...	RES # 1		
I4	740101	-0.5	740408	-0.5	740422	-0.7	740708 -0.7
I4	740826	-0.7	741231	-0.5	-1		
I2	2	0	TRIB 2 ...	RIGHT INFLOW TEMPERATURE			
I4	740101	-0.1	740125	2.0	740210	1.2	740224 -1.8
I4	740310	0.1	740324	-10.4	740414	-15.8	740428 -24.3
I4	740512	-15.6	740527	-16.0	740609	-11.0	740623 -15.6
I4	740714	-9.1	740728	-12.3	740811	-10.3	740825 -15.0
I4	740908	-15.5	740922	-17.8	741014	-11.1	741028 -6.1
I4	741110	-6.5	741124	-4.4	741208	-6.2	741231 1.5
I4	-1						
I2		0	TRIB 2 ...	RIGHT INFLOW - TDS			
I4	740101	140	740115	110	740215	240	740315 400
I4	740415	130	740515	1095	740615	80	740715 100
I4	740815	70	740915	50	741015	100	741115 90
I4	741215	310	741231	360	-1		
I2		0	TRIB 2 ...	RIGHT INFLOW - CBOD			
I4	740101	.2	740115	.2	740215	.4	740315 .5

I4	740415	.2	740515	1.8	740615	.1	740715	.2
I4	740815	.1	740915	.1	741015	.2	741115	.1
I4	741215	.5	741231	.6	-1			
I2		0	TRIB 2 ... RIGHT INFLOW - DISSOLVED OXYGEN					
I4	740101	13.1	740115	13.1	740215	12.4	740315	11.8
I4	740415	11.8	740515	9.4	740615	9.0	740715	8.3
I4	740815	7.8	740915	9.7	741015	10.0	741115	11.0
I4	741215	12.4	741231	12.8	-1			
I2		0	TRIB 3 INFLOW RATE - RM 45 & RES # 2					
I4	740101	-1	741231	-1.	-1			
I2	1	0	TRIB 3 - RM 45					
I4	740101	-1.5	740408	-1.5	740422	-3.0	740708	-4.
I4	740826	-3.	741231	-1.5	-1			
I2		0	TRIB 3 - RM 45 - TOTAL DISSOLVED SOLIDS					
I4	740101	160.	741231	160.	-1			
I2		0	TRIB 3 - RM 45 - CARBONACEOUS BOD					
I4	740101	0.6	741231	0.6	-1			
I2		0	TRIB 3 - RM 45 - DISSOLVED OXYGEN					
I4	740101	12.8	740115	13.1	740215	12.4	740315	11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715	8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115	11.0
I4	741215	12.4	741231	12.8	-1			
I2		0	TRIB 4 INFLOW RATE - RM 30					
I4	740826	-1.	741231	-1.	-1			
I2	1	0	TRIB 4 - RM 30					
I4	740101	-1.5	740408	-1.5	740422	-3.0	740708	-6.
I4	740826	-5.	741231	-1.5	-1			
I2		0	TRIB 4 - RM 30 - TOTAL DISSOLVED SOLIDS					
I4	740101	160.	741231	160.	-1			
I2		0	TRIB 4 - RM 30 - CARBONACEOUS BOD					
I4	740101	0.6	741231	0.6	-1			
I2		0	TRIB 4 - RM 30 - DISSOLVED OXYGEN					
I4	740101	12.8	740115	13.1	740215	12.4	740315	11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715	8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115	11.0
I4	741215	12.4	741231	12.8	-1			

ER

```

*****
* HEC-5Q SIMULATION OF FLOOD CONTROL AND CONSERVATION SYSTEMS *
* (INCLUDING WATER QUALITY ANALYSIS) *
* OCTOBER 1985 *
*
* RUN DATE 16 MAY 86 TIME 9:42:40
*****

```

```

*****
* U.S. ARMY CORPS OF ENGINEERS *
* THE HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET, SUITE D *
* DAVIS, CALIFORNIA 95616 *
* (916) 551-1748 (FTS) 460-1748 *
*****

```

```

X X XXXXXX XXXX XXX
X X X X X X X X
X X X X X X X X
XXXXXX XXXX X XXXX XXXX X X
X X X X X X X X
X X X X X X X X
X X XXXXXX XXXX XXXX

```

```

*****
*
*
*
* MODELING CAPABILITIES OF THIS VERSION ARE:
* MAXIMUM NUMBER OF RESERVOIRS=15, CONTROL POINTS=25, DIVERSIONS=10, POWER PLANTS= 7
*
* INPUT INSTRUCTIONS FOR THE FIRST FIELD OF THE CC CARD HAVE BEEN CHANGED. SEE THE
* OCTOBER 1984 OR THE JANUARY 1985 EXHIBIT 8 (HEC-5 USERS MANUAL) FOR NEW INPUT.
*
*****

```

HEC-5 SIMULATION OF FLOOD CONTROL  
AND CONSERVATION SYSTEMS

SEGMENTED VERSION (UPDATED MARCH 1985)

MAX DIMENSION LIMITS ARE CURRENTLY SET AT 15 RESERVOIRS AND 25 CONTROL POINTS

\*INPUT LISTING FROM PRERD

TO SUPPRESS LISTING, INSERT NOLIST CARD INTO INPUT DECK AT DESIRED POINT

T1 TESTING HEC5Q WATER QUALITY SIMULATION CAPABILITY

T2 PARALLEL RIVER SYSTEM

T3 TEST PROBLEM 1

J1	0	5	5	3	4	2	0	0
J2	36	0	0	0	0	0	0	0
J9								

RL	10	1200000	0	100000	200000	1500000	1600000	
RO	3	30	40	50				
RS	7	100	6300	31300	88000	188000	563000	1688000
RQ	7	0	20000	30000	40000	50000	50000	50000
RA	7	10	500	1500	3000	5000	10000	20000
RE	7	800	825	850	870	900	950	1030
R3	2	2	2	2	99	99	99	99
R3	99	99						

CP 10 20000 300 200

IDCP10-BAKER DAM

RT 10 30 2.2 .25 12 0

RL	20	550000	0	2000	550000	952000	1130000	
RO	3	30	40	50				
RS	8	2000	20000	52000	113000	209000	320000	550000
RQ	8	0	5680	5680	5680	5680	5680	29180
RA	8	150	2100	4500	7600	11800	17000	22400
RE	8	892	910	920	930	940	950	962.5
R3	2	2	2	2	99	99	99	99
R3	99	99						

CP 20 20000 30 20

IDCP20-SMITH DAM

RT 20 30 2.2 .25 12 0

CP 30 30000 300 200

IDCP30-CONF RM60

RT 30 40 2.2 .25 12 0

CP 40 30000 300 200

ID CP40 \*\* RM 40

RT 40 50 2.2 .25 12 0

CP 50 50000 300 200

IDCP50 \*\* RM24.2

RT 50 0 0 0 0 0

ED

BF 0 120 0 074050100 120 24

NOLIST

START COMPUTATIONS FOR JOB NUMBER 1 FOR 1 FLOODS READ

NRES= 2 NCPT= 5

FIXED DIM. - DIVS.= 10 PUR.= 7

DYNAMIC DIM. - RES = 2 CPTS.= 5 PERS.= 121

NOTE \*\* RA, RE AND R3 CARDS ARE REQUIRED FOR TEMPERATURE SIMULATION

MX= 10 IF MUSK ROUT K LESS THAN 16.00

\*\*\* CAUTION \*\*\*

NOTE \*\*\* RA, RE AND R3 CARDS ARE REQUIRED FOR TEMPERATURE SIMULATION

MX= 20 IF MUSK ROUT K LESS THAN 16.00

\*\*\* CAUTION \*\*\*

MX= 30 IF MUSK ROUT K LESS THAN 16.00

\*\*\* CAUTION \*\*\*

MX= 40 IF MUSK ROUT K LESS THAN 16.00

\*\*\* CAUTION \*\*\*

\*FLOWS

FLOFMT NPER NPSTO CNSTI FLDAT EPER IPER . MINPER NDAYWK ONESUM

BF	0.	120.	0.	0.00	74050100.	120.	24	0	0.	0.		
IN	10	1MAY74	2059.0	1814.0	2125.0	2243.0	1947.0	1836.0	1735.0	1587.0	1549.0	1509.0
			1413.0	4584.0	7520.0	5061.0	3549.0	2931.0	2801.0	3866.0	2752.0	2293.0
			1962.0	1793.0	2476.0	2528.0	1958.0	1650.0	1462.0	1344.0	1810.0	3581.0
			3367.0	7629.0	5501.0	3699.0	3057.0	2603.0	2294.0	2073.0	1894.0	1750.0
			1596.0	1423.0	1313.0	1251.0	1052.0	1312.0	2547.0	2301.0	1803.0	1360.0
			1185.0	1200.0	1456.0	2434.0	4601.0	3121.0	2769.0	2230.0	1846.0	2107.0
			1918.0	15259.0	7046.0	4185.0	3113.0	3167.0	2814.0	2295.0	1910.0	1606.0
			1448.0	1535.0	1368.0	1196.0	1039.0	1032.0	1013.0	940.0	890.0	890.0
			865.0	826.0	783.0	826.0	928.0	847.0	788.0	829.0	804.0	806.0
			945.0	801.0	712.0	751.0	914.0	911.0	935.0	792.0	747.0	717.0
			823.0	1416.0	997.0	806.0	759.0	732.0	683.0	653.0	633.0	639.0
			621.0	644.0	604.0	598.0	598.0	596.0	601.0	642.0	662.0	838.0
												SUM=
												234248.
IN	20	1MAY74	430.0	816.0	668.0	1979.0	1523.0	1195.0	1065.0	847.0	698.0	569.0
			455.0	402.0	472.0	424.0	415.0	956.0	613.0	510.0	434.0	381.0
			361.0	327.0	289.0	338.0	758.0	355.0	262.0	202.0	169.0	133.0
			163.0	192.0	203.0	181.0	166.0	212.0	1017.0	639.0	639.0	366.0
			255.0	194.0	236.0	596.0	432.0	284.0	251.0	745.0	348.0	226.0
			179.0	198.0	198.0	164.0	155.0	159.0	177.0	888.0	348.0	386.0
			197.0	133.0	134.0	141.0	181.0	407.0	212.0	145.0	126.0	122.0
			112.0	108.0	89.0	80.0	87.0	80.0	69.0	68.0	64.0	58.0
			47.0	53.0	49.0	39.0	43.0	46.0	60.0	60.0	56.0	50.0
			49.0	41.0	43.0	39.0	39.0	43.0	39.0	39.0	47.0	47.0
			49.0	43.0	47.0	96.0	151.0	112.0	473.0	212.0	297.0	405.0
			201.0	128.0	100.0	79.0	64.0	89.0	102.0	90.0	88.0	165.0
												SUM=
												34776.
IN	40	1MAY74	645.0	588.0	561.0	488.0	452.0	440.0	425.0	405.0	406.0	398.0
			380.0	923.0	1207.0	1171.0	1161.0	1075.0	1190.0	1601.0	1685.0	1941.0
			1849.0	1752.0	1784.0	1322.0	645.0	397.0	366.0	458.0	669.0	1011.0
			1113.0	1740.0	1529.0	1352.0	1273.0	1219.0	1171.0	908.0	575.0	431.0
			407.0	375.0	357.0	348.0	243.0	231.0	469.0	598.0	671.0	585.0
			369.0	237.0	288.0	360.0	546.0	768.0	900.0	874.0	829.0	712.0
			549.0	2648.0	1733.0	1751.0	1617.0	1671.0	1565.0	1433.0	922.0	465.0
			361.0	384.0	353.0	328.0	298.0	305.0	296.0	285.0	279.0	235.0
			143.0	142.0	139.0	150.0	226.0	282.0	276.0	191.0	106.0	139.0
			183.0	220.0	269.0	268.0	278.0	283.0	311.0	249.0	178.0	172.0
			162.0	177.0	135.0	119.0	117.0	117.0	130.0	164.0	161.0	166.0
			160.0	117.0	61.0	42.0	51.0	141.0	142.0	108.0	87.0	235.0
												SUM=
												73148.

IN	50	1MAY74	3317.0	3816.0	3333.0	3150.0	2843.0	2861.0	2976.0	2831.0	3011.0	3250.0
			3265.0	4695.0	13438.0	10915.0	9154.0	8282.0	7643.0	7539.0	6757.0	6013.0
			4768.0	3744.0	3530.0	3463.0	3178.0	2914.0	2592.0	2150.0	1941.0	1852.0
			1735.0	1747.0	1903.0	2065.0	1847.0	1399.0	1148.0	1035.0	978.0	844.0
			714.0	809.0	784.0	873.0	969.0	816.0	1405.0	1972.0	2159.0	1563.0
			1308.0	1482.0	1621.0	1469.0	1155.0	1353.0	975.0	1469.0	1483.0	1761.0
			1469.0	4196.0	7637.0	5846.0	5734.0	4803.0	4285.0	3660.0	3314.0	2783.0
			1990.0	1912.0	1651.0	1441.0	937.0	893.0	1209.0	1028.0	980.0	990.0
			1160.0	785.0	550.0	695.0	679.0	705.0	701.0	786.0	566.0	627.0
			774.0	742.0	696.0	661.0	613.0	578.0	630.0	914.0	930.0	930.0
			918.0	981.0	1006.0	881.0	924.0	829.0	857.0	780.0	684.0	606.0
			637.0	670.0	578.0	562.0	558.0	486.0	458.0	440.0	621.0	825.0
												SUM=
												265843.
QA	10	1MAY74	1270.0	1320.0	1360.0	1410.0	1440.0	1470.0	1480.0	1480.0	1480.0	1480.0
			1790.0	2190.0	2480.0	3480.0	4490.0	4420.0	4300.0	4210.0	4130.0	3960.0
			3720.0	3370.0	2470.0	1910.0	1950.0	1940.0	1890.0	1570.0	1270.0	1680.0
			2210.0	2480.0	4000.0	5510.0	5350.0	4400.0	2930.0	1970.0	1570.0	1570.0
			1570.0	1560.0	1560.0	1530.0	1510.0	1480.0	1830.0	2690.0	3120.0	2840.0
			1640.0	819.0	854.0	900.0	1540.0	2750.0	3250.0	2860.0	2100.0	2030.0
			2030.0	3600.0	9280.0	11000.0	7280.0	4130.0	3250.0	2180.0	1750.0	1470.0
			1210.0	1290.0	1320.0	1320.0	1290.0	1270.0	1230.0	948.0	570.0	600.0
			610.0	610.0	621.0	631.0	642.0	707.0	764.0	753.0	741.0	730.0
			730.0	741.0	730.0	719.0	707.0	707.0	775.0	775.0	819.0	786.0
			494.0	819.0	865.0	654.0	865.0	831.0	797.0	764.0	719.0	685.0
			494.0	631.0	580.0	521.0	346.0	540.0	486.0	486.0	521.0	600.0
												SUM=
												225847.
QA	20	1MAY74	1236.0	521.0	387.0	405.0	442.0	949.0	1602.0	1572.0	1528.0	1040.0
			600.0	593.0	590.0	488.0	390.0	497.0	600.0	600.0	597.0	495.0
			310.0	220.0	220.0	220.0	226.0	325.0	420.0	417.0	403.0	400.0
			286.0	165.0	110.0	110.0	110.0	110.0	275.0	540.0	637.0	627.0
			518.0	420.0	420.0	420.0	420.0	320.0	227.0	330.0	430.0	423.0
			226.0	110.0	110.0	110.0	110.0	105.0	316.0	440.0	440.0	437.0
			430.0	226.0	110.0	110.0	110.0	110.0	110.0	110.0	110.0	105.0
			110.0	110.0	110.0	110.0	110.0	110.0	110.0	110.0	110.0	110.0
			110.0	110.0	110.0	110.0	75.0	35.0	35.0	35.0	35.0	35.0
			35.0	35.0	35.0	35.0	35.0	35.0	35.0	35.0	35.0	35.0
			35.0	35.0	36.0	38.0	62.0	85.0	105.0	125.0	182.0	240.0
			240.0	240.0	235.0	230.0	178.0	125.0	125.0	125.0	125.0	125.0
												SUM=
												33957.
EJ		0.00										

\*INTAB

J1	METRIC	ISTMO	NULEV	LEVCON	LEVTFC	LEVBUF	LEVPBS
0		5	5	3	4	2	3
J2	IFCAST	CFLOD	RATCHG	IPRIO	IOPMD	ISCHED	NCPTR
1		1.00	0.96	0	0	0	0
J3	IPRINT	PRCOL	IPLOTJ	FLONAT	CRITPR	ILOCAL	NOROUT
511		130.	0	0.	0.	0	24
J4	IANDAM	ECFCT	IPREC	BCRFAC	COSFAC	PCVAL	PEPVAL
0		1.0	0	1.00	1.00	0.0	0.0
						0.0	0.0

USER ID	QMAX	QMDRAT	QMIN	QMINR	LQCP	RTLQ	QLAG
10	20000.	1.	300.	200.	0	0.000	0.CP10-BAKER DAM
20	20000.	1.	30.	20.	0	0.000	0.CP20-SMITH DAM
30	30000.	1.	300.	200.	0	0.000	0.CP30-CONF RM60
40	30000.	1.	300.	200.	0	0.000	0. CP40 ** RM 40
50	50000.	1.	300.	200.	0	0.000	0.CP50 ** RM24.2

USER ID	COMP ID	RTFR	RTTO	RTMD	X	K	LAG
10	1	10.	30.	2.20	0.25	12.000	0
20	2	20.	30.	2.20	0.25	12.000	0
30	3	30.	40.	2.20	0.25	12.000	0
40	4	40.	50.	2.20	0.25	12.000	0
50	5	50.	0.	0.00	0.00	0.000	0

USER ID	COMP ID	STOR1	STORL-1	-2	-3	-4	-5
10	1	1200000.	0.	100000.	200000.	1500000.	1600000.
20	2	5500000.	0.	2000.	5500000.	9520000.	11300000.

USER ID LOCATIONS RESERVOIR IS SERVING

10	10.	30.	40.	50.
20	20.	30.	40.	50.



RESERVOIR DATA

USER ID=	10	COMP ID=	1				
RS	STORAGES=	100.	6300.	31300.	88000.	188000.	
		563000.	1688000.				
RQ	Q CAPACITIES=	0.	20000.	30000.	40000.	50000.	
		50000.	50000.				
RA	AREAS=	10.	500.	1500.	3000.	5000.	
		10000.	20000.				
RE	ELEVATIONS=	800.00	825.00	850.00	870.00	900.00	
		950.00	1030.00				
USER ID=	20	COMP ID=	2				
RS	STORAGES=	2000.	20000.	52000.	113000.	209000.	
		320000.	550000.	800000.			
RQ	Q CAPACITIES=	0.	5680.	5680.	5680.	5680.	
		5680.	29180.	59680.			
RA	AREAS=	150.	2100.	4500.	7600.	11800.	
		17000.	22400.	28600.			
RE	ELEVATIONS=	892.00	910.00	920.00	930.00	940.00	
		950.00	962.50	970.00			

DATA FROM HYDRAULIC ROUTINE

\* TITLE  
TESTING HEC5Q WATER QUALITY SIMULATION CAPABILITY  
PARALLEL RIVER SYSTEM  
TEST PROBLEM 1

\* METRIC 0

\* RESERVOIR C.P. 10

\* NELV, CAPIN 7 1200000.

\* ELEVAC, CAPCTY, SURARA  
800.0 100.0 10.0  
825.0 6300.0 500.0  
850.0 31300.0 1500.0  
870.0 88000.0 3000.0  
900.0 188000.0 5000.0  
950.0 563000.0 10000.0  
1030.0 1688000.0 20000.0

\* RESERVOIR C.P. 20

\* NELV, CAPIN 8 550000.

\* ELEVAC, CAPCTY, SURARA  
892.0 2000.0 150.0  
910.0 20000.0 2100.0  
920.0 52000.0 4500.0  
930.0 113000.0 7600.0  
940.0 209000.0 11800.0  
950.0 320000.0 17000.0  
962.5 550000.0 22400.0  
970.0 800000.0 28600.0

FICTICIOUS PARALLEL RIVER BASIN TEST OF HEC-5Q WITH WATER QUALITY  
 RESERVOIRS ARE FICTICIOUS ALSO \*\* C.P. OF 10, 20, 30, 40 AND 50  
 CONSTITUENTS ARE TEMPERATURE, TDS, CARBONACEOUS BOD AND OXYGEN

DAYS OF SIMULATION	123
FIRST DAY OF SIMULATION	121 (74/ 5/ 1)
FINAL DAY OF SIMULATION	243 (74/ 8/31)
NUMBER OF CONTROL POINTS	5
NUMBER OF RESERVOIRS	2
INPUT UNITS (ENGLISH=0/METRIC=1)	0
WATER TEMPERATURE UNITS	F

IN ADDITION TO TEMPERATURE, THE FOLLOWING CONSTITUENTS ARE BEING SIMULATED. (EXCEPT AS NOTED)

TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY  
 CARBONACEOUS BOD IN MG/L  
 DISSOLVED OXYGEN IN MG/L

\*\*\*\*\* INDICATES QUALITY DATA WILL BE READ BUT NOT SIMULATED

# RESERVOIR RELATED DATA

PRINTOUT INTERVAL, DAYS 10  
 VERTICAL LAYER PRINTOUT INTERVAL 1

RESERVOIR NUMBER 1

CONTROL POINT I.D. 10

LAYER THICKNESS, FT 5.0  
 MAXIMUM WATER SURFACE ELEVATION, FT 1030.0  
 BOTTOM ELEVATION, FT 800.0  
 STARTING RESERVOIR VOLUME, ACFT 1200000.  
 SECCHI DISK DEPTH, FT 10.0  
 DEPTH OF INITIAL SOLAR ENERGY ABSORPTION, FT 1.00  
 FRACTION OF SOLAR ENERGY ABSORBED 0.40  
 METEOROLOGICAL DATA ZONE 2  
 INFLOW I.D. EFFECTIVE RES. LENGTH, FT 2  
 10000.  
 5000.

WATER COLUMN MINIMUM STABILITY, KG/M3/M 0.10E-01  
 WATER COLUMN CRITICAL STABILITY (GSHH), KG/M3/M 0.10E-05  
 MAXIMUM ALLOWABLE DISPERSION (A1), M2/SEC 0.10E-03  
 COEFFICIENT RELATING GRADIENT TO DISPERSION (A3) -0.70E+00

## OUTLET CHARACTERISTICS

	VIRTUAL WIDTH, FT	MAXIMUM FLOW, CFS	ELEMENT	ELEVATION, FT
F.C. OUTLET	50.00	50000.00	6	825.00
WET WELL 1	10.00	2000.00	5	820.00
			13	860.00
			21	900.00
			29	940.00
WET WELL 2	10.00	2000.00	9	840.00
			17	880.00
			25	920.00
			33	960.00

## GATE SELECTION SUBOPTIMIZATION FUNCTION

CONSTITUENT	WEIGHTING	POLYNOMIAL FUNCTION COEFFICIENTS
1	2.50E-01	1.00E+02 0.00E+00 -4.00E+00
2	5.00E-02	1.00E+02 0.00E+00 -2.00E-01
6	2.00E-01	1.00E+02 0.00E+00 -8.00E+00
8	2.50E-01	1.00E+02 3.20E+00 -7.00E-01
		1.00E-01 -5.00E-02

# RESERVOIR GEOMETRY AND INITIAL TEMPERATURE

ELEMENT	ELEVATION FT	AREA ACRE	VOLUME ACFT	ELEMENT VOL ACFT	WIDTH FT	TEMPERATURE F
1	800.0	10.	100.	388.	200.	40.00
2	805.0	105.	388.	764.	240.	40.20
3	810.0	200.	1152.	1240.	280.	40.40
4	815.0	296.	2392.	1716.	320.	40.60
5	820.0	391.	4108.	2192.	360.	40.80
6	825.0	486.	6300.	2944.	400.	41.00
7	830.0	692.	9244.	3972.	480.	41.20
8	835.0	897.	13216.	5000.	560.	41.40
9	840.0	1103.	18216.	6028.	640.	41.60
10	845.0	1308.	24244.	7056.	720.	41.80
11	850.0	1514.	31300.	9221.	800.	42.00
12	855.0	2175.	40521.	12524.	950.	42.25
13	860.0	2835.	53045.	15826.	1100.	42.50
14	865.0	3495.	68871.	19129.	1250.	42.75
15	870.0	4156.	88000.	20094.	1400.	43.00
16	875.0	3882.	108094.	18723.	1500.	43.33
17	880.0	3608.	126818.	17352.	1600.	43.67
18	885.0	3333.	144170.	15981.	1700.	44.00
19	890.0	3059.	160151.	14610.	1800.	44.33
20	895.0	2785.	174761.	13239.	1900.	44.67
21	900.0	2511.	188000.	15048.	2000.	45.00
22	905.0	3509.	203048.	20037.	2100.	45.30
23	910.0	4506.	223085.	25027.	2200.	45.60
24	915.0	5504.	248112.	30016.	2300.	45.90
25	920.0	6502.	278128.	35005.	2400.	46.20
26	925.0	7500.	313133.	39995.	2500.	46.50
27	930.0	8498.	353128.	44984.	2600.	46.80
28	935.0	9496.	398112.	49973.	2700.	47.10
29	940.0	10494.	448085.	54963.	2800.	47.40
30	945.0	11491.	503048.	59952.	2900.	47.70
31	950.0	12489.	563000.	62938.	3000.	48.00
32	955.0	12686.	625938.	63922.	3125.	48.75
33	960.0	12883.	689860.	64905.	3250.	49.50
34	965.0	13079.	754765.	65888.	3375.	50.25
35	970.0	13276.	820652.	66871.	3500.	51.00
36	975.0	13473.	887524.	67854.	3625.	51.75
37	980.0	13669.	955378.	68838.	3750.	52.50
38	985.0	13866.	1024216.	69821.	3875.	53.25
39	990.0	14062.	1094037.	70804.	4000.	54.00
40	995.0	14259.	1164841.	71787.	4125.	54.75
41	1000.0	14456.	1236628.	72771.	4250.	55.50
42	1005.0	14652.	1309399.	73754.	4375.	56.25
43	1010.0	14849.	1383152.	74737.	4500.	57.00
44	1015.0	15046.	1457890.	75720.	4625.	57.75
45	1020.0	15242.	1533610.	76703.	4750.	58.50
46	1025.0	15439.	1610313.	77687.	4875.	59.25
47	1030.0	15636.	1688000.	77687.	5000.	60.00

## INITIAL RESERVOIR WATER QUALITY DATA

ELEMENT	ELEV	CONS.1	CONS.2	CONS.3	NONCONS.1	NONCONS.2(NBOD)	NONCONS.3(CBOD)	OXYGEN	O2 SOURCE/SINK
1	800.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
2	805.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
3	810.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
4	815.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
5	820.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
6	825.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
7	830.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
8	835.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
9	840.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
10	845.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
11	850.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
12	855.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
13	860.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
14	865.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
15	870.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
16	875.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
17	880.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
18	885.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
19	890.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
20	895.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
21	900.0	120.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
22	905.0	126.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
23	910.0	132.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
24	915.0	138.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
25	920.0	144.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
26	925.0	150.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
27	930.0	156.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
28	935.0	162.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
29	940.0	168.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
30	945.0	174.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
31	950.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
32	955.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
33	960.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
34	965.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
35	970.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
36	975.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
37	980.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
38	985.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
39	990.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
40	995.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
41	1000.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
42	1005.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
43	1010.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
44	1015.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
45	1020.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
46	1025.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00
47	1030.0	180.00	0.00	0.00	0.00	0.50	0.00	9.1	100.00

CONSTITUENT NO. 1 IS TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY  
 CONSTITUENT NO. 2 IS NOT BEING SIMULATED  
 CONSTITUENT NO. 3 IS NOT BEING SIMULATED  
 CONSTITUENT NO. 4 IS NOT BEING SIMULATED  
 CONSTITUENT NO. 5 IS CARBONACEOUS BOD IN MG/L  
 CONSTITUENT NO. 6 IS NOT BEING SIMULATED  
 CONSTITUENT NO. 7 IS DISSOLVED OXYGEN IN MG/L

DECAY RATES AND CONVERSION FACTORS ARE

CONSTITUENT NO. 4 DECAY RATE = 0.0000  
 CONSTITUENT NO. 5 DECAY RATE = 0.1000  
 CONSTITUENT NO. 6 DECAY RATE = 0.0000  
 CONSTITUENT NO. 5 CONVERSION FACTOR = 1.4630  
 CONSTITUENT NO. 6 CONVERSION FACTOR = 2.2700

RESERVOIR NUMBER 2

CONTROL POINT I.D.

20

LAYER THICKNESS, FT 2.0  
 MAXIMUM WATER SURFACE ELEVATION, FT 970.0  
 BOTTOM ELEVATION, FT 892.0  
 STARTING RESERVOIR VOLUME, ACFT 550000.  
 SECCHI DISK DEPTH, FT 5.0  
 DEPTH OF INITIAL SOLAR ENERGY ABSORPTION, FT 1.00  
 FRACTION OF SOLAR ENERGY ABSORBED 0.40  
 METEOROLOGICAL DATA ZONE 1  
 INFLOW I.D. EFFECTIVE RES. LENGTH, FT 1  
 3 60000.  
 WATER COLUMN MINIMUM STABILITY, KG/M3/M 0.10E-01  
 WATER COLUMN CRITICAL STABILITY (GSHH), KG/M3/M 0.10E-05  
 MAXIMUM ALLOWABLE DISPERSION (A1), M2/SEC 0.10E-03  
 COEFFICIENT RELATING GRADIENT TO DISPERSION (A3) -0.70E+00

## OUTLET CHARACTERISTICS

	VIRTUAL WIDTH, FT	MAXIMUM FLOW, CFS	ELEMENT	ELEVATION, FT
F.C. OUTLET	1.00	10.00	3	895.50
SPILLWAY	870.00	99300.00	36	962.50
WET WELL 1	7.90	2840.00	3	895.50
			10	909.50
			17	923.50
			24	937.50
WET WELL 2	7.90	2840.00	6	902.50
			13	916.50
			20	930.50
			27	944.50

## GATE SELECTION SUBOPTIMIZATION FUNCTION

CONSTITUENT	WEIGHTING	POLYNOMIAL FUNCTION COEFFICIENTS
1	2.50E-01	1.00E+02 0.00E+00 -4.00E+00
2	5.00E-02	1.00E+02 0.00E+00 -2.00E-01
6	2.00E-01	1.00E+02 0.00E+00 -8.00E+00
8	2.50E-01	1.00E+02 3.20E+00 -7.00E-01
		1.00E-01 -5.00E-02



# RESERVOIR GEOMETRY AND INITIAL TEMPERATURE

ELEMENT	ELEVATION FT	AREA ACRE	VOLUME ACFT	ELEMENT VOL ACFT	WIDTH FT	TEMPERATURE F
1	892.0	150.	2000.	2489.	410.	54.00
2	894.0	339.	2489.	867.	416.	54.11
3	896.0	528.	3356.	1244.	421.	54.22
4	898.0	717.	4600.	1622.	427.	54.33
5	900.0	906.	6222.	2000.	432.	54.44
6	902.0	1094.	8222.	2378.	438.	54.56
7	904.0	1283.	10600.	2756.	443.	54.67
8	906.0	1472.	13356.	3133.	449.	54.78
9	908.0	1661.	16489.	3511.	454.	54.89
10	910.0	1850.	20000.	4240.	460.	55.00
11	912.0	2390.	24240.	5320.	468.	55.40
12	914.0	2930.	29560.	6400.	476.	55.80
13	916.0	3470.	35960.	7480.	484.	56.20
14	918.0	4010.	43440.	8560.	492.	56.60
15	920.0	4550.	52000.	9720.	500.	57.00
16	922.0	5170.	61720.	10960.	510.	57.00
17	924.0	5790.	72680.	12200.	520.	57.00
18	926.0	6410.	84880.	13440.	530.	57.00
19	928.0	7030.	98320.	14680.	540.	57.00
20	930.0	7650.	113000.	16080.	550.	57.00
21	932.0	8430.	129080.	17640.	560.	57.00
22	934.0	9210.	146720.	19200.	570.	57.00
23	936.0	9990.	165920.	20760.	580.	57.00
24	938.0	10770.	186680.	22320.	590.	57.00
25	940.0	11550.	209000.	22920.	600.	57.00
26	942.0	11370.	231920.	22560.	610.	57.00
27	944.0	11190.	254480.	22200.	620.	57.00
28	946.0	11010.	276680.	21840.	630.	57.00
29	948.0	10830.	298520.	21480.	640.	57.00
30	950.0	10650.	320000.	23780.	650.	57.00
31	952.0	13130.	343780.	28740.	658.	57.00
32	954.0	15610.	372520.	33700.	666.	57.00
33	956.0	18090.	406220.	38660.	674.	57.00
34	958.0	20570.	444880.	43620.	682.	57.00
35	960.0	23050.	488500.	48580.	690.	57.00
36	962.0	25530.	537080.	54553.	698.	57.00
37	964.0	29023.	591633.	61878.	710.	57.00
38	966.0	32854.	653511.	69540.	723.	57.00
39	968.0	36686.	723051.	77202.	737.	57.00
40	970.0	40517.	800253.	77202.	750.	57.00

## INITIAL RESERVOIR WATER QUALITY DATA

ELEMENT	ELEV	CONS.1	CONS.2	CONS.3	NONCONS.1	NONCONS.2(NBOD)	NONCONS.3(CBOD)	OXYGEN	O2 SOURCE/SINK
1	892.0	160.00	0.00	0.00	0.00	0.30	0.00	8.4	100.00
2	894.0	163.33	0.00	0.00	0.00	0.30	0.00	8.4	100.00
3	896.0	166.67	0.00	0.00	0.00	0.30	0.00	8.5	100.00
4	898.0	170.00	0.00	0.00	0.00	0.30	0.00	8.5	100.00
5	900.0	173.33	0.00	0.00	0.00	0.30	0.00	8.5	100.00
6	902.0	176.67	0.00	0.00	0.00	0.30	0.00	8.6	100.00
7	904.0	180.00	0.00	0.00	0.00	0.30	0.00	8.6	100.00
8	906.0	183.33	0.00	0.00	0.00	0.30	0.00	8.6	100.00
9	908.0	186.67	0.00	0.00	0.00	0.30	0.00	8.7	100.00
10	910.0	190.00	0.00	0.00	0.00	0.30	0.00	8.7	100.00
11	912.0	190.00	0.00	0.00	0.00	0.30	0.00	8.8	100.00
12	914.0	190.00	0.00	0.00	0.00	0.30	0.00	8.8	100.00
13	916.0	190.00	0.00	0.00	0.00	0.30	0.00	8.9	100.00
14	918.0	190.00	0.00	0.00	0.00	0.30	0.00	9.0	100.00
15	920.0	190.00	0.00	0.00	0.00	0.30	0.00	9.1	100.00
16	922.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
17	924.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
18	926.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
19	928.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
20	930.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
21	932.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
22	934.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
23	936.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
24	938.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
25	940.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
26	942.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
27	944.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
28	946.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
29	948.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
30	950.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
31	952.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
32	954.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
33	956.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
34	958.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
35	960.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
36	962.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
37	964.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
38	966.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
39	968.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00
40	970.0	190.00	0.00	0.00	0.00	0.30	0.00	9.2	100.00

CONSTITUENT NO. 1 IS TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY  
 CONSTITUENT NO. 2 IS NOT BEING SIMULATED  
 CONSTITUENT NO. 3 IS NOT BEING SIMULATED  
 CONSTITUENT NO. 4 IS NOT BEING SIMULATED  
 CONSTITUENT NO. 5 IS CARBONACEOUS BOD IN MG/L  
 CONSTITUENT NO. 6 IS NOT BEING SIMULATED  
 CONSTITUENT NO. 7 IS DISSOLVED OXYGEN IN MG/L

DECAY RATES AND CONVERSION FACTORS ARE

CONSTITUENT NO. 4 DECAY RATE = 0.0000  
 CONSTITUENT NO. 5 DECAY RATE = 0.2000  
 CONSTITUENT NO. 6 DECAY RATE = 0.0000  
 CONSTITUENT NO. 5 CONVERSION FACTOR = 1.4630  
 CONSTITUENT NO. 6 CONVERSION FACTOR = 2.2700

THERMAL ADJUSTMENT FACTORS FOR

CONSTITUENT NO. 4 DECAY RATE = 1.0470  
 CONSTITUENT NO. 5 DECAY RATE = 1.0470  
 CONSTITUENT NO. 6 DECAY RATE = 1.0470  
 OXYGEN REAERATION RATE = 1.0159

# STREAM RELATED DATA

PRINTOUT INTERVAL, DAYS 10  
 PRINTOUT INTERVAL, ELEMENTS 1  
 CROSS SECTION PRINT CONTROL 0  
 NUMBER OF CROSS SECTIONS 10  
 POINTS DEFINING CROSS SECTION GEOMETRY 20  
 X-SECTION WIDTH ADJUSTMENT RATIO 1.00

## STREAM REACH DATA

REACH	UP STREAM CP. LOC.	DOWN STREAM CP. LOC.	ELT LENGTH MILE	TRIB LOCATIONS AND NUMBER
1	10 65.5	30 60.0	1.50	0 0.0 0 0.0 0
2	20 4.7	30 0.0	1.50	0 0.0 0 0.0 0
3	30 60.0	40 40.0	2.00	3 0.0 0 0.0 0
4	40 40.0	50 24.2	1.97	4 0.0 0 0.0 0

## METEOROLOGICAL AND REAERATION CONTROLS

ELEMENT	LOCATION	MET. ZONE	K2 METHOD	K2(1F SET)
1	64.81 10	2	(INPUT K2 DIRECTLY)	1.00
2	63.44	2	(INPUT K2 DIRECTLY)	1.00
3	62.06	2	(INPUT K2 DIRECTLY)	1.00
4	60.69 30	2	(INPUT K2 DIRECTLY)	1.00
5	3.92 20	1	(O'CONNER AND DOBBINS)	
6	2.35	1	(O'CONNER AND DOBBINS)	
7	0.78 30	1	(O'CONNER AND DOBBINS)	
8	59.00 30	1	(LANGBIEN AND DURUM)	
9	57.00	1	(LANGBIEN AND DURUM)	
10	55.00	1	(LANGBIEN AND DURUM)	
11	53.00	1	(LANGBIEN AND DURUM)	
12	51.00	1	(LANGBIEN AND DURUM)	
13	49.00	1	(LANGBIEN AND DURUM)	
14	47.00	1	(LANGBIEN AND DURUM)	
15	45.00	1	(LANGBIEN AND DURUM)	
16	43.00	1	(LANGBIEN AND DURUM)	
17	41.00 40	1	(LANGBIEN AND DURUM)	
18	39.01 40	1	(LANGBIEN AND DURUM)	
19	37.04	1	(LANGBIEN AND DURUM)	
20	35.06	1	(LANGBIEN AND DURUM)	
21	33.09	1	(LANGBIEN AND DURUM)	
22	31.11	1	(LANGBIEN AND DURUM)	
23	29.14	1	(LANGBIEN AND DURUM)	
24	27.16	1	(LANGBIEN AND DURUM)	
25	25.19 50	1	(LANGBIEN AND DURUM)	

REACH NO	DECAY RATES FOR STREAM REACHES			CONVERSION FACTORS
	CONS 4	CONS 5	CONS 6	
1	0.000	0.100	0.000	1.463 2.270
2	0.000	0.150	0.000	1.463 2.270
3	0.000	0.200	0.000	1.463 2.270
4	0.000	0.250	0.000	1.463 2.270

## CONTROL POINT 10

TEMPERATURE OBJECTIVES, F		WEIGHTING		RESERVOIRS SPECIFIED FOR FLOW AUGMENTATION CONTROL	
DATE	TARGET				
740101	40.00	3.00	0.00	0	0
740318	45.00	3.00	0.00	0	0
740723	50.00	3.00	0.00	0	0
741017	45.00	3.00	0.00	0	0
741206	40.00	3.00	0.00	0	0
-741231	40.00	3.00	0.00	0	0

## TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY

DATE	TARGET	WEIGHTING
740101	150.00	1.00
-741231	150.00	1.00

## CARBONACEOUS BOD IN MG/L

DATE	TARGET	WEIGHTING
740101	0.10	1.00
-741231	0.10	1.00

## DISSOLVED OXYGEN IN MG/L

DATE	TARGET	WEIGHTING
740101	5.00	0.00
-741231	5.00	0.00

## CONTROL POINT 20

TEMPERATURE OBJECTIVES, F		WEIGHTING		RESERVOIRS SPECIFIED FOR FLOW AUGMENTATION CONTROL	
DATE	TARGET				
740101	45.00	4.00	0.00	0	0
740318	50.00	4.00	0.00	0	0
740723	55.00	4.00	0.00	0	0
741017	50.00	4.00	0.00	0	0
741206	45.00	4.00	0.00	0	0
-741231	42.00	4.00	0.00	0	0

## TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY

DATE	TARGET	WEIGHTING
740101	160.00	0.80
-741231	160.00	0.80

## CARBONACEOUS BOD IN MG/L

DATE	TARGET	WEIGHTING
740101	0.05	0.15
-741231	0.05	0.15

## DISSOLVED OXYGEN IN MG/L

DATE	TARGET	WEIGHTING
740101	4.00	0.00
-741231	4.00	0.00

CONTROL POINT 30

TEMPERATURE OBJECTIVES, F		WEIGHTING		RESERVOIRS SPECIFIED FOR FLOW AUGMENTATION CONTROL			
DATE	TARGET			10	20	0	0
740101	45.00	3.00	0.00	0	0	0	0
740510	50.00	3.00	0.00	0	0	0	0
740531	60.00	3.00	0.00	0	0	0	0
741001	55.00	3.00	0.00	0	0	0	0
-741231	45.00	3.00	0.00	0	0	0	0

TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY

DATE	TARGET	WEIGHTING
740101	160.00	1.00
-741231	160.00	1.00

CARBONACEOUS BOD IN MG/L

DATE	TARGET	WEIGHTING
740101	0.15	4.00
-741231	0.15	4.00

DISSOLVED OXYGEN IN MG/L

DATE	TARGET	WEIGHTING
740101	4.50	4.00
-741231	4.50	4.00

CONTROL POINT 40

TEMPERATURE OBJECTIVES, F		WEIGHTING		RESERVOIRS SPECIFIED FOR FLOW AUGMENTATION CONTROL			
DATE	TARGET			10	20	0	0
740101	45.00	3.00	0.00	0	0	0	0
740504	50.00	3.00	0.00	0	0	0	0
740514	55.00	3.00	0.00	0	0	0	0
740515	60.00	3.00	0.00	0	0	0	0
741005	55.00	3.00	0.00	0	0	0	0
741109	50.00	3.00	0.00	0	0	0	0
741214	45.00	3.00	0.00	0	0	0	0
-741231	45.00	3.00	0.00	0	0	0	0

TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY

DATE	TARGET	WEIGHTING
740101	170.00	1.00
-741231	170.00	1.00

CARBONACEOUS BOD IN MG/L

DATE	TARGET	WEIGHTING
740101	0.20	1.00
-741231	0.20	1.00

DISSOLVED OXYGEN IN MG/L

DATE	TARGET	WEIGHTING
740101	5.50	0.00
-741231	5.50	0.00

TEMPERATURE OBJECTIVES, F		WEIGHTING		RESERVOIRS SPECIFIED FOR FLOW AUGMENTATION CONTROL				
DATE	TARGET			10	20	0	0	0
740101	50.00	3.00	0.00	0	0	0	0	0
740506	55.00	3.00	0.00	0	0	0	0	0
740510	60.00	3.00	0.00	0	0	0	0	0
740515	65.00	3.00	0.00	0	0	0	0	0
740708	70.00	3.00	0.00	0	0	0	0	0
740924	65.00	3.00	0.00	0	0	0	0	0
741018	60.00	3.00	0.00	0	0	0	0	0
741112	55.00	3.00	0.00	0	0	0	0	0
741206	50.00	3.00	0.00	0	0	0	0	0
-741231	50.00	3.00	0.00	0	0	0	0	0

## TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY

DATE	TARGET	WEIGHTING
740101	190.00	1.00
-741231	190.00	1.00

## CARBONACEOUS BOD IN MG/L

DATE	TARGET	WEIGHTING
740101	0.30	1.00
-741231	0.30	1.00

## DISSOLVED OXYGEN IN MG/L

DATE	TARGET	WEIGHTING
740101	6.00	0.00
-741231	6.00	0.00

FIRST DAY OF INFLOW QUALITY RECORD 740101  
 LAST DAY OF INFLOW QUALITY RECORD 741231  
 TOTAL NUMBER OF DAYS 365

TRIB 1 ...	2 CARDS READ FOR	TRIB 1 ...	LEFT INFLOW RATE ... RES # 1
TRIB 1 ...	2 CARDS READ FOR	TRIB 1 ...	LEFT INFLOW TEMPERATURE
TRIB 1 ...	1 CARDS READ FOR	TRIB 1 ...	LEFT INFLOW - TOTAL DISSOLVE
TRIB 1 ...	1 CARDS READ FOR	TRIB 1 ...	LEFT INFLOW - CARBONACEOUS B
TRIB 1 ...	4 CARDS READ FOR	TRIB 1 ...	LEFT INFLOW - DISSOLVED OXYG
TRIB 2 ...	2 CARDS READ FOR	TRIB 2 ...	RIGHT INFLOW RATE ... RES #
TRIB 2 ...	7 CARDS READ FOR	TRIB 2 ...	RIGHT INFLOW TEMPERATURE
TRIB 2 ...	4 CARDS READ FOR	TRIB 2 ...	RIGHT INFLOW - TDS
TRIB 2 ...	4 CARDS READ FOR	TRIB 2 ...	RIGHT INFLOW - CBOD
TRIB 2 ...	4 CARDS READ FOR	TRIB 2 ...	RIGHT INFLOW - DISSOLVED OXY
TRIB 3 ...	1 CARDS READ FOR	TRIB 3 ...	INFLOW RATE - RM 45 & RES # 2
TRIB 3 ...	2 CARDS READ FOR	TRIB 3 - RM 45	
TRIB 3 ...	1 CARDS READ FOR	TRIB 3 - RM 45	TOTAL DISSOLVED SOLIDS
TRIB 3 ...	1 CARDS READ FOR	TRIB 3 - RM 45	CARBONACEOUS BOD
TRIB 3 ...	4 CARDS READ FOR	TRIB 3 - RM 45	DISSOLVED OXYGEN
TRIB 4 ...	1 CARDS READ FOR	TRIB 4	INFLOW RATE - RM 30
TRIB 4 ...	2 CARDS READ FOR	TRIB 4 - RM 30	
TRIB 4 ...	1 CARDS READ FOR	TRIB 4 - RM 30	TOTAL DISSOLVED SOLIDS
TRIB 4 ...	1 CARDS READ FOR	TRIB 4 - RM 30	CARBONACEOUS BOD
TRIB 4 ...	4 CARDS READ FOR	TRIB 4 - RM 30	DISSOLVED OXYGEN

TIME (YEAR/MONTH/DAY) VS. INFLOW QUALITY AT CONTROL POINTS

TRIB 1 ...		LEFT INFLOW RATE ... RES # 1		INFLOW RATE AS FRACTION OF LOCAL FLOW	
TIME	VALUE	TIME	VALUE	TIME	VALUE
74/ 1/ 1	-0.50	74/ 4/ 8	-0.50	74/ 7/ 8	-0.30
74/ 1/ 1	-1.50	74/ 4/ 8	-1.50	74/ 7/ 8	-0.70
74/ 1/ 1	105.00	74/ 12/31	105.00	74/ 8/26	-0.30
74/ 1/ 1	0.50	74/ 12/31	0.50	74/ 8/26	-5.00
74/ 1/ 1	12.80	74/ 1/15	13.10	74/ 4/15	11.70
74/ 6/15	8.90	74/ 7/15	8.20	74/ 10/15	10.00
74/12/15	12.40	74/12/31	12.80	74/11/15	11.00



TRIB 2 ... TIME 74/ 1/ 1	TRIB 2 ... VALUE -0.50	RIGHT INFLOW RATE ... RES # TIME 74/ 4/ 8	VALUE -0.50	INFLOW RATE AS FRACTION OF LOCAL FLOW TIME 74/ 4/22	VALUE -0.70	74/ 7/ 8	VALUE -0.70	74/ 8/26	VALUE -0.70	74/12/31	VALUE -0.50
TRIB 2 ... TIME 74/ 1/ 1	TRIB 2 ... VALUE -0.10	RIGHT INFLOW TEMPERATURE TIME 74/ 1/25	VALUE 2.00	TEMPERATURE (F) AS DEPARTURE FRO EQUILIBRIUM TEMPERATURE TIME 74/ 2/10	VALUE 1.20	74/ 2/24	VALUE -1.80	74/ 3/10	VALUE 0.10	74/ 3/24	VALUE -10.40
74/ 4/14	-15.80	74/ 4/28	-24.30	74/ 5/12	-15.60	74/ 5/27	-16.00	74/ 6/ 9	-11.00	74/ 6/23	-15.60
74/ 7/14	-9.10	74/ 7/28	-12.30	74/ 8/11	-10.30	74/ 8/25	-15.00	74/ 9/ 8	-15.50	74/ 9/22	-17.80
74/10/14	-11.10	74/10/28	-6.10	74/11/10	-6.50	74/11/24	-4.40	74/12/ 8	-6.20	74/12/31	1.50
TRIB 2 ... TIME 74/ 1/ 1	TRIB 2 ... VALUE 140.00	RIGHT INFLOW - TDS TIME 74/ 1/15	VALUE 110.00	TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY TIME 74/ 2/15	VALUE 240.00	74/ 3/15	VALUE 400.00	74/ 4/15	VALUE 130.00	74/ 5/15	VALUE 1095.00
74/ 6/15	80.00	74/ 7/15	100.00	74/ 8/15	70.00	74/ 9/15	50.00	74/10/15	100.00	74/11/15	90.00
74/12/15	310.00	74/12/31	360.00								
TRIB 2 ... TIME 74/ 1/ 1	TRIB 2 ... VALUE 0.20	RIGHT INFLOW - CBOD TIME 74/ 1/15	VALUE 0.20	CARBONACEOUS BOD IN MG/L TIME 74/ 2/15	VALUE 0.40	74/ 3/15	VALUE 0.50	74/ 4/15	VALUE 0.20	74/ 5/15	VALUE 1.80
74/ 6/15	0.10	74/ 7/15	0.20	74/ 8/15	0.10	74/ 9/15	0.10	74/10/15	0.20	74/11/15	0.10
74/12/15	0.50	74/12/31	0.60								
TRIB 2 ... TIME 74/ 1/ 1	TRIB 2 ... VALUE 13.10	RIGHT INFLOW - DISSOLVED OXYGEN, MG/L TIME 74/ 1/15	VALUE 13.10	DISSOLVED OXYGEN, MG/L TIME 74/ 2/15	VALUE 12.40	74/ 3/15	VALUE 11.80	74/ 4/15	VALUE 11.80	74/ 5/15	VALUE 9.40
74/ 6/15	9.00	74/ 7/15	8.30	74/ 8/15	7.80	74/ 9/15	9.70	74/10/15	10.00	74/11/15	11.00
74/12/15	12.40	74/12/31	12.80								
TRIB 3 ... TIME 74/ 1/ 1	TRIB 3 ... VALUE -1.00	INFLOW RATE - RM 45 & RES # 2 TIME 74/12/31	VALUE -1.00	INFLOW RATE AS FRACTION OF LOCAL FLOW TIME 74/12/31	VALUE -1.00						
TRIB 3 ... TIME 74/ 1/ 1	TRIB 3 ... VALUE -1.50	RM 45 TIME 74/ 4/ 8	VALUE -1.50	TEMPERATURE (F) AS DEPARTURE FRO EQUILIBRIUM TEMPERATURE TIME 74/ 4/22	VALUE -3.00	74/ 7/ 8	VALUE -4.00	74/ 8/26	VALUE -3.00	74/12/31	VALUE -1.50
TRIB 3 ... TIME 74/ 1/ 1	TRIB 3 ... VALUE 160.00	TOTAL DISSOLVED SOLIDS TIME 74/12/31	VALUE 160.00	TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY TIME 74/12/31	VALUE 160.00						
TRIB 3 ... TIME 74/ 1/ 1	TRIB 3 ... VALUE 0.60	RM 45 - CARBONACEOUS BOD TIME 74/12/31	VALUE 0.60	CARBONACEOUS BOD IN MG/L TIME 74/12/31	VALUE 0.60						
TRIB 3 ... TIME 74/ 1/ 1	TRIB 3 ... VALUE 12.80	DISSOLVED OXYGEN TIME 74/ 1/15	VALUE 13.10	DISSOLVED OXYGEN, MG/L TIME 74/ 2/15	VALUE 12.40	74/ 3/15	VALUE 11.80	74/ 4/15	VALUE 11.70	74/ 5/15	VALUE 9.30
74/ 6/15	8.90	74/ 7/15	8.20	74/ 8/15	7.80	74/ 9/15	9.70	74/10/15	10.00	74/11/15	11.00
74/12/15	12.40	74/12/31	12.80								

TRIB 4 ...				INFLW RATE AS FRACTION OF LOCAL FLOW			
TIME	VALUE	TIME	VALUE	TIME	VALUE	TIME	VALUE
74/ 8/26	-1.00	74/12/31	-1.00				
TRIB 4 ...				TEMPERATURE (F) AS DEPARTURE FRO EQUILIBRIUM TEMPERATURE			
TIME	VALUE	TIME	VALUE	TIME	VALUE	TIME	VALUE
74/ 1/ 1	-1.50	74/ 4/ 8	-1.50	74/ 4/22	-3.00	74/ 7/ 8	-6.00
				74/ 8/26	-5.00	74/12/31	-1.50
TRIB 4 ...				TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY			
TIME	VALUE	TIME	VALUE	TIME	VALUE	TIME	VALUE
74/ 1/ 1	160.00	74/12/31	160.00				
TRIB 4 ...				CARBONACEOUS BOD IN MG/L			
TIME	VALUE	TIME	VALUE	TIME	VALUE	TIME	VALUE
74/ 1/ 1	0.60	74/12/31	0.60				
TRIB 4 ...				DISSOLVED OXYGEN, MG/L			
TIME	VALUE	TIME	VALUE	TIME	VALUE	TIME	VALUE
74/ 1/ 1	12.80	74/ 1/15	13.10	74/ 2/15	12.40	74/ 3/15	11.80
74/ 6/15	8.90	74/ 7/15	8.20	74/ 8/15	7.80	74/ 9/15	9.70
74/12/15	12.40	74/12/31	12.80			74/10/15	10.00
						74/11/15	11.00

\*RTCOF

ROUTING COEFFICIENTS FROM RES 10 TO MY  
MY= 30 0.1837 0.4898 0.3265  
MY= 40 0.0337 0.1799 0.3599 0.3199 0.1066  
MY= 50 0.0062 0.0496 0.1652 0.2938 0.2938 0.1567 0.0348

ROUTING COEFFICIENTS FROM RES 20 TO MY  
MY= 30 0.1837 0.4898 0.3265  
MY= 40 0.0337 0.1799 0.3599 0.3199 0.1066  
MY= 50 0.0062 0.0496 0.1652 0.2938 0.2938 0.1567 0.0348

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 121

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
10	2059.00	1270.00	0.00	20	430.00	1236.00	0.00
30	0.00	2506.00	0.00	40	645.00	3151.00	0.00
50	3317.00	6468.00	0.00				

120 DAYS OF INFLOW DATA BYPASSED ON RESERVOIR INFLOW DATA TAPE

INFLOWS TO RESERVOIR 1 CHANGED BY 0.74 ON DAY 121

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 122

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
---------	----	----	----	---------	----	----	----

10	1814.00	1320.00	0.00	20	816.00	521.00	0.00
30	0.00	2383.86	0.00	40	588.00	3071.57	0.00
50	3816.00	6952.41	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.74 ON DAY 122

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 123

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
---------	----	----	----	---------	----	----	----

10	2125.00	1360.00	0.00	20	668.00	387.00	0.00
30	0.00	1994.35	0.00	40	561.00	2904.65	0.00
50	3333.00	6394.29	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.75 ON DAY 123

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 124

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
---------	----	----	----	---------	----	----	----

10	2243.00	1410.00	0.00	20	1979.00	405.00	0.00
30	0.00	1723.78	0.00	40	488.00	2521.60	0.00
50	3150.00	6019.97	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.75 ON DAY 124

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 125

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
---------	----	----	----	---------	----	----	----

10	1947.00	1440.00	0.00	20	1523.00	442.00	0.00
30	0.00	1815.01	0.00	40	452.00	2229.41	0.00
50	2843.00	5395.82	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.75 ON DAY 125

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 126

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
---------	----	----	----	---------	----	----	----

10	1836.00	1470.00	0.00	20	1195.00	949.00	0.00
30	0.00	1968.82	0.00	40	440.00	2243.00	0.00
50	2861.00	5136.51	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.75 ON DAY 126

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 127

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
---------	----	----	----	---------	----	----	----

10	1735.00	1480.00	0.00	20	1065.00	1602.00	0.00
30	0.00	2407.75	0.00	40	425.00	2447.25	0.00
50	2976.00	5233.97	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.76 ON DAY 127

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 128

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
---------	----	----	----	---------	----	----	----

10	1587.00	1480.00	0.00	20	847.00	1572.00	0.00
30	0.00	2953.59	0.00	40	405.00	2811.54	0.00
50	2831.00	5298.53	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.76 ON DAY 128

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 129

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
10	1549.00	1480.00	0.00	20	698.00	1528.00	0.00
30	0.00	3100.49	0.00	40	406.00	3283.38	0.00
50	3011.00	5832.93	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.76 ON DAY 129

FLOW DATA FROM HEC-5 QUANTITY SIMULATION FOR DAY 130

C.P. ID	QL	QN	DQ	C.P. ID	QL	QN	DQ
10	1509.00	1480.00	0.00	20	569.00	1040.00	0.00
30	0.00	2915.50	0.00	40	398.00	3467.47	0.00
50	3250.00	6474.95	0.00				

INFLOWS TO RESERVOIR 1 CHANGED BY 0.77 ON DAY 130

# RESERVOIR MODEL RESULTS

RESERVOIR NO 1 .. CONTROL POINT 10

JULIAN DATE 130

METEOROLOGICAL DATA EQUILIBRIUM TEMPERATURE, F 67.7  
 HEAT EXCHANGE COEFFICIENT, BTU/FT2/DAY/F 96.1  
 SHORT WAVE SOLAR RADIATION, BTU/FT2/DAY 2495.  
 WIND SPEED, MPH 7.8  
 EVAPORATION RATE, AC.FT/DAY 87.38

## INFLOW DATA

TRIB NO	FLOW CFS	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
2	810.1	51.1	950.2	0.00	0.00	0.00	1.07	0.00	9.8
1	698.9	62.0	105.0	0.00	0.00	0.00	0.34	0.00	9.7

## OUTFLOW INFORMATION

OUTLET	FLOW CFS	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
WET WELL NO 1	292.5	45.0	150.5	0.00	0.00	0.00	0.32	0.00	8.8
WET WELL NO 2	1187.4	44.0	156.9	0.00	0.00	0.00	0.33	0.00	8.9
TOTAL OUTFLOW	1480.0	44.2	155.6	0.00	0.00	0.00	0.33	0.00	8.9
OBJECTIVES		41.8*	146.9*	0.00	0.00	0.00	0.27*	0.00	8.8*

\* INCLUDED IN WITHDRAWAL QUALITY OPTIMIZATION

RESERVOIR INFORMATION WATER SURFACE ELEVATION, FT 997.95  
 RESERVOIR SURFACE AREA, AC 14376.  
 RESERVOIR STORAGE VOLUME, ACFT 1207466.

RESERVOIR WATER QUALITY

DEPTH FT	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
2.5	59.0	176.3	0.00	0.00	0.00	0.25	0.00	9.8
7.5	59.0	176.3	0.00	0.00	0.00	0.25	0.00	9.8
12.5	58.1	177.1	0.00	0.00	0.00	0.25	0.00	9.6
17.5	55.0	177.9	0.00	0.00	0.00	0.26	0.00	9.0
22.5	52.9	178.4	0.00	0.00	0.00	0.27	0.00	8.8
27.5	51.4	180.9	0.00	0.00	0.00	0.27	0.00	8.8
32.5	50.3	181.7	0.00	0.00	0.00	0.28	0.00	8.8
37.5	49.4	184.5	0.00	0.00	0.00	0.29	0.00	8.8
42.5	48.7	182.0	0.00	0.00	0.00	0.29	0.00	8.8
47.5	48.2	178.3	0.00	0.00	0.00	0.29	0.00	8.8
52.5	47.9	172.4	0.00	0.00	0.00	0.29	0.00	8.8
57.5	47.5	167.2	0.00	0.00	0.00	0.29	0.00	8.8
62.5	47.3	162.4	0.00	0.00	0.00	0.29	0.00	8.8
67.5	47.0	158.5	0.00	0.00	0.00	0.29	0.00	8.8
72.5	46.7	155.1	0.00	0.00	0.00	0.29	0.00	8.8
77.5	46.5	152.4	0.00	0.00	0.00	0.29	0.00	8.8
82.5	46.2	150.3	0.00	0.00	0.00	0.29	0.00	8.8
87.5	46.0	148.9	0.00	0.00	0.00	0.29	0.00	8.8
92.5	45.7	148.2	0.00	0.00	0.00	0.30	0.00	8.8
97.5W1	45.4	148.5	0.00	0.00	0.00	0.30	0.00	8.8
102.5	44.7	151.2	0.00	0.00	0.00	0.31	0.00	8.8
107.5	44.1	154.2	0.00	0.00	0.00	0.31	0.00	8.8
112.5	43.7	157.0	0.00	0.00	0.00	0.32	0.00	8.9
117.5W2	43.4	159.6	0.00	0.00	0.00	0.32	0.00	8.9
122.5	43.1	161.6	0.00	0.00	0.00	0.32	0.00	8.9
127.5	43.0	162.9	0.00	0.00	0.00	0.32	0.00	8.9
132.5	42.9	163.7	0.00	0.00	0.00	0.33	0.00	8.9
137.5	42.8	164.5	0.00	0.00	0.00	0.33	0.00	8.9
142.5	42.8	165.5	0.00	0.00	0.00	0.33	0.00	8.9
147.5	42.7	166.7	0.00	0.00	0.00	0.33	0.00	8.9
152.5	42.5	168.7	0.00	0.00	0.00	0.33	0.00	8.9
157.5	42.4	170.3	0.00	0.00	0.00	0.33	0.00	8.9
162.5	42.3	171.6	0.00	0.00	0.00	0.33	0.00	8.9
167.5	42.2	172.9	0.00	0.00	0.00	0.33	0.00	8.9
172.5	42.1	174.1	0.00	0.00	0.00	0.33	0.00	8.9
177.5	42.0	175.5	0.00	0.00	0.00	0.33	0.00	8.9
182.5	42.0	176.6	0.00	0.00	0.00	0.33	0.00	8.9
187.5	41.9	177.6	0.00	0.00	0.00	0.33	0.00	8.9
192.5	41.9	178.3	0.00	0.00	0.00	0.33	0.00	8.9
197.5	41.9	178.7	0.00	0.00	0.00	0.34	0.00	8.9

# RESERVOIR MODEL RESULTS

RESERVOIR NO 2 .. CONTROL POINT 20

JULIAN DATE 130

METEOROLOGICAL DATA EQUILIBRIUM TEMPERATURE, F 67.6  
 HEAT EXCHANGE COEFFICIENT, BTU/FT2/DAY/F 95.1  
 SHORT WAVE SOLAR RADIATION, BTU/FT2/DAY 2451.  
 WIND SPEED, MPH 7.6  
 EVAPORATION RATE, AC.FT/DAY 124.38

## INFLOW DATA

TRIB NO	FLOW CFS	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
3	569.0	64.3	160.0	0.00	0.00	0.00	0.41	0.00	9.7

## OUTFLOW INFORMATION

OUTLET	FLOW CFS	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
WET WELL NO 1	1040.0	56.2	185.2	0.00	0.00	0.00	0.09	0.00	8.7
TOTAL OUTFLOW	1040.0	56.2	185.2	0.00	0.00	0.00	0.09	0.00	8.7
OBJECTIVES		55.3*	180.9*	0.00	0.00	0.00	0.08*	0.00	8.4*

\* INCLUDED IN WITHDRAWAL QUALITY OPTIMIZATION

RESERVOIR INFORMATION WATER SURFACE ELEVATION, FT 962.39  
 RESERVOIR SURFACE AREA, AC 26029.  
 RESERVOIR STORAGE VOLUME, ACFT 548959.

## RESERVOIR WATER QUALITY

DEPTH FT	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
1.0	62.7	189.7	0.00	0.00	0.00	0.07	0.00	9.8
3.0	62.7	189.7	0.00	0.00	0.00	0.07	0.00	9.8
5.0	62.8	189.7	0.00	0.00	0.00	0.07	0.00	9.8
7.0	62.7	189.7	0.00	0.00	0.00	0.07	0.00	9.8
9.0	62.4	189.7	0.00	0.00	0.00	0.07	0.00	9.8
11.0	61.8	189.7	0.00	0.00	0.00	0.07	0.00	9.7
13.0	60.2	189.6	0.00	0.00	0.00	0.07	0.00	9.5
15.0	59.2	189.4	0.00	0.00	0.00	0.07	0.00	9.3
17.0	58.6	189.3	0.00	0.00	0.00	0.07	0.00	9.2
19.0	58.2	189.3	0.00	0.00	0.00	0.07	0.00	9.1
21.0	57.9	189.2	0.00	0.00	0.00	0.07	0.00	9.0
23.0	57.8	189.2	0.00	0.00	0.00	0.07	0.00	9.0
25.0	57.7	189.2	0.00	0.00	0.00	0.07	0.00	9.0
27.0	57.6	189.1	0.00	0.00	0.00	0.07	0.00	9.0
29.0	57.5	189.1	0.00	0.00	0.00	0.07	0.00	9.0
31.0	57.4	189.0	0.00	0.00	0.00	0.07	0.00	8.9
33.0	57.4	189.0	0.00	0.00	0.00	0.07	0.00	8.9
35.0	57.3	188.9	0.00	0.00	0.00	0.07	0.00	8.9
37.0	57.2	188.9	0.00	0.00	0.00	0.07	0.00	8.9
39.0	57.2	188.8	0.00	0.00	0.00	0.08	0.00	8.9
41.0	57.1	188.6	0.00	0.00	0.00	0.08	0.00	8.9
43.0	57.1	188.5	0.00	0.00	0.00	0.08	0.00	8.9
45.0	57.0	188.3	0.00	0.00	0.00	0.08	0.00	8.8
47.0	56.9	188.0	0.00	0.00	0.00	0.08	0.00	8.8
49.0	56.8	187.6	0.00	0.00	0.00	0.08	0.00	8.8
51.0	56.6	187.2	0.00	0.00	0.00	0.08	0.00	8.8
53.0	56.4	186.5	0.00	0.00	0.00	0.08	0.00	8.7
55.0	56.2	185.8	0.00	0.00	0.00	0.08	0.00	8.7
57.0	56.1	185.2	0.00	0.00	0.00	0.08	0.00	8.6
59.0	55.9	184.6	0.00	0.00	0.00	0.08	0.00	8.6
61.0	55.8	184.0	0.00	0.00	0.00	0.08	0.00	8.6
63.0	55.7	183.6	0.00	0.00	0.00	0.08	0.00	8.5
65.0W1	55.6	183.1	0.00	0.00	0.00	0.08	0.00	8.5
67.0	55.6	182.7	0.00	0.00	0.00	0.08	0.00	8.5
69.0	55.4	181.8	0.00	0.00	0.00	0.08	0.00	8.5



STREAM MODEL RESULTS

JULIAN DATE 130

METEOROLOGICAL DATA  
(NET.ZONE 1)

EQUILIBRIUM TEMPERATURE, F 67.6  
HEAT EXCHANGE COEFFICIENT, BTU/FT2/DAY/F 95.1  
SHORT WAVE SOLAR RADIATION, BTU/FT2/DAY 2451.  
WIND SPEED, MPH 7.6

RESERVOIR RELEASES

RESERVOIR NO	FLOW CFS	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
10	1480.0	44.2	155.6	0.00	0.00	0.00	0.33	0.00	8.9
20	1040.0	56.2	185.2	0.00	0.00	0.00	0.09	0.00	8.7

LOCAL FLOWS AND WATER QUALITY

C.P. NO	FLOW CFS	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
40	398.0	64.3	160.0	0.00	0.00	0.00	0.41	0.00	9.7
50	3250.0	63.9	160.0	0.00	0.00	0.00	0.41	0.00	9.7

STREAM WATER QUALITY

LOCATION MILE	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L	MEAN FLOW CFS	W/S ELEV. FT
64.81 C10	44.8	155.5	0.00	0.00	0.00	0.33	0.00	9.0	1480.0	849.8
63.44	45.2	155.5	0.00	0.00	0.00	0.33	0.00	9.1	1538.0	845.0
62.06	45.6	155.4	0.00	0.00	0.00	0.33	0.00	9.2	1596.1	840.2
60.69 C30	46.0	155.3	0.00	0.00	0.00	0.33	0.00	9.3	1654.2	836.5
3.92 C20	56.4	185.3	0.00	0.00	0.00	0.09	0.00	8.9	1040.0	858.0
2.35	56.6	185.3	0.00	0.00	0.00	0.09	0.00	9.1	1094.4	847.1
0.78 C30	57.1	185.3	0.00	0.00	0.00	0.09	0.00	9.1	1148.8	838.4
59.00 C30	51.6	169.7	0.00	0.00	0.00	0.22	0.00	9.3	2915.5	832.1
57.00	51.8	169.8	0.00	0.00	0.00	0.22	0.00	9.4	2930.9	826.0
55.00	52.0	169.8	0.00	0.00	0.00	0.21	0.00	9.5	2946.3	819.9
53.00	52.2	169.8	0.00	0.00	0.00	0.21	0.00	9.6	2961.7	813.8
51.00	52.4	169.8	0.00	0.00	0.00	0.21	0.00	9.7	2977.0	807.8
49.00	52.6	169.8	0.00	0.00	0.00	0.21	0.00	9.8	2992.4	801.7
47.00	52.8	169.8	0.00	0.00	0.00	0.21	0.00	9.9	3007.8	795.6
45.00	53.0	169.8	0.00	0.00	0.00	0.21	0.00	10.0	3023.2	789.5
43.00 T 3	54.4	168.7	0.00	0.00	0.00	0.23	0.00	10.0	3436.6	783.7
41.00 C40	54.6	168.7	0.00	0.00	0.00	0.23	0.00	10.0	3452.0	777.9
39.01 C40	54.7	168.7	0.00	0.00	0.00	0.23	0.00	10.1	3467.4	770.6
37.04	54.9	168.7	0.00	0.00	0.00	0.23	0.00	10.1	3437.1	762.2
35.06	55.0	168.7	0.00	0.00	0.00	0.23	0.00	10.1	3406.8	753.8
33.09	55.1	168.7	0.00	0.00	0.00	0.23	0.00	10.1	3376.5	745.3
31.11	55.7	168.7	0.00	0.00	0.00	0.22	0.00	10.2	3346.2	738.9
29.14 T 4	59.8	164.4	0.00	0.00	0.00	0.31	0.00	9.9	6565.8	736.7
27.16	60.1	164.4	0.00	0.00	0.00	0.31	0.00	9.9	6535.5	735.4
25.19 C50	60.3	164.4	0.00	0.00	0.00	0.30	0.00	9.9	6505.2	733.1

T = TRIBUTARY LOCATION  
C = CONTROL POINT  
C\* = END OF REACH


TARGETS

C.P. NO	TEMP F	CONS.1 MG/L	CONS.2 MG/L	CONS.3 MG/L	NONCON.1 MG/L	NONCON.2 MG/L	NONCON.3 MG/L	OXYGEN MG/L
10	45.0	150.0	0.00	0.00	0.00	0.10	0.00	5.0
20	50.0	160.0	0.00	0.00	0.00	0.05	0.00	4.0
30	50.0	160.0	0.00	0.00	0.00	0.15	0.00	4.5
40	50.0	170.0	0.00	0.00	0.00	0.20	0.00	5.5
50	60.0	190.0	0.00	0.00	0.00	0.30	0.00	6.0

## TEST PROBLEM 2 - Standard Tandem Reservoir Case

- a. The system simulated in this test of the water quality simulation module consists of two tandem reservoirs, the reach of the stream between the reservoirs and a reach of stream below the more downstream reservoir. The system diagram is shown on the following page.
- b. The reservoirs used for this test problem have the same sizes, depths and outlet characteristics as the two reservoirs used for Test Problem 1. The Hayes Reservoir, in this example, corresponds to the Baker Reservoir in Test Problem 1. Similarly, Davis Reservoir, in this example, corresponds to the Smith reservoir in Test Problem 1.
- c. The stream system consists of 25.5 miles of stream between the Hayes and Davis Reservoirs. The energy grade line (EGL) slope between the Hayes Reservoir, at RM 65.5 and RM 60 (CP #20) is 0.00065. The EGL slope between RM 60 and RM 40 (CP #30), in the headwaters of the Davis Reservoir is 0.00057. From Davis dam, at RM 32.0 (CP #40) to RM 30.4, the stream has an EGL slope of 0.00012. From RM 30.4 to the end of the system, RM 24.2 (CP #5), the EGL slope is 0.000076.
- d. Tributary inflows to the stream system between the two reservoirs occur at control point 20 and 30. Below the Davis Reservoir, tributary inflow occurs at river mile 30.0.
- e. Temperature, total dissolved solids (TDS), carbonaceous BOD and dissolved oxygen are simulated. All data, inflow values, control points, water quality objectives, and gate selection weights and objective function parameters are furnished as described for Test Problem 1.

A complete listing of the input data file is given below. A complete output listing is included with the computer source code distribution.



### EXAMPLE TANDEM RESERVOIR PROBLEM

T1	TESTING HEC5Q WATER QUALITY SIMULATION CAPABILITY									
T2	TANDEM RIVER SYSTEM.									
T3	TEST PROBLEM 2									
J1	0	5	5	3	4	2	0	0		
J2	36	0	0	0	0	0	0			
J9										
RL	10	1200000	0	100000	200000	1500000	1600000			
RO	3	20	30	40						
RS	7	100	6300	31300	88000	188000	563000	1688000		
RQ	7	0	20000	30000	40000	50000	50000	50000		
RA	7	10	500	1500	3000	5000	10000	20000		
RE	7	800	825	850	870	900	950	1030		
R3	2	2	2	2	99	99	99	99	99	99
R3	99	99								
CP	10	15000	300	200						
IDCP10-HAYES DAM										
RT	10	20	2.2	.25	12	0				
CP	20	12000	300	200						
ID CP20 ** RM 60										
RT	20	30	2.2	.25	12	0				
CP	30	12000	300	200						
ID CP30 ** RM 40										
RT	30	40	2.2	.25	12	0				
RL	40	550000	0	2000	550000	952000	1130000			
RO	1	50								
RS	8	2000	20000	52000	113000	209000	320000	550000	800000	1130000
RQ	8	0	5680	5680	5680	5680	5680	29180	59680	104980
RA	8	150	2100	4500	7600	11800	17000	22400	28600	37200
RE	8	892	910	920	930	940	950	962.5	970	980
R3	2	2	2	2	99	99	99	99	99	99
R3	99	99								
CP	40	10000	300	200						
IDCP40-DAVIS DAM										
RT	40	50	2.2	.25	12	0				
CP	50	50000	300	200						
IDCP50 ** RM24.2										
RT	50	0	0	0	0	0				
ED										
BF	0	120	0	074050100	120	24				
NOLIST										
IN	10	1MAY74	2059	1814	2125	2243	1947	1836	1735	1587
IN	1549	1509	1413	4584	7520	5061	3549	2931	2801	3866
IN	2752	2293	1962	1793	2476	2528	1958	1650	1462	1344
IN	1810	3581	3367	7629	5501	3699	3057	2603	2294	2073
IN	1894	1750	1596	1423	1313	1251	1052	1312	2547	2301
IN	1803	1360	1185	1200	1456	2434	4601	3121	2769	2230
IN	1846	2107	1918	15259	7046	4185	3113	3167	2814	2295
IN	1910	1606	1448	1535	1368	1196	1039	1032	1013	940
IN	890	890	865	826	783	826	928	847	788	829
IN	804	806	945	801	712	751	914	911	935	792
IN	747	717	823	1416	997	806	759	732	683	653
IN	633	639	621	644	604	598	598	596	601	642
IN	662	838	756	1130	1138	1202	1774	2727	2659	1566

IN	20	1MAY74	645	588	561	488	452	440	425	405
IN	406	398	380	923	1207	1171	1161	1075	1190	1601
IN	1685	1941	1849	1752	1784	1322	645	397	366	458
IN	669	1011	1113	1740	1529	1352	1273	1219	1171	908
IN	575	431	407	375	357	348	243	231	469	598
IN	671	585	369	237	288	360	546	768	900	874
IN	829	712	549	2648	1733	1751	1617	1671	1565	1433
IN	922	465	361	384	353	328	298	305	296	285
IN	279	235	143	142	139	150	226	282	276	191
IN	106	139	183	220	269	268	278	283	311	249
IN	178	172	162	177	135	119	117	117	130	164
IN	161	166	160	117	61	42	51	141	142	108
IN	87	235	418	701	621	790	976	1222	1532	1570
IN	30	1MAY74	645	588	561	488	452	440	425	405
IN	406	398	380	923	1207	1171	1161	1075	1190	1601
IN	1685	1941	1849	1752	1784	1322	645	397	366	458
IN	669	1011	1113	1740	1529	1352	1273	1219	1171	908
IN	575	431	407	375	357	348	243	231	469	598
IN	671	585	369	237	288	360	546	768	900	874
IN	829	712	549	2648	1733	1751	1617	1671	1565	1433
IN	922	465	361	384	353	328	298	305	296	285
IN	279	235	143	142	139	150	226	282	276	191
IN	106	139	183	220	269	268	278	283	311	249
IN	178	172	162	177	135	119	117	117	130	164
IN	161	166	160	117	61	42	51	141	142	108
IN	87	235	418	701	621	790	976	1222	1532	1570
IN	50	1MAY74	3317	3816	3333	3150	2843	2861	2976	2831
IN	3011	3250	3265	4695	13438	10915	9154	8282	7643	7539
IN	6757	6013	4768	3744	3530	3463	3178	2914	2592	2150
IN	1941	1852	1735	1747	1903	2065	1847	1399	1148	1035
IN	978	844	714	809	784	873	969	816	1405	1972
IN	2159	1563	1308	1482	1621	1469	1155	1353	975	1469
IN	1483	1761	1469	4196	7637	5846	5734	4803	4285	3660
IN	3314	2783	1990	1912	1651	1441	937	893	1209	1028
IN	980	990	1160	785	550	695	679	705	701	786
IN	566	627	774	742	696	661	613	578	630	914
IN	930	930	918	981	1006	881	924	829	857	780
IN	684	606	637	670	578	562	558	486	458	440
IN	621	825	1619	2200	2012	1742	1687	2852	4965	4311
QA	10	1MAY74	1270	1320	1360	1410	1440	1470	1480	1480
QA	1480	1480	1790	2190	2480	3480	4490	4420	4300	4210
QA	4130	3960	3720	3370	2470	1910	1950	1940	1890	1570
QA	1270	1680	2210	2480	4000	5510	5350	4400	2930	1970
QA	1570	1570	1570	1560	1560	1530	1510	1480	1830	2690
QA	3120	2840	1640	819	854	900	1540	2750	3250	2860
QA	2100	2030	2030	3600	9280	11000	7280	4130	3250	2180
QA	1750	1470	1210	1290	1320	1320	1290	1270	1230	948
QA	570	600	610	610	621	631	642	707	764	753
QA	741	730	730	741	730	719	707	707	775	775
QA	819	786	494	819	865	654	865	831	797	764
QA	719	685	494	631	580	521	346	540	486	486
QA	521	600	438	797	1410	2000	2050	2130	3460	4590
EJ										

TI	FICTICIOUS TANDEM RIVER BASIN TEST OF HEC-5Q WITH WATER QUALITY				
TI	RESERVOIRS ARE FICTICIOUS ALSO ** C.P. OF 10, 20, 30, 40 AND 50				
TI	CONSTITUENTS ARE TEMPERATURE, TDS, CARBONACEOUS BOD AND OXYGEN				
JA	740501	740831	5	2	F 1
EZ	1				
ET	116	67.59	105.5	2350.0	8.53
ET	117	75.54	75.0	2350.5	5.56
ET	118	72.51	155.0	2250.2	11.54
ET	119	73.50	195.0	2250.1	13.59
ET	120	74.51	125.5	2250.3	8.54
ET	121	64.56	135.8	2350.6	12.55
ET	122	62.54	115.4	2450.1	10.51
ET	123	65.54	125.3	2350.9	10.50
ET	124	60.56	105.7	2450.1	10.54
ET	125	63.56	105.6	2450.1	9.55
ET	126	57.50	125.1	2450.3	12.50
ET	127	58.55	85.7	2550.6	8.58
ET	128	66.56	95.8	2450.1	7.52
ET	129	66.56	135.3	2450.0	11.58
ET	130	67.58	95.1	2450.6	7.55
ET	131	70.53	135.1	2450.9	10.59
ET	132	66.58	145.4	2450.1	12.51
ET	133	62.56	145.1	2550.4	13.50
ET	134	72.50	145.0	2450.1	11.53
ET	135	71.59	175.2	2450.3	13.52
ET	136	74.51	135.5	2450.6	9.56
ET	137	78.51	175.4	2450.2	10.55
ET	138	75.56	125.7	2450.3	8.59
ET	139	72.54	135.9	2550.7	9.50
ET	140	73.53	115.8	2550.2	8.55
ET	141	81.53	95.9	2550.9	5.56
ET	142	77.55	145.0	2450.5	8.58
ET	143	73.54	145.7	2550.6	10.51
ET	144	68.59	155.9	2550.9	12.51
ET	145	67.54	95.2	2650.1	8.51
ET	146	69.55	95.3	2650.0	7.52
ET	147	64.59	115.9	2650.5	10.56
ET	148	71.57	95.5	2650.2	7.57
ET	149	73.54	145.0	2550.2	10.52
ET	150	80.54	105.4	2550.5	6.51
ET	151	77.53	135.9	2550.9	8.54
ET	152	70.57	135.4	2550.9	10.59
ET	153	72.59	125.6	2650.7	9.56
ET	154	78.51	85.5	2650.4	5.50
ET	155	79.57	95.9	2550.9	6.59
ET	156	76.56	135.5	2550.6	8.53
ET	157	77.55	135.5	2550.1	8.50
ET	158	75.53	175.0	2550.3	11.53
ET	159	78.50	135.6	2550.9	8.54
ET	160	82.50	135.6	2550.4	7.57
ET	161	77.57	215.1	2550.9	13.52
ET	162	69.53	175.9	2650.5	13.57
ET	163	71.57	115.4	2650.6	8.58
ET	164	73.56	105.8	2650.3	7.56

ET	165	79.58	95.8	2650.5	5.55
ET	166	72.52	155.5	2650.4	10.55
ET	167	71.52	145.3	2650.1	10.52
ET	168	71.56	115.0	2650.7	8.54
ET	169	73.53	125.3	2650.5	8.58
ET	170	77.59	125.1	2650.1	8.51
ET	171	82.54	145.8	2550.0	8.55
ET	172	77.57	195.4	2550.1	12.54
ET	173	81.55	105.0	2550.8	6.52
ET	174	72.52	145.9	2650.9	10.51
ET	175	71.55	155.0	2650.8	11.52
ET	176	71.52	125.3	2650.1	9.50
ET	177	77.58	95.6	2650.1	6.53
ET	178	75.59	125.3	2650.7	8.53
ET	179	74.59	125.5	2650.1	8.58
ET	180	74.58	135.1	2650.1	8.54
ET	181	74.58	215.0	2550.0	14.58
ET	182	80.55	135.6	2550.8	8.51
ET	183	80.59	185.1	2550.8	10.57
ET	184	83.54	205.0	2450.3	10.56
ET	185	83.50	205.2	2450.8	10.56
ET	186	82.50	145.0	2550.8	7.58
ET	187	83.57	105.5	2550.4	5.57
ET	188	89.50	85.1	2550.7	4.54
ET	189	89.52	105.4	2550.9	4.52
ET	190	86.57	145.1	2450.9	6.55
ET	191	82.55	165.3	2450.5	8.57
ET	192	77.54	165.3	2550.5	10.55
ET	193	79.50	105.1	2550.9	6.58
ET	194	87.51	85.2	2550.5	4.50
ET	195	82.50	165.8	2450.9	9.56
ET	196	78.59	165.8	2450.7	10.53
ET	197	76.58	145.4	2550.0	9.58
ET	198	85.58	95.6	2550.9	4.59
ET	199	83.50	145.6	2450.7	7.57
ET	200	81.54	205.3	2450.6	11.50
ET	201	77.55	145.3	2450.5	9.51
ET	202	77.58	125.0	2550.5	8.50
ET	203	82.52	105.7	2450.6	6.52
ET	204	79.54	125.5	2450.3	7.59
ET	205	80.52	115.4	2450.2	6.55
ET	206	84.59	85.9	2450.7	4.50
ET	207	89.54	85.8	2450.1	3.51
ET	208	88.57	95.9	2350.6	4.55
ET	209	82.58	135.1	2350.5	7.58
ET	210	78.56	155.3	2350.3	8.53
ET	211	77.51	155.5	2350.2	9.52
ET	212	79.53	125.3	2350.3	7.57
ET	213	83.59	105.3	2350.8	5.55
ET	214	84.54	115.8	2350.0	5.58
ET	215	79.54	175.7	2250.5	10.54
ET	216	76.56	175.7	2350.9	10.55
ET	217	75.50	115.1	2350.3	7.56
ET	218	79.52	105.2	2350.8	6.59



ET	219	84.54	95.9	2250.2	4.57
ET	220	83.50	105.5	2250.9	5.59
ET	221	83.53	95.9	2250.4	5.58
ET	222	78.55	135.9	2250.7	8.59
ET	223	78.58	165.9	2250.5	9.54
ET	224	83.56	115.8	2150.0	5.58
ET	225	82.54	125.9	2150.5	6.55
ET	226	79.58	135.4	2250.7	7.56
ET	227	81.59	95.2	2250.6	5.55
ET	228	85.58	85.2	2150.8	4.55
ET	229	79.57	155.6	2150.0	8.57
ET	230	87.54	75.6	2150.9	3.52
ET	231	86.54	75.1	2150.0	3.57
ET	232	90.50	65.8	2150.1	2.53
ET	233	85.53	85.0	2150.1	4.58
ET	234	85.52	85.0	2150.5	4.53
ET	235	84.58	95.2	2050.7	4.57
ET	236	82.52	115.2	2050.5	5.58
ET	237	87.52	75.2	2050.9	3.52
ET	238	86.52	85.3	2050.6	4.51
ET	239	80.53	155.8	2050.4	8.58
ET	240	79.58	145.3	2050.1	8.59
ET	241	79.51	145.2	1950.7	8.58
ET	242	80.52	125.7	1950.4	6.59
ET	243	77.59	155.1	1950.6	9.56
ET	244	76.55	115.8	1950.0	6.50
ET	245	73.52	115.2	1950.1	7.54
ET	246	65.54	145.9	2050.9	12.50
ET	247	67.58	105.8	2050.9	8.55
ET	248	69.56	85.2	1950.8	6.50
ET	249	70.57	95.1	1950.5	7.55
ET	250	78.58	75.3	1950.2	4.55
ET	251	84.57	55.1	1850.7	2.51
ET	252	86.58	55.5	1850.6	2.57
ET	253	82.51	65.2	1850.6	3.59
ET	254	78.58	95.0	1850.5	5.50
ET	255	77.58	155.8	1750.7	8.58
ET	256	76.50	155.9	1750.1	9.56
ET	257	68.51	105.2	1850.9	7.57
ET	258	68.50	95.7	1850.5	6.59
ET	259	71.50	85.1	1750.5	5.54
ET	260	70.58	115.5	1750.5	8.51
ET	261	71.53	105.1	1750.1	7.54
ET	262	74.53	85.9	1750.1	5.51
ET	263	73.53	115.4	1650.7	7.55
ET	264	64.59	105.9	1750.2	8.58
ET	265	60.57	105.2	1750.1	9.53
ET	266	57.50	75.9	1750.6	7.54
ET	267	59.59	75.2	1750.0	6.51
ET	268	62.56	115.1	1650.1	9.54
ET	269	65.51	115.0	1650.5	9.52
ET	270	70.54	85.4	1550.5	5.53
ET	271	72.54	125.1	1550.2	8.53
ET	272	63.56	165.7	1550.3	13.51

ET	273	56.54	115.4	1550.0	11.53
ET	-274	53.71	104.9	1568.0	10.72
EZ	-2				
ET	116	67.19	100.5	2335.0	8.43
ET	117	75.04	77.0	2331.5	5.26
ET	118	72.91	155.0	2291.2	11.34
ET	119	73.40	196.0	2278.1	13.89
ET	120	74.01	127.5	2294.3	8.64
ET	121	64.06	138.8	2385.6	12.35
ET	122	62.44	111.4	2409.1	10.31
ET	123	65.44	126.3	2385.9	10.60
ET	124	60.66	107.7	2456.1	10.34
ET	125	63.36	102.6	2457.1	9.35
ET	126	57.60	124.1	2466.3	12.60
ET	127	58.75	89.7	2507.6	8.88
ET	128	66.16	90.8	2484.1	7.72
ET	129	66.36	138.3	2446.0	11.48
ET	130	67.68	96.1	2494.6	7.85
ET	131	70.23	130.1	2473.9	10.09
ET	132	66.18	147.4	2470.1	12.21
ET	133	62.56	144.1	2518.4	13.40
ET	134	72.00	149.0	2492.1	11.23
ET	135	71.49	175.2	2472.3	13.02
ET	136	74.91	133.5	2480.6	9.06
ET	137	78.21	176.4	2413.2	10.65
ET	138	75.06	127.7	2486.3	8.59
ET	139	72.84	131.9	2525.7	9.60
ET	140	73.33	118.8	2544.2	8.55
ET	141	81.63	95.9	2508.9	5.46
ET	142	77.95	142.0	2476.5	8.68
ET	143	73.94	148.7	2521.6	10.31
ET	144	68.99	151.9	2563.9	12.01
ET	145	67.24	99.2	2614.1	8.21
ET	146	69.55	97.3	2617.0	7.72
ET	147	64.69	119.9	2640.5	10.76
ET	148	71.17	97.5	2626.2	7.47
ET	149	73.54	145.0	2558.2	10.02
ET	150	80.04	107.4	2543.5	6.31
ET	151	77.13	137.9	2528.9	8.64
ET	152	70.47	132.4	2598.9	10.09
ET	153	72.09	120.6	2629.7	9.06
ET	154	78.21	86.5	2621.4	5.50
ET	155	79.57	99.9	2598.9	6.09
ET	156	76.06	133.5	2597.6	8.93
ET	157	77.65	133.5	2579.1	8.50
ET	158	75.63	175.0	2568.3	11.63
ET	159	78.80	137.6	2562.9	8.34
ET	160	82.00	138.6	2539.4	7.67
ET	161	77.77	212.1	2535.9	13.02
ET	162	69.73	170.9	2626.5	13.27
ET	163	71.67	119.4	2644.6	8.88
ET	164	73.76	105.8	2658.3	7.56
ET	165	79.68	93.8	2632.5	5.75
ET	166	72.72	153.5	2601.4	10.85

ET	167	71.62	145.3	2627.1	10.72
ET	168	71.26	110.0	2663.7	8.34
ET	169	73.63	124.3	2646.5	8.88
ET	170	77.79	129.1	2600.1	8.21
ET	171	82.04	144.8	2542.0	8.05
ET	172	77.67	199.4	2553.1	12.44
ET	173	81.25	107.0	2592.8	6.22
ET	174	72.32	143.9	2625.9	10.51
ET	175	71.35	151.0	2647.8	11.52
ET	176	71.62	129.3	2649.1	9.80
ET	177	77.68	96.6	2622.1	6.13
ET	178	75.09	129.3	2628.7	8.93
ET	179	74.39	127.5	2615.1	8.88
ET	180	74.98	130.1	2601.1	8.84
ET	181	74.88	210.0	2568.0	14.18
ET	182	80.55	135.6	2566.8	8.01
ET	183	80.89	185.1	2524.8	10.67
ET	184	83.64	204.0	2486.3	10.76
ET	185	83.70	200.2	2483.8	10.56
ET	186	82.60	140.0	2503.8	7.58
ET	187	83.17	106.5	2566.4	5.97
ET	188	89.10	87.1	2546.7	4.14
ET	189	89.42	102.4	2502.9	4.72
ET	190	86.77	141.1	2467.9	6.85
ET	191	82.85	165.3	2461.5	8.77
ET	192	77.04	165.3	2538.5	10.65
ET	193	79.90	105.1	2557.9	6.38
ET	194	87.21	86.2	2531.5	4.30
ET	195	82.40	168.8	2466.9	9.26
ET	196	78.49	168.8	2498.7	10.43
ET	197	76.98	140.4	2528.0	9.08
ET	198	85.08	91.6	2508.9	4.79
ET	199	83.80	141.6	2436.7	7.47
ET	200	81.34	201.3	2425.6	11.30
ET	201	77.05	147.3	2496.5	9.51
ET	202	77.18	127.0	2509.5	8.30
ET	203	82.02	109.7	2467.6	6.22
ET	204	79.34	124.5	2445.3	7.29
ET	205	80.82	119.4	2435.2	6.85
ET	206	84.99	86.9	2450.7	4.50
ET	207	89.44	81.8	2408.1	3.71
ET	208	88.47	90.9	2398.6	4.25
ET	209	82.58	133.1	2372.5	7.18
ET	210	78.96	151.3	2377.3	8.93
ET	211	77.41	150.5	2393.2	9.42
ET	212	79.23	127.3	2391.3	7.67
ET	213	83.59	103.3	2373.8	5.55
ET	214	84.94	111.8	2329.0	5.68
ET	215	79.84	175.7	2297.5	10.04
ET	216	76.86	172.7	2324.9	10.85
ET	217	75.70	118.1	2364.3	7.76
ET	218	79.32	102.2	2340.8	6.09
ET	219	84.34	95.9	2296.2	4.97
ET	220	83.50	107.5	2261.9	5.59

ET	221	83.93	98.9	2259.4	5.08
ET	222	78.15	134.9	2266.7	8.19
ET	223	78.78	161.9	2230.5	9.64
ET	224	83.66	114.8	2198.0	5.88
ET	225	82.54	122.9	2195.5	6.55
ET	226	79.68	132.4	2210.7	7.76
ET	227	81.79	96.2	2219.6	5.35
ET	228	85.68	86.2	2188.8	4.25
ET	229	79.77	152.6	2150.0	8.77
ET	230	87.04	73.6	2159.9	3.42
ET	231	86.54	73.1	2158.0	3.47
ET	232	90.10	67.8	2142.1	2.93
ET	233	85.53	89.0	2121.1	4.38
ET	234	85.12	89.0	2106.5	4.43
ET	235	84.78	95.2	2088.7	4.77
ET	236	82.42	110.2	2072.5	5.88
ET	237	87.62	71.2	2069.9	3.22
ET	238	86.02	88.3	2042.6	4.21
ET	239	80.53	159.8	2012.4	8.88
ET	240	79.48	145.3	2004.1	8.19
ET	241	79.11	149.2	1979.7	8.48
ET	242	80.02	122.7	1985.4	6.89
ET	243	77.29	150.1	1973.6	9.06
ET	244	76.95	112.8	1979.0	6.80
ET	245	73.62	110.2	1992.1	7.34
ET	246	65.34	149.9	2008.9	12.30
ET	247	67.48	102.8	2007.9	8.05
ET	248	69.66	89.2	1996.8	6.60
ET	249	70.47	99.1	1948.5	7.05
ET	250	78.08	71.3	1920.2	4.05
ET	251	84.67	58.1	1888.7	2.71
ET	252	86.58	50.5	1870.6	2.17
ET	253	82.51	63.2	1844.6	3.09
ET	254	78.78	98.0	1817.5	5.50
ET	255	77.58	150.8	1779.7	8.88
ET	256	76.30	152.9	1764.1	9.26
ET	257	68.81	104.2	1823.9	7.67
ET	258	68.40	92.7	1819.5	6.89
ET	259	71.20	85.1	1791.5	5.84
ET	260	70.88	113.5	1763.5	8.01
ET	261	71.83	105.1	1738.1	7.14
ET	262	74.23	83.9	1717.1	5.21
ET	263	73.63	110.4	1677.7	7.05
ET	264	64.69	107.9	1709.2	8.68
ET	265	60.17	102.2	1716.1	9.13
ET	266	57.00	77.9	1727.6	7.34
ET	267	59.29	71.2	1705.0	6.31
ET	268	62.06	114.1	1649.1	9.84
ET	269	65.01	115.0	1620.5	9.22
ET	270	70.84	87.4	1585.5	5.93
ET	271	72.84	129.1	1529.2	8.43
ET	272	63.36	163.7	1549.3	13.71
ET	273	56.34	119.4	1576.0	11.63
ET	-274	53.71	104.9	1568.0	10.72

QC	1	0	0	0	1	0	1
TQTOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY							
TQCARBONACEOUS BOD IN MG/L							
TQDISSOLVED OXYGEN IN MG/L							
L1	10	1					
L2	10	5		10	.4	1	2
LR	1	10000					
L3		.01	1.-6	1.-4	0	-.7	
L5	50	50000	825				
L7	10	2000	820	860	900	940	
L7	10	2000	840	880	920	960	
L8		200	400	800	1400	2000	3000 5000
PL	0.25	100		-4.00			
PL	0.05	100		-0.20			
PL	0.20	100		-8.00			
PL	0.25	100	3.2	-0.70	0.10	-0.05	
L9		40	41	42	43	45	48 60
C1		105.	110.	115.	120.	125.	135. 145.
C5		1.5	1.5	1.0	0.5	1.0	2.5 2.5
C7		6.0	6.0	6.5	7.5	8.5	9.0 9.5
SA			100		100	100	100 100 100
DK			0.1		1.463		
L2	40	2	60000	5	.4	1	1
LR							
L3		.01	1.-6	1.-4	0	-.7	
L5	50.	5000.	895.				
L6	870	99300	962.5				
L7	7.9	2840	895.5	909.5	923.5	937.5	
L7	7.9	2840	902.5	916.5	930.5	944.5	
L8		410	460	500	550	600	650 700 750
PL	0.25	100		-4.00			
PL	0.05	100		-0.20			
PL	0.20	100		-8.00			
PL	0.25	100	3.2	-0.70	0.10	-0.05	
L9		54	55	57	57	57	57 57 57
C1		150	155	160	165	170	180 190 200
C5		1.0	1.0	1.0	1.5	2.0	2.5 3.0 3.0
C7		5.5	5.5	6.0	6.5	7.0	8.0 9.0 9.5
SA		100	100	100	100	100	100 100 100
DK			.2		1.463		
CR		1.047	1.047	1.047	1.0159		
S1		10	1	-1	8	20	1
S2	10	65.5	20	60	1.5		
S2	20	60.0	30	40	1.5		
S2	0	0	0	0			
S2	40	32	50	24.2	1.975	30	4
SR	10	20	2	7			
SK		1.	1.	1.	1.	1.	1.
SR	20	30	2	2			
SR	-40	50	1	2			
S3	10	65.5	844.0	0.	0.	0.	.050
S3		65.5	844.2	0.	.21	5.0	.050
S3		65.5	844.6	4.0	.35	20.0	.050
S3		65.5	845.0	14.0	.61	29.0	.050

S3		65.5	846.0	54.0	1.04	50.0	.050
S3		65.5	847.0	114.0	1.40	67.0	.050
S3		65.5	848.0	194.0	1.55	99.0	.050
S3		65.5	849.0	305.0	1.84	121.0	.050
S3		65.5	850.0	440.0	2.02	152.0	.050
S3		65.5	851.0	605.0	2.20	185.0	.050
S3		65.5	852.0	827.0	2.17	264.0	.050
S3		65.5	853.0	1100.0	2.52	279.0	.050
S3		65.5	854.0	1384.0	2.87	288.0	.050
S3		65.5	855.0	1677.0	3.15	301.0	.050
S3		65.5	856.0	1985.0	3.40	316.0	.050
S3		65.5	857.0	2308.0	3.67	326.0	.050
S3		65.5	858.0	2634.0	3.99	326.0	.050
S3		65.5	859.0	2960.0	4.30	326.0	.050
S3		65.5	861.0	3612.0	4.88	326.0	.050
S3		65.5	863.0	4264.0	5.41	326.0	.050
S3	20	60.0	825.4	0.	0.	0.	.050
S3		60.0	825.6	1.0	.22	9.0	.050
S3		60.0	826.0	10.0	.43	33.0	.050
S3		60.0	826.4	27.0	.64	52.0	.050
S3		60.0	827.4	92.0	1.13	77.0	.050
S3		60.0	828.4	179.0	1.51	96.0	.050
S3		60.0	829.4	287.0	1.79	119.0	.050
S3		60.0	830.4	418.0	2.08	138.0	.050
S3		60.0	831.4	563.0	2.38	152.0	.050
S3		60.0	832.4	723.0	2.65	166.0	.050
S3		60.0	833.4	893.0	2.95	174.0	.050
S3		60.0	834.4	1071.0	3.23	183.0	.050
S3		60.0	835.4	1258.0	3.48	191.0	.050
S3		60.0	836.4	1455.0	3.64	207.0	.050
S3		60.0	837.4	1675.0	3.68	234.0	.050
S3		60.0	838.4	1922.0	3.83	253.0	.050
S3		60.0	839.4	2175.0	4.16	253.0	.050
S3		60.0	840.4	2428.0	4.48	253.0	.050
S3		60.0	842.4	2934.0	5.08	253.0	.050
S3		60.0	844.4	3440.0	5.65	253.0	.050
S3	30	40.0	765.0	0.	0.	0.	.050
S3		40.0	765.2	1.0	.22	9.0	.050
S3		40.0	765.6	10.0	.43	33.0	.050
S3		40.0	766.0	27.0	.64	52.0	.050
S3		40.0	767.0	92.0	1.13	77.0	.050
S3		40.0	768.0	179.0	1.51	96.0	.050
S3		40.0	769.0	287.0	1.79	119.0	.050
S3		40.0	770.0	418.0	2.08	138.0	.050
S3		40.0	771.0	563.0	2.38	152.0	.050
S3		40.0	772.0	723.0	2.65	166.0	.050
S3		40.0	773.0	893.0	2.95	174.0	.050
S3		40.0	774.0	1071.0	3.23	183.0	.050
S3		40.0	775.0	1258.0	3.48	191.0	.050
S3		40.0	776.0	1455.0	3.64	207.0	.050
S3		40.0	777.0	1675.0	3.68	234.0	.050
S3		40.0	778.0	1922.0	3.83	253.0	.050
S3		40.0	779.0	2175.0	4.16	253.0	.050
S3		40.0	780.0	2428.0	4.48	253.0	.050

S3		40.0	782.0	2934.0	5.08	253.0	.050
S3		40.0	784.0	3440.0	5.65	253.0	.050
S3	40	32.0	730.6	0.	0.	0.	.050
S3		32.0	730.8	0.	.21	2.0	.050
S3		32.0	731.2	2.0	.44	6.0	.050
S3		32.0	731.6	6.0	.45	19.0	.050
S3		32.0	732.6	74.0	.84	96.0	.050
S3		32.0	733.6	177.0	1.37	109.0	.050
S3		32.0	734.6	291.0	1.80	120.0	.050
S3		32.0	735.6	421.0	2.12	135.0	.050
S3		32.0	736.6	565.0	2.44	147.0	.050
S3		32.0	737.6	715.0	2.74	155.0	.050
S3		32.0	738.6	878.0	2.99	168.0	.050
S3		32.0	739.6	1050.0	3.26	176.0	.050
S3		32.0	740.6	1230.0	3.51	184.0	.050
S3		32.0	741.6	1418.0	3.74	193.0	.050
S3		32.0	742.6	1618.0	3.83	212.0	.050
S3		32.0	743.6	1844.0	3.86	239.0	.050
S3		32.0	744.6	2094.0	4.05	253.0	.050
S3		32.0	745.6	2347.0	4.37	253.0	.050
S3		32.0	747.6	2853.0	4.98	253.0	.050
S3		32.0	749.6	3359.0	5.55	253.0	.050
S3	50	30.4	722.9	0.	0.	0.	.030
S3		30.4	723.1	2.0	.22	15.0	.030
S3		30.4	723.5	14.0	.45	45.0	.030
S3		30.4	723.9	37.0	.64	74.0	.030
S3		30.4	724.9	130.0	1.12	111.0	.030
S3		30.4	725.9	271.0	1.43	167.0	.030
S3		30.4	726.9	462.0	1.72	218.0	.030
S3		30.4	727.9	701.0	2.04	257.0	.030
S3		30.4	728.9	978.0	2.34	287.0	.030
S3		30.4	729.9	1275.0	2.59	310.0	.030
S3		30.4	730.9	1599.0	2.79	337.0	.030
S3		30.4	731.9	1964.0	2.71	418.0	.030
S3		30.4	732.9	2394.0	2.98	444.0	.030
S3		30.4	733.9	2851.0	3.24	469.0	.030
S3		30.4	734.9	3342.0	3.39	518.0	.030
S3		30.4	735.9	3887.0	3.54	571.0	.030
S3		30.4	736.9	4482.0	3.74	610.0	.030
S3		30.4	737.9	5100.0	4.01	627.0	.030
S3		30.4	739.9	6390.0	4.49	662.0	.030
S3		30.4	741.9	7745.0	4.96	692.0	.030
S3	50	28.4	725.3	0.	0.	0.	.030
S3		28.4	725.5	4.0	.23	30.0	.030
S3		28.4	725.9	22.0	.48	59.0	.030
S3		28.4	726.3	51.0	.67	90.0	.030
S3		28.4	727.3	167.0	1.13	139.0	.030
S3		28.4	728.3	375.0	1.37	249.0	.030
S3		28.4	729.3	644.0	1.75	289.0	.030
S3		28.4	730.3	946.0	2.13	313.0	.030
S3		28.4	731.3	1271.0	2.46	336.0	.030
S3		28.4	732.3	1617.0	2.76	357.0	.030
S3		28.4	733.3	1985.0	3.03	379.0	.030
S3		28.4	734.3	2387.0	3.20	428.0	.030

S3		28.4	735.3	2831.0	3.41	463.0	.030
S3		28.4	736.3	3311.0	3.55	497.0	.030
S3		28.4	737.3	3824.0	3.73	527.0	.030
S3		28.4	738.3	4370.0	3.86	575.0	.030
S3		28.4	739.3	4985.0	3.99	634.0	.030
S3		28.4	740.3	5632.0	4.20	659.0	.030
S3		28.4	742.3	7002.0	4.58	709.0	.030
S3		28.4	744.3	8458.0	5.02	742.0	.030
S3	50	26.3	722.7	0.	0.	0.	.030
S3		26.3	722.8	1.0	.22	9.0	.030
S3		26.3	723.2	8.0	.45	26.0	.030
S3		26.3	723.7	22.0	.62	45.0	.030
S3		26.3	724.7	92.0	1.00	94.0	.030
S3		26.3	725.7	219.0	1.22	167.0	.030
S3		26.3	726.7	436.0	1.38	265.0	.030
S3		26.3	727.7	751.0	1.58	365.0	.030
S3		26.3	728.7	1158.0	1.86	441.0	.030
S3		26.3	729.7	1628.0	2.17	496.0	.030
S3		26.3	730.7	2254.0	2.19	729.0	.030
S3		26.3	731.7	3038.0	2.44	809.0	.030
S3		26.3	732.7	3867.0	2.74	858.0	.030
S3		26.3	733.7	4756.0	3.00	913.0	.030
S3		26.3	734.7	5699.0	3.23	981.0	.030
S3		26.3	735.7	6697.0	3.45	1022.0	.030
S3		26.3	736.7	7750.0	3.68	1067.0	.030
S3		26.3	737.7	8825.0	3.97	1083.0	.030
S3		26.3	739.7	11032.0	4.51	1117.0	.030
S3		26.3	741.7	13278.0	5.08	1129.0	.030
S3	50	24.2	721.6	0.	0.	0.	.030
S3		24.2	721.8	6.0	.22	56.0	.030
S3		24.2	722.2	50.0	.47	150.0	.030
S3		24.2	722.6	118.0	.69	190.0	.030
S3		24.2	723.6	354.0	1.13	270.0	.030
S3		24.2	724.6	656.0	1.41	358.0	.030
S3		24.2	725.6	1079.0	1.60	484.0	.030
S3		24.2	726.6	1606.0	1.88	568.0	.030
S3		24.2	727.6	2215.0	2.16	648.0	.030
S3		24.2	728.6	2903.0	2.41	730.0	.030
S3		24.2	729.6	3687.0	2.62	834.0	.030
S3		24.2	730.6	4563.0	2.87	914.0	.030
S3		24.2	731.6	5511.0	3.10	994.0	.030
S3		24.2	732.6	6555.0	3.32	1081.0	.030
S3		24.2	733.6	7684.0	3.50	1191.0	.030
S3		24.2	734.6	8885.0	3.80	1211.0	.030
S3		24.2	735.6	10105.0	4.09	1229.0	.030
S3		24.2	736.6	11341.0	4.38	1242.0	.030
S3		24.2	738.6	13849.0	4.93	1266.0	.030
S3		24.2	740.6	16405.0	5.45	1289.0	.030
S4		854	835	775	743	742	741
S4		739.5					740
KR			0.10		1.463		
KR			0.15		1.463		
KR			0.25		1.463		
CT	10	740101	40.	3.	0.		
CT		740318	45.	3.	0.		



CT		740723	50.	3.	0.
CT		741017	45.	3.	0.
CT		741206	40.	3.	0.
CT		-741231	40.	3.	0.
CT		740101	150.	1.	0.
CT		-741231	150.	1.	0.
CT		740101	0.1	1.	0.
CT		-741231	0.1	1.	0.
CT		740101	5.	0.	30.
CT		-741231	5.	0.	30.
CT	20	740101	45	4	0
CT		740318	50	4	0
CT		740723	55	4	0
CT		741017	50	4	0
CT		741206	45	4	0
CT		-741231	42	4	0
CT		740101	160	.8	0
CT		-741231	160	.8	0
CT		740101	.05	.15	0
CT		-741231	.05	.15	0
CT		740101	4	0	50
CT		-741231	4	0	50
CT	30	740101	45.	3.	0.
CT		740510	50.	3.	0.
CT		740531	60.	3.	0.
CT		741001	55.	3.	0.
CT		-741231	45.	3.	0.
CT		740101	160.	1.	0.
CT		-741231	160.	1.	0.
CT		740101	.15	4.	0.
CT		-741231	.15	4.	0.
CT		740101	4.5	4.	0.
CT		-741231	4.5	4.	0.
CT	40	740101	45.	3.	0.
CT		740504	50.	3.	0.
CT		740514	55.	3.	0.
CT		740515	60.	3.	0.
CT		741005	55.	3.	0.
CT		741109	50.	3.	0.
CT		741214	45.	3.	0.
CT		-741231	45.	3.	0.
CT		740101	170.	1.	0.
CT		-741231	170.	1.	0.
CT		740101	0.2	1.	0.
CT		-741231	0.2	1.	0.
CT		740101	5.5	0.	30.
CT		-741231	5.5	0.	30.
CT	50	740101	50.	3.	0.
CT		740506	55.	3.	0.
CT		740510	60.	3.	0.
CT		740515	65.	3.	0.
CT		740708	70.	3.	0.
CT		740924	65.	3.	0.
CT		741018	60.	3.	0.

CT	741112	55.	3.	0.			
CT	741206	50.	3.	0.			
CT	-741231	50.	3.	0.			
CT	740101	190.	1.	0.			
CT	-741231	190.	1.	0.			
CT	740101	0.3	1.	0.			
CT	-741231	0.3	1.	0.			
CT	740101	6.0	0.	30.			
CT	-741231	6.0	0.	30.			
I1	740101	741231					
I2		0	TRIB 1 INFLOW RATE - RES #1				
I4	740101	-1	741231	-1.	-1		
I2	2	0	UPPER INFLOW				
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0	UPPER INFLOW - TOTAL DISSOLVED SOLIDS				
I4	740101	105.	741231	105.	-1		
I2		0	UPPER INFLOW - CARBONACEOUS BOD				
I4	740101	0.5	741231	0.5	-1		
I2		0	UPPER INFLOW - DISSOLVED OXYGEN				
I4	740101	12.8	740115	13.1	740215	12.4	740315 11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715 8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115 11.0
I4	741215	12.4	741231	12.8	-1		
I2		0	TRIB 2 INFLOW RATE - RM 60				
I4	740101	-1	741231	-1.	-1		
I2	2	0	TRIB 2 - RM 60				
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0	TRIB 2 - RM 60 - TDS				
I4	740101	150.	741231	150.	-1		
I2		0	TRIB 2 - RM 60 - CBOD				
I4	740101	0.5	741231	0.5	-1		
I2		0	TRIB 2 - RM 60 - DO				
I4	740101	12.6	740115	12.7	740215	13.0	740315 12.6
I4	740415	11.5	740515	9.1	740615	8.6	740715 7.7
I4	740815	7.7	740915	9.0	741015	9.7	741115 11.1
I4	741215	12.6	741231	12.6	-1		
I2		0	TRIB 3 INFLOW RATE - RM 40				
I4	740101	-1	741231	-1.	-1		
I2	1	0	TRIB 3 - RM 40				
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0	TRIB 3 - RM 40 - TDS				
I4	740101	150.	741231	150.	-1		
I2		0	TRIB 3 - RM 40 - CBOD				
I4	740101	0.5	741231	0.5	-1		
I2		0	TRIB 3 - RM 40 - DO				
I4	740101	12.6	740115	12.7	740215	13.0	740315 12.6
I4	740415	11.5	740515	9.1	740615	8.6	740715 7.7
I4	740815	7.7	740915	9.0	741015	9.7	741115 11.1
I4	741215	12.6	741231	12.6	-1		
I2		0	TRIB 4 INFLOW RATE - RM 30				
I4	740101	-1	741231	-1.	-1		

I2	1	0 TRIB 4 - RM 30				
I4	740101	-1.5 740408	-1.5	740422	-3.0 740708	-6.
I4	740826	-5. 741231	-1.5	-1		
I2		0 TRIB 4 - RM 30 - TOTAL DISSOLVED SOLIDS				
I4	740101	160. 741231	160.	-1		
I2		0 TRIB 4 - RM 30 - CARBONACEOUS BOD				
I4	740101	0.6 741231	0.6	-1		
I2	-1	0 TRIB 4 - RM 30 - DISSOLVED OXYGEN				
I4	740101	100. 741231	100.	-1		
ER						

### TEST PROBLEM 3 - Parallel Reservoirs with Calibration Option

The system simulated in this test of the water quality module consists of the same reservoir and stream configuration as Test Problem 1. The unique input to this test problem includes selecting the calibration option (J9 card, Field 4) and specifying the gate operation cards (G1 and G2 cards).

A complete listing of the input data deck is given below. A complete output listing is included with the computer source code distribution.

T1	TESTING HEC5Q WATER QUALITY SIMULATION CAPABILITY									
T2	PARALLEL RIVER SYSTEM...CALIBRATION OPTION									
T3	TEST PROBLEM 3									
J1	0	5	5	3	4	2	0	0		
J2	36	0	0	0	0	0	0	0		
J9		0	0	1						
RL	10	1200000	0	100000	200000	1500000	1600000			
RO	3	30	40	50						
RS	7	100	6300	31300	88000	188000	563000	1688000		
RQ	7	0	20000	30000	40000	50000	50000	50000		
RA	7	10	500	1500	3000	5000	10000	20000		
RE	7	800	825	850	870	900	950	1030		
R3	2	2	2	2	99	99	99	99	99	99
R3	99	99								
CP	10	20000	300	200						
IDCP10-BAKER DAM										
RT	10	30	2.2	.25	12	0				
RL	20	550000	0	2000	550000	952000	1130000			
RO	3	30	40	50						
RS	8	2000	20000	52000	113000	209000	320000	550000	800000	1130000
RQ	8	0	5680	5680	5680	5680	5680	29180	59680	104980
RA	8	150	2100	4500	7600	11800	17000	22400	28600	37200
RE	8	892	910	920	930	940	950	962.5	970	980
R3	2	2	2	2	99	99	99	99	99	99
R3	99	99								
CP	20	20000	300	200						
IDCP20-SMITH DAM										
RT	20	30	2.2	.25	12	0				
CP	30	30000	300	200						
IDCP30-CONF RM60										
RT	30	40	2.2	.25	12	0				
CP	40	30000	300	200						
ID CP40 ** RM 40										
RT	40	50	2.2	.25	12	0				
CP	50	50000	300	200						
IDCP50 ** RM24.2										
RT	50	0	0	0	0	0				
ED										
BF	0	120	0	074050100	120	24				
NOLIST										
IN	10	1MAY74	2059	1814	2125	2243	1947	1836	1735	1587
IN	1549	1509	1413	4584	7520	5061	3549	2931	2801	3866
IN	2752	2293	1962	1793	2476	2528	1958	1650	1462	1344
IN	1810	3581	3367	7629	5501	3699	3057	2603	2294	2073
IN	1894	1750	1596	1423	1313	1251	1052	1312	2547	2301
IN	1803	1360	1185	1200	1456	2434	4601	3121	2769	2230
IN	1846	2107	1918	15259	7046	4185	3113	3167	2814	2295
IN	1910	1606	1448	1535	1368	1196	1039	1032	1013	940
IN	890	890	865	826	783	826	928	847	788	829
IN	804	806	945	801	712	751	914	911	935	792
IN	747	717	823	1416	997	806	759	732	683	653
IN	633	639	621	644	604	598	598	596	601	642
IN	662	838	756	1130	1138	1202	1774	2727	2659	1566

IN	20	1MAY74	430	816	668	1979	1523	1195	1065	847
IN	698	569	455	402	472	424	415	956	613	510
IN	434	381	361	327	289	338	758	355	262	202
IN	169	133	163	192	203	181	166	212	1017	639
IN	639	366	255	194	236	596	432	284	251	745
IN	348	226	179	198	198	164	155	159	177	888
IN	348	386	197	133	134	141	181	407	212	145
IN	126	122	112	108	89	80	87	80	69	68
IN	64	58	47	53	49	39	43	46	60	60
IN	56	50	49	41	43	39	39	43	39	39
IN	47	47	49	43	47	96	151	112	473	212
IN	297	405	201	128	100	79	64	89	102	90
IN	88	165	95	83	184	1167	463	601	676	665
IN	40	1MAY74	645	588	561	488	452	440	425	405
IN	406	398	380	923	1207	1171	1161	1075	1190	1601
IN	1685	1941	1849	1752	1784	1322	645	397	366	458
IN	669	1011	1113	1740	1529	1352	1273	1219	1171	908
IN	575	431	407	375	357	348	243	231	469	598
IN	671	585	369	237	288	360	546	768	900	874
IN	829	712	549	2648	1733	1751	1617	1671	1565	1433
IN	922	465	361	384	353	328	298	305	296	285
IN	279	235	143	142	139	150	226	282	276	191
IN	106	139	183	220	269	268	278	283	311	249
IN	178	172	162	177	135	119	117	117	130	164
IN	161	166	160	117	61	42	51	141	142	108
IN	87	235	418	701	621	790	976	1222	1532	1570
IN	50	1MAY74	3317	3816	3333	3150	2843	2861	2976	2831
IN	3011	3250	3265	4695	13438	10915	9154	8282	7643	7539
IN	6757	6013	4768	3744	3530	3463	3178	2914	2592	2150
IN	1941	1852	1735	1747	1903	2065	1847	1399	1148	1035
IN	978	844	714	809	784	873	969	816	1405	1972
IN	2159	1563	1308	1482	1621	1469	1155	1353	975	1469
IN	1483	1761	1469	4196	7637	5846	5734	4803	4285	3660
IN	3314	2783	1990	1912	1651	1441	937	893	1209	1028
IN	980	990	1160	785	550	695	679	705	701	786
IN	566	627	774	742	696	661	613	578	630	914
IN	930	930	918	981	1006	881	924	829	857	780
IN	684	606	637	670	578	562	558	486	458	440
IN	621	825	1619	2200	2012	1742	1687	2852	4965	4311
QA	10	1MAY74	1270	1320	1360	1410	1440	1470	1480	1480
QA	1480	1480	1790	2190	2480	3480	4490	4420	4300	4210
QA	4130	3960	3720	3370	2470	1910	1950	1940	1890	1570
QA	1270	1680	2210	2480	4000	5510	5350	4400	2930	1970
QA	1570	1570	1570	1560	1560	1530	1510	1480	1830	2690
QA	3120	2840	1640	819	854	900	1540	2750	3250	2860
QA	2100	2030	2030	3600	9280	11000	7280	4130	3250	2180
QA	1750	1470	1210	1290	1320	1320	1290	1270	1230	948
QA	570	600	610	610	621	631	642	707	764	753
QA	741	730	730	741	730	719	707	707	775	775
QA	819	786	494	819	865	654	865	831	797	764
QA	719	685	494	631	580	521	346	540	486	486
QA	521	600	438	797	1410	2000	2050	2130	3460	4590

QA	20	1MAY74	1236	521	387	405	442	949	1602	1572
QA	1528	1040	600	593	590	488	390	497	600	600
QA	597	495	310	220	220	220	226	325	420	417
QA	403	400	286	165	110	110	110	110	275	540
QA	637	627	518	420	420	420	420	320	227	330
QA	430	423	226	110	110	110	110	105	316	440
QA	440	437	430	226	110	110	110	110	110	110
QA	110	105	110	110	110	110	110	110	110	110
QA	110	110	110	110	110	110	75	35	35	35
QA	35	35	35	35	35	35	35	35	35	35
QA	35	35	35	35	36	38	62	85	105	125
QA	182	240	240	240	235	230	178	125	125	125
QA	125	125	125	125	285	463	601	676	665	655

EJ

TI PARALLEL RIVER BASIN TEST WITH PRESET GATE OPERATION (CAL.MODE)  
 TI RESERVOIRS ARE FICTICIOUS ALSO \*\* C.P. OF 10, 20, 30, 40 AND 50  
 TI CONSTITUENTS ARE TEMPERATURE, TDS, CARBONACEOUS BOD AND OXYGEN

JA	740501	740831	5	2	F	0
----	--------	--------	---	---	---	---

EZ

ET	121	64.06	138.8	2385.6	12.35
ET	122	62.44	111.4	2409.1	10.31
ET	123	65.44	126.3	2385.9	10.60
ET	124	60.66	107.7	2456.1	10.34
ET	125	63.36	102.6	2457.1	9.35
ET	126	57.60	124.1	2466.3	12.60
ET	127	58.75	89.7	2507.6	8.88
ET	128	66.16	90.8	2484.1	7.72
ET	129	66.36	138.3	2446.0	11.48
ET	130	67.68	96.1	2494.6	7.85
ET	131	70.23	130.1	2473.9	10.09
ET	132	66.18	147.4	2470.1	12.21
ET	133	62.56	144.1	2518.4	13.40
ET	134	72.00	149.0	2492.1	11.23
ET	135	71.49	175.2	2472.3	13.02
ET	136	74.91	133.5	2480.6	9.06
ET	137	78.21	176.4	2413.2	10.65
ET	138	75.06	127.7	2486.3	8.59
ET	139	72.84	131.9	2525.7	9.60
ET	140	73.33	118.8	2544.2	8.55
ET	141	81.63	95.9	2508.9	5.46
ET	142	77.95	142.0	2476.5	8.68
ET	143	73.94	148.7	2521.6	10.31
ET	144	68.99	151.9	2563.9	12.01
ET	145	67.24	99.2	2614.1	8.21
ET	146	69.55	97.3	2617.0	7.72
ET	147	64.69	119.9	2640.5	10.76
ET	148	71.17	97.5	2626.2	7.47
ET	149	73.54	145.0	2558.2	10.02
ET	150	80.04	107.4	2543.5	6.31
ET	151	77.13	137.9	2528.9	8.64
ET	152	70.47	132.4	2598.9	10.09
ET	153	72.09	120.6	2629.7	9.06
ET	154	78.21	86.5	2621.4	5.50
ET	155	79.57	99.9	2598.9	6.09

ET	156	76.06	133.5	2597.6	8.93
ET	157	77.65	133.5	2579.1	8.50
ET	158	75.63	175.0	2568.3	11.63
ET	159	78.80	137.6	2562.9	8.34
ET	160	82.00	138.6	2539.4	7.67
ET	161	77.77	212.1	2535.9	13.02
ET	162	69.73	170.9	2626.5	13.27
ET	163	71.67	119.4	2644.6	8.88
ET	164	73.76	105.8	2658.3	7.56
ET	165	79.68	93.8	2632.5	5.75
ET	166	72.72	153.5	2601.4	10.85
ET	167	71.62	145.3	2627.1	10.72
ET	168	71.26	110.0	2663.7	8.34
ET	169	73.63	124.3	2646.5	8.88
ET	170	77.79	129.1	2600.1	8.21
ET	171	82.04	144.8	2542.0	8.05
ET	172	77.67	199.4	2553.1	12.44
ET	173	81.25	107.0	2592.8	6.22
ET	174	72.32	143.9	2625.9	10.51
ET	175	71.35	151.0	2647.8	11.52
ET	176	71.62	129.3	2649.1	9.80
ET	177	77.68	96.6	2622.1	6.13
ET	178	75.09	129.3	2628.7	8.93
ET	179	74.39	127.5	2615.1	8.88
ET	180	74.98	130.1	2601.1	8.84
ET	181	74.88	210.0	2568.0	14.18
ET	182	80.55	135.6	2566.8	8.01
ET	183	80.89	185.1	2524.8	10.67
ET	184	83.64	204.0	2486.3	10.76
ET	185	83.70	200.2	2483.8	10.56
ET	186	82.60	140.0	2503.8	7.58
ET	187	83.17	106.5	2566.4	5.97
ET	188	89.10	87.1	2546.7	4.14
ET	189	89.42	102.4	2502.9	4.72
ET	190	86.77	141.1	2467.9	6.85
ET	191	82.85	165.3	2461.5	8.77
ET	192	77.04	165.3	2538.5	10.65
ET	193	79.90	105.1	2557.9	6.38
ET	194	87.21	86.2	2531.5	4.30
ET	195	82.40	168.8	2466.9	9.26
ET	196	78.49	168.8	2498.7	10.43
ET	197	76.98	140.4	2528.0	9.08
ET	198	85.08	91.6	2508.9	4.79
ET	199	83.80	141.6	2436.7	7.47
ET	200	81.34	201.3	2425.6	11.30
ET	201	77.05	147.3	2496.5	9.51
ET	202	77.18	127.0	2509.5	8.30
ET	203	82.02	109.7	2467.6	6.22
ET	204	79.34	124.5	2445.3	7.29
ET	205	80.82	119.4	2435.2	6.85
ET	206	84.99	86.9	2450.7	4.50
ET	207	89.44	81.8	2408.1	3.71
ET	208	88.47	90.9	2398.6	4.25
ET	209	82.58	133.1	2372.5	7.18



ET	210	78.96	151.3	2377.3	8.93			
ET	211	77.41	150.5	2393.2	9.42			
ET	212	79.23	127.3	2391.3	7.67			
ET	213	83.59	103.3	2373.8	5.55			
ET	214	84.94	111.8	2329.0	5.68			
ET	215	79.84	175.7	2297.5	10.04			
ET	216	76.86	172.7	2324.9	10.85			
ET	217	75.70	118.1	2364.3	7.76			
ET	218	79.32	102.2	2340.8	6.09			
ET	219	84.34	95.9	2296.2	4.97			
ET	220	83.50	107.5	2261.9	5.59			
ET	221	83.93	98.9	2259.4	5.08			
ET	222	78.15	134.9	2266.7	8.19			
ET	223	78.78	161.9	2230.5	9.64			
ET	224	83.66	114.8	2198.0	5.88			
ET	225	82.54	122.9	2195.5	6.55			
ET	226	79.68	132.4	2210.7	7.76			
ET	227	81.79	96.2	2219.6	5.35			
ET	228	85.68	86.2	2188.8	4.25			
ET	229	79.77	152.6	2150.0	8.77			
ET	230	87.04	73.6	2159.9	3.42			
ET	231	86.54	73.1	2158.0	3.47			
ET	232	90.10	67.8	2142.1	2.93			
ET	233	85.53	89.0	2121.1	4.38			
ET	234	85.12	89.0	2106.5	4.43			
ET	235	84.78	95.2	2088.7	4.77			
ET	236	82.42	110.2	2072.5	5.88			
ET	237	87.62	71.2	2069.9	3.22			
ET	238	86.02	88.3	2042.6	4.21			
ET	239	80.53	159.8	2012.4	8.88			
ET	-240	79.48	145.3	2004.1	8.19			
QC	1	0	0	0	1	0	1	
TQ	TOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY							
TQ	CARBONACEOUS BOD IN MG/L							
TQ	DISSOLVED OXYGEN IN MG/L							
L1	10	1						
L2	10	5	10	.6	2	1		
LR	2	10000	1	5000				
L3		.01	1.-6	1.-4	0	-.7		
L5	50	50000	825					
L7	10	2000	820	860	900	940		
L7	10	2000	840	880	920	960		
L8		200	400	800	1400	2000	3000	5000
PL	0.25	100		-4.00				
PL	0.05	100		-0.20				
PL	0.20	100		-8.00				
PL	0.25	100	3.2	-0.70	0.10	-0.05		
L9		40	41	42	43	45	48	60
C1		120.	120.	120.	120.	120.	180.	180.
C5		0.5	0.5	0.5	0.5	0.5	0.5	0.5
C7		9.1	9.1	9.1	9.1	9.1	9.1	9.1
SA		100	100	100	100	100	100	100
DK			0.1	1.463				

L2	20	2		5	.6	2	1		
LR	3	60000.							
L3		.01	1.-6	1.-4	0	-.7			
L5	1	10	895.5						
L6	870	99300	962.5						
L7	7.9	2840	895.5	909.5	923.5	937.5			
L7	7.9	2840	902.5	916.5	930.5	944.5			
L8		410	460	500	550	600	650	700	750
PL	0.25	100		-4.00					
PL	0.05	100		-0.20					
PL	0.20	100		-8.00					
PL	0.25	100	3.2	-0.70	0.10	-0.05			
L9		54	55	57	57	57	57	57	57
C1		160	190	190	190	190	190	190	190
C5		.3	.3	.3	.3	.3	.3	.3	.3
C7		8.4	8.7	9.2	9.2	9.2	9.2	9.2	9.2
SA		100	100	100	100	100	100	100	100
DK			.2		1.463				
CR		1.047	1.047	1.047	1.0159				
S1		10	1	0	10	20	1		
S2	10	65.5	30	60	1.5				
S2	20	4.7	30	0.	1.5				
S2	30	60	40	40	2	45	3		
S2	40	40	50	24.2	1.975	30	4		
SR	10	30	1	2					
SR	20	30	1	2					
SR	30	40	1	2					
SR	-40	50	1	2					
S3	10	65.5	844.0	0.	0.	0.	.050		
S3			844.2	0.	.21	5.0	.050		
S3			844.6	4.0	.35	20.0	.050		
S3			845.0	14.0	.61	29.0	.050		
S3			846.0	54.0	1.04	50.0	.050		
S3			847.0	114.0	1.40	67.0	.050		
S3			848.0	194.0	1.55	99.0	.050		
S3			849.0	305.0	1.84	121.0	.050		
S3			850.0	440.0	2.02	152.0	.050		
S3			851.0	605.0	2.20	185.0	.050		
S3			852.0	827.0	2.17	264.0	.050		
S3			853.0	1100.0	2.52	279.0	.050		
S3			854.0	1384.0	2.87	288.0	.050		
S3			855.0	1677.0	3.15	301.0	.050		
S3			856.0	1985.0	3.40	316.0	.050		
S3			857.0	2308.0	3.67	326.0	.050		
S3			858.0	2634.0	3.99	326.0	.050		
S3			859.0	2960.0	4.30	326.0	.050		
S3			861.0	3612.0	4.88	326.0	.050		
S3			863.0	4264.0	5.41	326.0	.050		
S3	30	60.	825.4	0.	0.	0.	.050		
S3			825.6	1.0	.22	9.0	.050		
S3			826.0	10.0	.43	33.0	.050		
S3			826.4	27.0	.64	52.0	.050		
S3			827.4	92.0	1.13	77.0	.050		
S3			828.4	179.0	1.51	96.0	.050		

S3			829.4	287.0	1.79	119.0	.050
S3			830.4	418.0	2.08	138.0	.050
S3			831.4	563.0	2.38	152.0	.050
S3			832.4	723.0	2.65	166.0	.050
S3			833.4	893.0	2.95	174.0	.050
S3			834.4	1071.0	3.23	183.0	.050
S3			835.4	1258.0	3.48	191.0	.050
S3			836.4	1455.0	3.64	207.0	.050
S3			837.4	1675.0	3.68	234.0	.050
S3			838.4	1922.0	3.83	253.0	.050
S3			839.4	2175.0	4.16	253.0	.050
S3			840.4	2428.0	4.48	253.0	.050
S3			842.4	2934.0	5.08	253.0	.050
S3			844.4	3440.0	5.65	253.0	.050
S3	20	4.7	859.6	0.	0.	0.	0.050
S3			859.8	1.5	0.16	24.	0.050
S3			860.2	22.0	0.46	70.	0.050
S3			860.6	56.1	0.73	104.	0.050
S3			861.6	178.2	1.28	128.	0.050
S3			862.6	307.7	1.82	134.	0.050
S3			863.6	442.8	2.28	140.	0.050
S3			864.6	583.8	2.57	142.	0.050
S3			865.6	729.1	2.97	147.	0.050
S3			866.6	878.1	3.19	149.	0.050
S3			867.6	1030.6	3.49	156.	0.050
S3			868.6	1186.8	3.78	162.	0.050
S3			869.6	1346.6	4.06	168.	0.050
S3			870.6	1510.1	4.32	174.	0.050
S3			871.6	1677.2	4.57	180.	0.050
S3			872.6	1848.0	4.81	186.	0.050
S3			873.6	2022.4	5.04	192.	0.050
S3			874.6	2200.5	5.27	198.	0.050
S3			876.6	2567.5	5.69	210.	0.050
S3			878.6	2949.1	6.10	222.	0.050
S3	30	0.	825.4	0.	0.	0.	.050
S3			825.6	1.0	.22	9.0	.050
S3			826.0	10.0	.43	33.0	.050
S3			826.4	27.0	.64	52.0	.050
S3			827.4	92.0	1.13	77.0	.050
S3			828.4	179.0	1.51	96.0	.050
S3			829.4	287.0	1.79	119.0	.050
S3			830.4	418.0	2.08	138.0	.050
S3			831.4	563.0	2.38	152.0	.050
S3			832.4	723.0	2.65	166.0	.050
S3			833.4	893.0	2.95	174.0	.050
S3			834.4	1071.0	3.23	183.0	.050
S3			835.4	1258.0	3.48	191.0	.050
S3			836.4	1455.0	3.64	207.0	.050
S3			837.4	1675.0	3.68	234.0	.050
S3			838.4	1922.0	3.83	253.0	.050
S3			839.4	2175.0	4.16	253.0	.050
S3			840.4	2428.0	4.48	253.0	.050
S3			842.4	2934.0	5.08	253.0	.050
S3			844.4	3440.0	5.65	253.0	.050

S3	40	40.0	765.0	0.	0.	0.	.050
S3			765.2	1.0	.22	9.0	.050
S3			765.6	10.0	.43	33.0	.050
S3			766.0	27.0	.64	52.0	.050
S3			767.0	92.0	1.13	77.0	.050
S3			768.0	179.0	1.51	96.0	.050
S3			769.0	287.0	1.79	119.0	.050
S3			770.0	418.0	2.08	138.0	.050
S3			771.0	563.0	2.38	152.0	.050
S3			772.0	723.0	2.65	166.0	.050
S3			773.0	893.0	2.95	174.0	.050
S3			774.0	1071.0	3.23	183.0	.050
S3			775.0	1258.0	3.48	191.0	.050
S3			776.0	1455.0	3.64	207.0	.050
S3			777.0	1675.0	3.68	234.0	.050
S3			778.0	1922.0	3.83	253.0	.050
S3			779.0	2175.0	4.16	253.0	.050
S3			780.0	2428.0	4.48	253.0	.050
S3			782.0	2934.0	5.08	253.0	.050
S3			784.0	3440.0	5.65	253.0	.050
S3	50	32.0	730.6	0.	0.	0.	.050
S3			730.8	0.	.21	2.0	.050
S3			731.2	2.0	.44	6.0	.050
S3			731.6	6.0	.45	19.0	.050
S3			732.6	74.0	.84	96.0	.050
S3			733.6	177.0	1.37	109.0	.050
S3			734.6	291.0	1.80	120.0	.050
S3			735.6	421.0	2.12	135.0	.050
S3			736.6	565.0	2.44	147.0	.050
S3			737.6	715.0	2.74	155.0	.050
S3			738.6	878.0	2.99	168.0	.050
S3			739.6	1050.0	3.26	176.0	.050
S3			740.6	1230.0	3.51	184.0	.050
S3			741.6	1418.0	3.74	193.0	.050
S3			742.6	1618.0	3.83	212.0	.050
S3			743.6	1844.0	3.86	239.0	.050
S3			744.6	2094.0	4.05	253.0	.050
S3			745.6	2347.0	4.37	253.0	.050
S3			747.6	2853.0	4.98	253.0	.050
S3			749.6	3359.0	5.55	253.0	.050
S3	50	30.4	722.9	0.	0.	0.	.030
S3			723.1	2.0	.22	15.0	.030
S3			723.5	14.0	.45	45.0	.030
S3			723.9	37.0	.64	74.0	.030
S3			724.9	130.0	1.12	111.0	.030
S3			725.9	271.0	1.43	167.0	.030
S3			726.9	462.0	1.72	218.0	.030
S3			727.9	701.0	2.04	257.0	.030
S3			728.9	978.0	2.34	287.0	.030
S3			729.9	1275.0	2.59	310.0	.030
S3			730.9	1599.0	2.79	337.0	.030
S3			731.9	1964.0	2.71	418.0	.030
S3			732.9	2394.0	2.98	444.0	.030
S3			733.9	2851.0	3.24	469.0	.030

S3			734.9	3342.0	3.39	518.0	.030
S3			735.9	3887.0	3.54	571.0	.030
S3			736.9	4482.0	3.74	610.0	.030
S3			737.9	5100.0	4.01	627.0	.030
S3			739.9	6390.0	4.49	662.0	.030
S3			741.9	7745.0	4.96	692.0	.030
S3	50	28.4	725.3	0.	0.	0.	.030
S3			725.5	4.0	.23	30.0	.030
S3			725.9	22.0	.48	59.0	.030
S3			726.3	51.0	.67	90.0	.030
S3			727.3	167.0	1.13	139.0	.030
S3			728.3	375.0	1.37	249.0	.030
S3			729.3	644.0	1.75	289.0	.030
S3			730.3	946.0	2.13	313.0	.030
S3			731.3	1271.0	2.46	336.0	.030
S3			732.3	1617.0	2.76	357.0	.030
S3			733.3	1985.0	3.03	379.0	.030
S3			734.3	2387.0	3.20	428.0	.030
S3			735.3	2831.0	3.41	463.0	.030
S3			736.3	3311.0	3.55	497.0	.030
S3			737.3	3824.0	3.73	527.0	.030
S3			738.3	4370.0	3.86	575.0	.030
S3			739.3	4985.0	3.99	634.0	.030
S3			740.3	5632.0	4.20	659.0	.030
S3			742.3	7002.0	4.58	709.0	.030
S3			744.3	8458.0	5.02	742.0	.030
S3	50	26.3	722.7	0.	0.	0.	.030
S3			722.8	1.0	.22	9.0	.030
S3			723.2	8.0	.45	26.0	.030
S3			723.7	22.0	.62	45.0	.030
S3			724.7	92.0	1.00	94.0	.030
S3			725.7	219.0	1.22	167.0	.030
S3			726.7	436.0	1.38	265.0	.030
S3			727.7	751.0	1.58	365.0	.030
S3			728.7	1158.0	1.86	441.0	.030
S3			729.7	1628.0	2.17	496.0	.030
S3			730.7	2254.0	2.19	729.0	.030
S3			731.7	3038.0	2.44	809.0	.030
S3			732.7	3867.0	2.74	858.0	.030
S3			733.7	4756.0	3.00	913.0	.030
S3			734.7	5699.0	3.23	981.0	.030
S3			735.7	6697.0	3.45	1022.0	.030
S3			736.7	7750.0	3.68	1067.0	.030
S3			737.7	8825.0	3.97	1083.0	.030
S3			739.7	11032.0	4.51	1117.0	.030
S3			741.7	13278.0	5.08	1129.0	.030
S3	50	24.2	721.6	0.	0.	0.	.030
S3			721.8	6.0	.22	56.0	.030
S3			722.2	50.0	.47	150.0	.030
S3			722.6	118.0	.69	190.0	.030
S3			723.6	354.0	1.13	270.0	.030
S3			724.6	656.0	1.41	358.0	.030
S3			725.6	1079.0	1.60	484.0	.030
S3			726.6	1606.0	1.88	568.0	.030

S3		727.6	2215.0	2.16	648.0	.030			
S3		728.6	2903.0	2.41	730.0	.030			
S3		729.6	3687.0	2.62	834.0	.030			
S3		730.6	4563.0	2.87	914.0	.030			
S3		731.6	5511.0	3.10	994.0	.030			
S3		732.6	6555.0	3.32	1081.0	.030			
S3		733.6	7684.0	3.50	1191.0	.030			
S3		734.6	8885.0	3.80	1211.0	.030			
S3		735.6	10105.0	4.09	1229.0	.030			
S3		736.6	11341.0	4.38	1242.0	.030			
S3		738.6	13849.0	4.93	1266.0	.030			
S3		740.6	16405.0	5.45	1289.0	.030			
S4	854	835	870	835	775	743	742	741	740
S4	739.5								
KR		0.10		1.463					
KR		0.15		1.463					
KR		0.20		1.463					
KR		0.25		1.463					
CT	10	740101	40.	3.	0.				
CT		740318	45.	3.	0.				
CT		740723	50.	3.	0.				
CT		741017	45.	3.	0.				
CT		741206	40.	3.	0.				
CT		-741231	40.	3.	0.				
CT		740101	150.	1.	0.				
CT		-741231	150.	1.	0.				
CT		740101	0.1	1.	0.				
CT		-741231	0.1	1.	0.				
CT		740101	5.	0.	30.				
CT		-741231	5.	0.	30.				
CT	20	740101	45	4	0				
CT		740318	50	4	0				
CT		740723	55	4	0				
CT		741017	50	4	0				
CT		741206	45	4	0				
CT		-741231	42	4	0				
CT		740101	160	.8	0				
CT		-741231	160	.8	0				
CT		740101	.05	.15	0				
CT		-741231	.05	.15	0				
CT		740101	4	0	50				
CT		-741231	4	0	50				
CT	30	740101	45.	3.	0.				
CT		740510	50.	3.	0.				
CT		740531	60.	3.	0.				
CT		741001	55.	3.	0.				
CT		-741231	45.	3.	0.				
CT		740101	160.	1.	0.				
CT		-741231	160.	1.	0.				
CT		740101	.15	4.	0.				
CT		-741231	.15	4.	0.				
CT		740101	4.5	4.	0.				
CT		-741231	4.5	4.	0.				

CT	40	740101	45.	3.	0.
CT		740504	50.	3.	0.
CT		740514	55.	3.	0.
CT		740515	60.	3.	0.
CT		741005	55.	3.	0.
CT		741109	50.	3.	0.
CT		741214	45.	3.	0.
CT		-741231	45.	3.	0.
CT		740101	170.	1.	0.
CT		-741231	170.	1.	0.
CT		740101	0.2	1.	0.
CT		-741231	0.2	1.	0.
CT		740101	5.5	0.	30.
CT		-741231	5.5	0.	30.
CT	50	740101	50.	3.	0.
CT		740506	55.	3.	0.
CT		740510	60.	3.	0.
CT		740515	65.	3.	0.
CT		740708	70.	3.	0.
CT		740924	65.	3.	0.
CT		741018	60.	3.	0.
CT		741112	55.	3.	0.
CT		741206	50.	3.	0.
CT		-741231	50.	3.	0.
CT		740101	190.	1.	0.
CT		-741231	190.	1.	0.
CT		740101	0.3	1.	0.
CT		-741231	0.3	1.	0.
CT		740101	6.0	0.	30.
CT		-741231	6.0	0.	30.
I1		740101	741231		
I2		0	TRIB 1 ...	BAKER INFLOW RATE ...	RES # 1
I4		740101	-0.5	740408	-0.5 740422 -0.7 740708 -0.3
I4		740826	-0.3	741231	-0.5 -1
I2		1	0	TRIB 1 ...	BAKER INFLOW TEMPERATURE
I4		740101	-1.5	740408	-1.5 740422 -5.0 740708 -8.
I4		740826	-5.	741231	-1.5 -1
I2		0	TRIB 1 ...	BAKER INFLOW -	TOTAL DISSOLVED SOLIDS
I4		740101	105.	741231	105. -1
I2		0	TRIB 1 ...	BAKER INFLOW -	CARBONACEOUS BOD
I4		740101	0.5	741231	0.5 -1
I2		0	TRIB 1 ...	BAKER INFLOW -	DISSOLVED OXYGEN
I4		740101	12.8	740115	13.1 740215 12.4 740315 11.8
I4		740415	11.7	740515	9.3 740615 8.9 740715 8.2
I4		740815	7.8	740915	9.7 741015 10.0 741115 11.0
I4		741215	12.4	741231	12.8 -1
I2		0	TRIB 2 ...	SMITH INFLOW RATE ...	RES # 1
I4		740101	-0.5	740408	-0.5 740422 -0.7 740708 -0.7
I4		740826	-0.7	741231	-0.5 -1
I2		1	0	TRIB 2 ...	SMITH INFLOW TEMPERATURE
I4		740101	-0.1	740125	2.0 740210 1.2 740224 -1.8
I4		740310	0.1	740324	-10.4 740414 -15.8 740428 -24.3
I4		740512	-15.6	740527	-16.0 740609 -11.0 740623 -15.6

I4	740714	-9.1	740728	-12.3	740811	-10.3	740825	-15.0
I4	740908	-15.5	740922	-17.8	741014	-11.1	741028	-6.1
I4	741110	-6.5	741124	-4.4	741208	-6.2	741231	1.5
I4	-1							
I2		0	TRIB 2 ... SMITH INFLOW - TDS					
I4	740101	140	740115	110	740215	240	740315	400
I4	740415	130	740515	1095	740615	80	740715	100
I4	740815	70	740915	50	741015	100	741115	90
I4	741215	310	741231	360	-1			
I2		0	TRIB 2 ... SMITH INFLOW - CBOD					
I4	740101	.2	740115	.2	740215	.4	740315	.5
I4	740415	.2	740515	1.8	740615	.1	740715	.2
I4	740815	.1	740915	.1	741015	.2	741115	.1
I4	741215	.5	741231	.6	-1			
I2		0	TRIB 2 ... SMITH INFLOW - DISSOLVED OXYGEN					
I4	740101	13.1	740115	13.1	740215	12.4	740315	11.8
I4	740415	11.8	740515	9.4	740615	9.0	740715	8.3
I4	740815	7.8	740915	9.7	741015	10.0	741115	11.0
I4	741215	12.4	741231	12.8	-1			
I2		0	TRIB 3 INFLOW RATE - RM 45 & RES # 2					
I4	740101	-1	741231	-1.	-1			
I2	1		OTRIB 3 - RM 45					
I4	740101	-1.5	740408	-1.5	740422	-3.0	740708	-4.
I4	740826	-3.	741231	-1.5	-1			
I2		0	TRIB 3 - RM 45 - TOTAL DISSOLVED SOLIDS					
I4	740101	160.	741231	160.	-1			
I2		0	TRIB 3 - RM 45 - CARBONACEOUS BOD					
I4	740101	0.6	741231	0.6	-1			
I2		0	TRIB 3 - RM 45 - DISSOLVED OXYGEN					
I4	740101	12.8	740115	13.1	740215	12.4	740315	11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715	8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115	11.0
I4	741215	12.4	741231	12.8	-1			
I2		0	TRIB 4 INFLOW RATE - RM 30					
I4	740826	-1.	741231	-1.	-1			
I2	1		OTRIB 4 - RM 30					
I4	740101	-1.5	740408	-1.5	740422	-3.0	740708	-6.
I4	740826	-5.	741231	-1.5	-1			
I2		0	TRIB 4 - RM 30 - TOTAL DISSOLVED SOLIDS					
I4	740101	160.	741231	160.	-1			
I2		0	TRIB 4 - RM 30 - CARBONACEOUS BOD					
I4	740101	0.6	741231	0.6	-1			
I2		0	TRIB 4 - RM 30 - DISSOLVED OXYGEN					
I4	740101	12.8	740115	13.1	740215	12.4	740315	11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715	8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115	11.0
I4	741215	12.4	741231	12.8	-1			
G1740501	740831							
G2	20	740501	740515	0	0	2	1	3
G2	10	740501	740520	0	0	1	2	3
G2	20	740516	740620	0	0	3	1	1
G2	20	740621	740831	0	0	2	2	2
G2	10	740521	740710	0	0	2	3	3
G2	10	740711	-740831	0	0	2	4	2
ER								



#### TEST PROBLEM 4 - Tandem Reservoirs with Phytoplankton Option

The system simulated in this test of the water quality module consists of the same reservoir and stream configuration as Test Problem 2. The unique input to this test problem, includes selecting the phytoplankton option (QC card, Field 9), omitting constituent title card (TQ cards), and specifying the necessary stream objective function values (CT cards) and the local inflow quality cards (I1-I4 cards).

A complete listing of the input data deck is given below. A complete output listing is included with the computer source code distribution.

T1	TESTING HEC5Q WATER QUALITY SIMULATION CAPABILITY									
T2	TANDEM RIVER SYSTEM...PHYTOPLANKTON OPTION									
T3	TEST PROBLEM 4									
J1	0	5	5	3	4	2	0	0		
J2	36	0	0	0	0	0	0			
J9										
RL	10	1200000	0	100000	200000	1500000	1600000			
RO	3	2	3	4						
RS	7	100	6300	31300	88000	188000	563000	1688000		
RQ	7	0	20000	30000	40000	50000	50000	50000		
RA	7	10	500	1500	3000	5000	10000	20000		
RE	7	800	825	850	870	900	950	1030		
R3	2	2	2	2	99	99	99	99	99	99
R3	99	99								
CP	10	15000	300	200						
IDCP10-HAYES DAM										
RT	10	20	2.2	.25	12	0				
CP	20	12000	300	200						
ID	CP20	** RM60								
RT	20	30	2.2	.25	12	0				
CP	30	12000	300	200						
ID	CP30	** RM40								
RT	30	40	2.2	.25	12	0				
RL	40	550000	0	2000	550000	952000	1130000			
RO	1	5								
RS	8	2000	20000	52000	113000	209000	320000	550000	800000	1130000
RQ	8	0	5680	5680	5680	5680	5680	29180	59680	104980
RA	8	150	2100	4500	7600	11800	17000	22400	28600	37200
RE	8	892	910	920	930	940	950	962.5	970	980
R3	2	2	2	2	99	99	99	99	99	99
R3	99	99								
CP	40	10000	300	200						
IDCP40-DAVIS DAM										
RT	40	50	2.2	.25	12	0				
CP	50	50000	300	200						
IDCP50	** RM24.2									
RT	50	0	0	0	0	0				
ED										
BF	0	120	0	074050100	120	24				
NOLIST										
IN	10	1MAY74	2059	1814	2125	2243	1947	1836	1735	1587
IN	1549	1509	1413	4584	7520	5061	3549	2931	2801	3866
IN	2752	2293	1962	1793	2476	2528	1958	1650	1462	1344
IN	1810	3581	3367	7629	5501	3699	3057	2603	2294	2073
IN	1894	1750	1596	1423	1313	1251	1052	1312	2547	2301
IN	1803	1360	1185	1200	1456	2434	4601	3121	2769	2230
IN	1846	2107	1918	15259	7046	4185	3113	3167	2814	2295
IN	1910	1606	1448	1535	1368	1196	1039	1032	1013	940
IN	890	890	865	826	783	826	928	847	788	829
IN	804	806	945	801	712	751	914	911	935	792
IN	747	717	823	1416	997	806	759	732	683	653
IN	633	639	621	644	604	598	598	596	601	642
IN	662	838	756	1130	1138	1202	1774	2727	2659	1566

IN	20	1MAY74	645	588	561	488	452	440	425	405
IN	406	398	380	923	1207	1171	1161	1075	1190	1601
IN	1685	1941	1849	1752	1784	1322	645	397	366	458
IN	669	1011	1113	1740	1529	1352	1273	1219	1171	908
IN	575	431	407	375	357	348	243	231	469	598
IN	671	585	369	237	288	360	546	768	900	874
IN	829	712	549	2648	1733	1751	1617	1671	1565	1433
IN	922	465	361	384	353	328	298	305	296	285
IN	279	235	143	142	139	150	226	282	276	191
IN	106	139	183	220	269	268	278	283	311	249
IN	178	172	162	177	135	119	117	117	130	164
IN	161	166	160	117	61	42	51	141	142	108
IN	87	235	418	701	621	790	976	1222	1532	1570
IN	30	1MAY74	645	588	561	488	452	440	425	405
IN	406	398	380	923	1207	1171	1161	1075	1190	1601
IN	1685	1941	1849	1752	1784	1322	645	397	366	458
IN	669	1011	1113	1740	1529	1352	1273	1219	1171	908
IN	575	431	407	375	357	348	243	231	469	598
IN	671	585	369	237	288	360	546	768	900	874
IN	829	712	549	2648	1733	1751	1617	1671	1565	1433
IN	922	465	361	384	353	328	298	305	296	285
IN	279	235	143	142	139	150	226	282	276	191
IN	106	139	183	220	269	268	278	283	311	249
IN	178	172	162	177	135	119	117	117	130	164
IN	161	166	160	117	61	42	51	141	142	108
IN	87	235	418	701	621	790	976	1222	1532	1570
IN	50	1MAY74	3317	3816	3333	3150	2843	2861	2976	2831
IN	3011	3250	3265	4695	13438	10915	9154	8282	7643	7539
IN	6757	6013	4768	3744	3530	3463	3178	2914	2592	2150
IN	1941	1852	1735	1747	1903	2065	1847	1399	1148	1035
IN	978	844	714	809	784	873	969	816	1405	1972
IN	2159	1563	1308	1482	1621	1469	1155	1353	975	1469
IN	1483	1761	1469	4196	7637	5846	5734	4803	4285	3660
IN	3314	2783	1990	1912	1651	1441	937	893	1209	1028
IN	980	990	1160	785	550	695	679	705	701	786
IN	566	627	774	742	696	661	613	578	630	914
IN	930	930	918	981	1006	881	924	829	857	780
IN	684	606	637	670	578	562	558	486	458	440
IN	621	825	1619	2200	2012	1742	1687	2852	4965	4311
QA	10	1MAY74	1270	1320	1360	1410	1440	1470	1480	1480
QA	1480	1480	1790	2190	2480	3480	4490	4420	4300	4210
QA	4130	3960	3720	3370	2470	1910	1950	1940	1890	1570
QA	1270	1680	2210	2480	4000	5510	5350	4400	2930	1970
QA	1570	1570	1570	1560	1560	1530	1510	1480	1830	2690
QA	3120	2840	1640	819	854	900	1540	2750	3250	2860
QA	2100	2030	2030	3600	9280	11000	7280	4130	3250	2180
QA	1750	1470	1210	1290	1320	1320	1290	1270	1230	948
QA	570	600	610	610	621	631	642	707	764	753
QA	741	730	730	741	730	719	707	707	775	775
QA	819	786	494	819	865	654	865	831	797	764
QA	719	685	494	631	580	521	346	540	486	486
QA	521	600	438	797	1410	2000	2050	2130	3460	4590
EJ										

TI	FICTICIOUS TANDEM RIVER BASIN TEST OF HEC-5Q WITH WATER QUALITY					
TI	UPPER AND LOWER RESERVOIRS ARE FICTICIOUS ALSO					
TI	PHYTOPLANKTON OPTION					
JA	740501	740831	5	2	F	0
EZ	-1					
ET	121	64.06	138.8	2385.6	12.35	
ET	122	62.44	111.4	2409.1	10.31	
ET	123	65.44	126.3	2385.9	10.60	
ET	124	60.66	107.7	2456.1	10.34	
ET	125	63.36	102.6	2457.1	9.35	
ET	126	57.60	124.1	2466.3	12.60	
ET	127	58.75	89.7	2507.6	8.88	
ET	128	66.16	90.8	2484.1	7.72	
ET	129	66.36	138.3	2446.0	11.48	
ET	130	67.68	96.1	2494.6	7.85	
ET	131	70.23	130.1	2473.9	10.09	
ET	132	66.18	147.4	2470.1	12.21	
ET	133	62.56	144.1	2518.4	13.40	
ET	134	72.00	149.0	2492.1	11.23	
ET	135	71.49	175.2	2472.3	13.02	
ET	136	74.91	133.5	2480.6	9.06	
ET	137	78.21	176.4	2413.2	10.65	
ET	138	75.06	127.7	2486.3	8.59	
ET	139	72.84	131.9	2525.7	9.60	
ET	140	73.33	118.8	2544.2	8.55	
ET	141	81.63	95.9	2508.9	5.46	
ET	142	77.95	142.0	2476.5	8.68	
ET	143	73.94	148.7	2521.6	10.31	
ET	144	68.99	151.9	2563.9	12.01	
ET	145	67.24	99.2	2614.1	8.21	
ET	146	69.55	97.3	2617.0	7.72	
ET	147	64.69	119.9	2640.5	10.76	
ET	148	71.17	97.5	2626.2	7.47	
ET	149	73.54	145.0	2558.2	10.02	
ET	150	80.04	107.4	2543.5	6.31	
ET	151	77.13	137.9	2528.9	8.64	
ET	152	70.47	132.4	2598.9	10.09	
ET	153	72.09	120.6	2629.7	9.06	
ET	154	78.21	86.5	2621.4	5.50	
ET	155	79.57	99.9	2598.9	6.09	
ET	156	76.06	133.5	2597.6	8.93	
ET	157	77.65	133.5	2579.1	8.50	
ET	158	75.63	175.0	2568.3	11.63	
ET	159	78.80	137.6	2562.9	8.34	
ET	160	82.00	138.6	2539.4	7.67	
ET	161	77.77	212.1	2535.9	13.02	
ET	162	69.73	170.9	2626.5	13.27	
ET	163	71.67	119.4	2644.6	8.88	
ET	164	73.76	105.8	2658.3	7.56	
ET	165	79.68	93.8	2632.5	5.75	
ET	166	72.72	153.5	2601.4	10.85	
ET	167	71.62	145.3	2627.1	10.72	
ET	168	71.26	110.0	2663.7	8.34	
ET	169	73.63	124.3	2646.5	8.88	

ET	170	77.79	129.1	2600.1	8.21
ET	171	82.04	144.8	2542.0	8.05
ET	172	77.67	199.4	2553.1	12.44
ET	173	81.25	107.0	2592.8	6.22
ET	174	72.32	143.9	2625.9	10.51
ET	175	71.35	151.0	2647.8	11.52
ET	176	71.62	129.3	2649.1	9.80
ET	177	77.68	96.6	2622.1	6.13
ET	178	75.09	129.3	2628.7	8.93
ET	179	74.39	127.5	2615.1	8.88
ET	180	74.98	130.1	2601.1	8.84
ET	181	74.88	210.0	2568.0	14.18
ET	182	80.55	135.6	2566.8	8.01
ET	183	80.89	185.1	2524.8	10.67
ET	184	83.64	204.0	2486.3	10.76
ET	185	83.70	200.2	2483.8	10.56
ET	186	82.60	140.0	2503.8	7.58
ET	187	83.17	106.5	2566.4	5.97
ET	188	89.10	87.1	2546.7	4.14
ET	189	89.42	102.4	2502.9	4.72
ET	190	86.77	141.1	2467.9	6.85
ET	191	82.85	165.3	2461.5	8.77
ET	192	77.04	165.3	2538.5	10.65
ET	193	79.90	105.1	2557.9	6.38
ET	194	87.21	86.2	2531.5	4.30
ET	195	82.40	168.8	2466.9	9.26
ET	196	78.49	168.8	2498.7	10.43
ET	197	76.98	140.4	2528.0	9.08
ET	198	85.08	91.6	2508.9	4.79
ET	199	83.80	141.6	2436.7	7.47
ET	200	81.34	201.3	2425.6	11.30
ET	201	77.05	147.3	2496.5	9.51
ET	202	77.18	127.0	2509.5	8.30
ET	203	82.02	109.7	2467.6	6.22
ET	204	79.34	124.5	2445.3	7.29
ET	205	80.82	119.4	2435.2	6.85
ET	206	84.99	86.9	2450.7	4.50
ET	207	89.44	81.8	2408.1	3.71
ET	208	88.47	90.9	2398.6	4.25
ET	209	82.58	133.1	2372.5	7.18
ET	210	78.96	151.3	2377.3	8.93
ET	211	77.41	150.5	2393.2	9.42
ET	212	79.23	127.3	2391.3	7.67
ET	213	83.59	103.3	2373.8	5.55
ET	214	84.94	111.8	2329.0	5.68
ET	215	79.84	175.7	2297.5	10.04
ET	216	76.86	172.7	2324.9	10.85
ET	217	75.70	118.1	2364.3	7.76
ET	218	79.32	102.2	2340.8	6.09
ET	219	84.34	95.9	2296.2	4.97
ET	220	83.50	107.5	2261.9	5.59
ET	221	83.93	98.9	2259.4	5.08
ET	222	78.15	134.9	2266.7	8.19
ET	223	78.78	161.9	2230.5	9.64

ET		224	83.66	114.8	2198.0	5.88			
ET		225	82.54	122.9	2195.5	6.55			
ET		226	79.68	132.4	2210.7	7.76			
ET		227	81.79	96.2	2219.6	5.35			
ET		228	85.68	86.2	2188.8	4.25			
ET		229	79.77	152.6	2150.0	8.77			
ET		230	87.04	73.6	2159.9	3.42			
ET		231	86.54	73.1	2158.0	3.47			
ET		232	90.10	67.8	2142.1	2.93			
ET		233	85.53	89.0	2121.1	4.38			
ET		234	85.12	89.0	2106.5	4.43			
ET		235	84.78	95.2	2088.7	4.77			
ET		236	82.42	110.2	2072.5	5.88			
ET		237	87.62	71.2	2069.9	3.22			
ET		238	86.02	88.3	2042.6	4.21			
ET		239	80.53	159.8	2012.4	8.88			
ET		-240	79.48	145.3	2004.1	8.19			
QC		1	1	1	1	1	1	1	1
L1		10	1						
L2	10	5		10	.6	2	1		
LR	1	10000							
L3		.01	1.-6	1.-4	0	-.7			
L5	50	50000	825						
L7	10	2000	820	860	900	940			
L7	10	2000	840	880	920	960			
L8		200	400	800	1400	2000	3000	5000	
PL	0.25	100		-4.00					
PL	0.05	100		-0.20					
PL	0.10	100		-8.00					
PL	0.10	100		-8.00					
PL	0.05	100		-8.00					
PL	0.20	100		-8.00					
PL	0.20	100	-22.60	-18.80	-6.55	-0.77			
PL	0.25	100	3.20	-0.70	0.10	-0.05			
L9		40	41	42	43	45	48	60	
C1		105.	105.	105.	105.	105.	105.	105.	
C2		.1	.1	.1	.1	.05	.02	.02	
C3		.05	.05	.05	.05	.05	.02	.02	
C4		.1	.1	.1	.1	.2	.3	.5	
C5		0.5	0.5	0.5	0.5	0.5	0.5	0.5	
C6		.1	.1	.1	.1	.1	.05	.05	
C7		9.1	9.1	9.1	9.1	9.1	9.1	9.1	
SA		100	100	100	100	100	100	100	
SB		10	10	10	10	10	10	10	
SC		5	5	5	5	5	5	5	
K1		-1	-1	-1	-1	-1	-1	-1	32.
K2									
K2									
K3		-1	-1	-1	-1				
DK			.2	.1	1.463				
L2	40	2	60000	5	.6	2	1		
LR									
L3		.01	1.-6	1.-4	0	-.7			
L5	1	10	895.5						

L6	870	99300	962.5						
L7	7.9	2840	895.5	909.5	923.5	937.5			
L7	7.9	2840	902.5	916.5	930.5	944.5			
L8		410	460	500	550	600	650	700	750
PL	0.25	100		-4.00					
PL	0.05	100		-0.20					
PL	0.10	100		-8.00					
PL	0.10	100		-8.00					
PL	0.05	100		-8.00					
PL	0.20	100		-8.00					
PL	0.20	100	-22.60	-18.80	-6.55	-0.77			
PL	0.25	100	3.20	-0.70	0.10	-0.05			
L9		54	55	57	57	57	57	57	57
C1		105.	105.	105.	105.	105.	105.	105.	105.
C2		.1	.1	.1	.1	.05	.02	.02	.02
C3		.05	.05	.05	.05	.05	.02	.02	.02
C4		.1	.1	.1	.1	.2	.3	.5	.5
C5		0.5	0.5	0.5	0.5	0.5	0.5	0.5	.5
C6		.1	.1	.1	.1	.1	.05	.05	.05
C7		9.1	9.1	9.1	9.1	9.1	9.1	9.1	9.1
SA		100	100	100	100	100	100	100	100
SB		10	10	10	10	10	10	10	10
SC		5	5	5	5	5	5	5	5
K1		-1	-1	-1	-1	-1	-1	-1	32.5
K2									
K2									
K3		-1	-1	26	34				
DK			.2	.1	1.463				
CR		1.047	1.047	1.047	1.0159				
S1		10	1	-1	8	20	1		
S2	10	65.5	20	60	1.5				2
S2	20	60.0	30	40	1.5				3
S2	0	0	0	0	1				
S2	40	32	50	24.2	1.975	30	4		
SR	10	20	1	2					
SR	20	30	1	2					
SR	-40	50	1	2					
S3	10	65.5	844.0	0.	0.	0.	.050		
S3		65.5	844.2	0.	.21	5.0	.050		
S3		65.5	844.6	4.0	.35	20.0	.050		
S3		65.5	845.0	14.0	.61	29.0	.050		
S3		65.5	846.0	54.0	1.04	50.0	.050		
S3		65.5	847.0	114.0	1.40	67.0	.050		
S3		65.5	848.0	194.0	1.55	99.0	.050		
S3		65.5	849.0	305.0	1.84	121.0	.050		
S3		65.5	850.0	440.0	2.02	152.0	.050		
S3		65.5	851.0	605.0	2.20	185.0	.050		
S3		65.5	852.0	827.0	2.17	264.0	.050		
S3		65.5	853.0	1100.0	2.52	279.0	.050		
S3		65.5	854.0	1384.0	2.87	288.0	.050		
S3		65.5	855.0	1677.0	3.15	301.0	.050		
S3		65.5	856.0	1985.0	3.40	316.0	.050		
S3		65.5	857.0	2308.0	3.67	326.0	.050		
S3		65.5	858.0	2634.0	3.99	326.0	.050		

S3		65.5	859.0	2960.0	4.30	326.0	.050
S3		65.5	861.0	3612.0	4.88	326.0	.050
S3		65.5	863.0	4264.0	5.41	326.0	.050
S3	20	60.0	825.4	0.	0.	0.	.050
S3		60.0	825.6	1.0	.22	9.0	.050
S3		60.0	826.0	10.0	.43	33.0	.050
S3		60.0	826.4	27.0	.64	52.0	.050
S3		60.0	827.4	92.0	1.13	77.0	.050
S3		60.0	828.4	179.0	1.51	96.0	.050
S3		60.0	829.4	287.0	1.79	119.0	.050
S3		60.0	830.4	418.0	2.08	138.0	.050
S3		60.0	831.4	563.0	2.38	152.0	.050
S3		60.0	832.4	723.0	2.65	166.0	.050
S3		60.0	833.4	893.0	2.95	174.0	.050
S3		60.0	834.4	1071.0	3.23	183.0	.050
S3		60.0	835.4	1258.0	3.48	191.0	.050
S3		60.0	836.4	1455.0	3.64	207.0	.050
S3		60.0	837.4	1675.0	3.68	234.0	.050
S3		60.0	838.4	1922.0	3.83	253.0	.050
S3		60.0	839.4	2175.0	4.16	253.0	.050
S3		60.0	840.4	2428.0	4.48	253.0	.050
S3		60.0	842.4	2934.0	5.08	253.0	.050
S3		60.0	844.4	3440.0	5.65	253.0	.050
S3	30	40.0	765.0	0.	0.	0.	.050
S3		40.0	765.2	1.0	.22	9.0	.050
S3		40.0	765.6	10.0	.43	33.0	.050
S3		40.0	766.0	27.0	.64	52.0	.050
S3		40.0	767.0	92.0	1.13	77.0	.050
S3		40.0	768.0	179.0	1.51	96.0	.050
S3		40.0	769.0	287.0	1.79	119.0	.050
S3		40.0	770.0	418.0	2.08	138.0	.050
S3		40.0	771.0	563.0	2.38	152.0	.050
S3		40.0	772.0	723.0	2.65	166.0	.050
S3		40.0	773.0	893.0	2.95	174.0	.050
S3		40.0	774.0	1071.0	3.23	183.0	.050
S3		40.0	775.0	1258.0	3.48	191.0	.050
S3		40.0	776.0	1455.0	3.64	207.0	.050
S3		40.0	777.0	1675.0	3.68	234.0	.050
S3		40.0	778.0	1922.0	3.83	253.0	.050
S3		40.0	779.0	2175.0	4.16	253.0	.050
S3		40.0	780.0	2428.0	4.48	253.0	.050
S3		40.0	782.0	2934.0	5.08	253.0	.050
S3		40.0	784.0	3440.0	5.65	253.0	.050
S3	40	32.0	730.6	0.	0.	0.	.050
S3		32.0	730.8	0.	.21	2.0	.050
S3		32.0	731.2	2.0	.44	6.0	.050
S3		32.0	731.6	6.0	.45	19.0	.050
S3		32.0	732.6	74.0	.84	96.0	.050
S3		32.0	733.6	177.0	1.37	109.0	.050
S3		32.0	734.6	291.0	1.80	120.0	.050
S3		32.0	735.6	421.0	2.12	135.0	.050
S3		32.0	736.6	565.0	2.44	147.0	.050
S3		32.0	737.6	715.0	2.74	155.0	.050
S3		32.0	738.6	878.0	2.99	168.0	.050



S3		32.0	739.6	1050.0	3.26	176.0	.050
S3		32.0	740.6	1230.0	3.51	184.0	.050
S3		32.0	741.6	1418.0	3.74	193.0	.050
S3		32.0	742.6	1618.0	3.83	212.0	.050
S3		32.0	743.6	1844.0	3.86	239.0	.050
S3		32.0	744.6	2094.0	4.05	253.0	.050
S3		32.0	745.6	2347.0	4.37	253.0	.050
S3		32.0	747.6	2853.0	4.98	253.0	.050
S3		32.0	749.6	3359.0	5.55	253.0	.050
S3	50	30.4	722.9	0.	0.	0.	.030
S3		30.4	723.1	2.0	.22	15.0	.030
S3		30.4	723.5	14.0	.45	45.0	.030
S3		30.4	723.9	37.0	.64	74.0	.030
S3		30.4	724.9	130.0	1.12	111.0	.030
S3		30.4	725.9	271.0	1.43	167.0	.030
S3		30.4	726.9	462.0	1.72	218.0	.030
S3		30.4	727.9	701.0	2.04	257.0	.030
S3		30.4	728.9	978.0	2.34	287.0	.030
S3		30.4	729.9	1275.0	2.59	310.0	.030
S3		30.4	730.9	1599.0	2.79	337.0	.030
S3		30.4	731.9	1964.0	2.71	418.0	.030
S3		30.4	732.9	2394.0	2.98	444.0	.030
S3		30.4	733.9	2851.0	3.24	469.0	.030
S3		30.4	734.9	3342.0	3.39	518.0	.030
S3		30.4	735.9	3887.0	3.54	571.0	.030
S3		30.4	736.9	4482.0	3.74	610.0	.030
S3		30.4	737.9	5100.0	4.01	627.0	.030
S3		30.4	739.9	6390.0	4.49	662.0	.030
S3		30.4	741.9	7745.0	4.96	692.0	.030
S3	50	28.4	725.3	0.	0.	0.	.030
S3		28.4	725.5	4.0	.23	30.0	.030
S3		28.4	725.9	22.0	.48	59.0	.030
S3		28.4	726.3	51.0	.67	90.0	.030
S3		28.4	727.3	167.0	1.13	139.0	.030
S3		28.4	728.3	375.0	1.37	249.0	.030
S3		28.4	729.3	644.0	1.75	289.0	.030
S3		28.4	730.3	946.0	2.13	313.0	.030
S3		28.4	731.3	1271.0	2.46	336.0	.030
S3		28.4	732.3	1617.0	2.76	357.0	.030
S3		28.4	733.3	1985.0	3.03	379.0	.030
S3		28.4	734.3	2387.0	3.20	428.0	.030
S3		28.4	735.3	2831.0	3.41	463.0	.030
S3		28.4	736.3	3311.0	3.55	497.0	.030
S3		28.4	737.3	3824.0	3.73	527.0	.030
S3		28.4	738.3	4370.0	3.86	575.0	.030
S3		28.4	739.3	4985.0	3.99	634.0	.030
S3		28.4	740.3	5632.0	4.20	659.0	.030
S3		28.4	742.3	7002.0	4.58	709.0	.030
S3		28.4	744.3	8458.0	5.02	742.0	.030
S3	50	26.3	722.7	0.	0.	0.	.030
S3		26.3	722.8	1.0	.22	9.0	.030
S3		26.3	723.2	8.0	.45	26.0	.030
S3		26.3	723.7	22.0	.62	45.0	.030
S3		26.3	724.7	92.0	1.00	94.0	.030

S3		26.3	725.7	219.0	1.22	167.0	.030
S3		26.3	726.7	436.0	1.38	265.0	.030
S3		26.3	727.7	751.0	1.58	365.0	.030
S3		26.3	728.7	1158.0	1.86	441.0	.030
S3		26.3	729.7	1628.0	2.17	496.0	.030
S3		26.3	730.7	2254.0	2.19	729.0	.030
S3		26.3	731.7	3038.0	2.44	809.0	.030
S3		26.3	732.7	3867.0	2.74	858.0	.030
S3		26.3	733.7	4756.0	3.00	913.0	.030
S3		26.3	734.7	5699.0	3.23	981.0	.030
S3		26.3	735.7	6697.0	3.45	1022.0	.030
S3		26.3	736.7	7750.0	3.68	1067.0	.030
S3		26.3	737.7	8825.0	3.97	1083.0	.030
S3		26.3	739.7	11032.0	4.51	1117.0	.030
S3		26.3	741.7	13278.0	5.08	1129.0	.030
S3	50	24.2	721.6	0.	0.	0.	.030
S3		24.2	721.8	6.0	.22	56.0	.030
S3		24.2	722.2	50.0	.47	150.0	.030
S3		24.2	722.6	118.0	.69	190.0	.030
S3		24.2	723.6	354.0	1.13	270.0	.030
S3		24.2	724.6	656.0	1.41	358.0	.030
S3		24.2	725.6	1079.0	1.60	484.0	.030
S3		24.2	726.6	1606.0	1.88	568.0	.030
S3		24.2	727.6	2215.0	2.16	648.0	.030
S3		24.2	728.6	2903.0	2.41	730.0	.030
S3		24.2	729.6	3687.0	2.62	834.0	.030
S3		24.2	730.6	4563.0	2.87	914.0	.030
S3		24.2	731.6	5511.0	3.10	994.0	.030
S3		24.2	732.6	6555.0	3.32	1081.0	.030
S3		24.2	733.6	7684.0	3.50	1191.0	.030
S3		24.2	734.6	8885.0	3.80	1211.0	.030
S3		24.2	735.6	10105.0	4.09	1229.0	.030
S3		24.2	736.6	11341.0	4.38	1242.0	.030
S3		24.2	738.6	13849.0	4.93	1266.0	.030
S3		24.2	740.6	16405.0	5.45	1289.0	.030
S4		854	835	775	743	742	741
S4		739.5					740
KR			0.10	.2	1.463		
KR			0.15	.2	1.463		
KR			0.25	.2	1.463		
CT	10	740101	40.	3.	0.		
CT		740318	45.	3.	0.		
CT		740723	50.	3.	0.		
CT		741017	45.	3.	0.		
CT		741206	40.	3.	0.		
CT		-741231	40.	3.	0.		
CT		740101	150.	1.	0.		
CT		-741231	150.	1.	0.		
CT		740101	.01	1.	0.		
CT		-741231	.01	1.	0.		
CT		740101	.001	1.	0.		
CT		-741231	.001	1.	0.		
CT		740101	.001	1.	0.		
CT		-741231	.001	1.	0.		
CT		740101	0.1	1.	0.		

CT	-741231	0.1	1.	0.
CT	740101	.10	1.	0.
CT	-741231	.10	1.	0.
CT	740101	5.	0.	30.
CT	-741231	5.	0.	30.
CT	20 740101	45	4	0
CT	740318	50	4	0
CT	740723	55	4	0
CT	741017	50	4	0
CT	741206	45	4	0
CT	-741231	42	4	0
CT	740101	160	.8	0
CT	-741231	160	.8	0
CT	740101	.01	1.	0.
CT	-741231	.01	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	.05	.15	0
CT	-741231	.05	.15	0
CT	740101	.10	1.	0.
CT	-741231	.10	1.	0.
CT	740101	4	0	50
CT	-741231	4	0	50
CT	30 740101	45.	3.	0.
CT	740510	50.	3.	0.
CT	740531	60.	3.	0.
CT	741001	55.	3.	0.
CT	-741231	45.	3.	0.
CT	740101	160.	1.	0.
CT	-741231	160.	1.	0.
CT	740101	.01	1.	0.
CT	-741231	.01	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	.15	4.	0.
CT	-741231	.15	4.	0.
CT	740101	.10	1.	0.
CT	-741231	.10	1.	0.
CT	740101	4.5	4.	0.
CT	-741231	4.5	4.	0.
CT	40 740101	45.	3.	0.
CT	740504	50.	3.	0.
CT	740514	55.	3.	0.
CT	740515	60.	3.	0.
CT	741005	55.	3.	0.
CT	741109	50.	3.	0.
CT	741214	45.	3.	0.
CT	-741231	45.	3.	0.
CT	740101	170.	1.	0.
CT	-741231	170.	1.	0.

CT	740101	.01	1.	0.
CT	-741231	.01	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	0.2	1.	0.
CT	-741231	0.2	1.	0.
CT	740101	.10	1.	0.
CT	-741231	.10	1.	0.
CT	740101	5.5	0.	30.
CT	-741231	5.5	0.	30.
CT	50 740101	50.	3.	0.
CT	740506	55.	3.	0.
CT	740510	60.	3.	0.
CT	740515	65.	3.	0.
CT	740708	70.	3.	0.
CT	740924	65.	3.	0.
CT	741018	60.	3.	0.
CT	741112	55.	3.	0.
CT	741206	50.	3.	0.
CT	-741231	50.	3.	0.
CT	740101	190.	1.	0.
CT	-741231	190.	1.	0.
CT	740101	.01	1.	0.
CT	-741231	.01	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	.001	1.	0.
CT	-741231	.001	1.	0.
CT	740101	0.3	1.	0.
CT	-741231	0.3	1.	0.
CT	740101	.10	1.	0.
CT	-741231	.10	1.	0.
CT	740101	6.0	0.	30.
CT	-741231	6.0	0.	30.
I1	740101	741231		
I2		0 TRIB 1 INFLOW RATE - RES #1		
I4	740101	-1 741231	-1.	-1
I2	1	0 HAYES INFLOW... TEMP		
I4	740101	-1.5 740408	-1.5 740422	-5.0 740708 -8.
I4	740826	-5. 741231	-1.5	-1
I2		0 HAYES INFLOW - TDS		
I4	740101	105. 741231	105.	-1
I2		0 TYPICAL NO3 - N		
I4	740101	.10 741231	.10	-1
I2		0 TYPICAL PO4 - P		
I4	740101	.03 741231	.03	-1
I2		0 TYPICAL PHYTOPLANKTON		
I4	740101	.25 741231	.25	-1
I2		0 HAYES INFLOW - CBOD		
I4	740101	0.5 41231	0.5	-1
I2		0 TYPICAL NH3 - N		
I4	740101	.03 741231	.03	-1

I2		0 HAYES INFLOW - DO					
I4	740101	12.8	740115	13.1	740215	12.4	740315 11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715 8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115 11.0
I4	741215	12.4	741231	12.8	-1		
I2		0 TRIB 2 INFLOW RATE - RM 60					
I4	740101	-1	741231	-1.	-1		
I2	1	0 TRIB 2 - RM 60.. TEMP					
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0 TRIB 2 - RM 60 - TDS					
I4	740101	150.	741231	150.	-1		
I2		0 TYPICAL NO3 - N					
I4	740101	.10	741231	.10	-1		
I2		0 TYPICAL PO4 - P					
I4	740101	.03	741231	.03	-1		
I2		0 TYPICAL PHYTOPLANKTON					
I4	740101	.25	741231	.25	-1		
I2		0 TRIB 2 - RM 60 - CBOD					
I4	740101	0.5	741231	0.5	-1		
I2		0 TYPICAL NH3 - N					
I4	740101	.03	741231	.03	-1		
I2		0 TRIB 2 - RM 60 - DO					
I4	740101	12.6	740115	12.7	740215	13.0	740315 12.6
I4	740415	11.5	740515	9.1	740615	8.6	740715 7.7
I4	740815	7.7	740915	9.0	741015	9.7	741115 11.1
I4	741215	12.6	741231	12.6	-1		
I2		0 TRIB 3 INFLOW RATE - RM 40					
I4	740101	-1	741231	-1.	-1		
I2	1	0 TRIB 3 - RM 40.. TEMP					
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0 TRIB 3 - RM 40 - TDS					
I4	740101	150.	741231	150.	-1		
I2		0 TYPICAL NO3 - N					
I4	740101	.10	741231	.10	-1		
I2		0 TYPICAL PO4 - P					
I4	740101	.03	741231	.03	-1		
I2		0 TYPICAL PHYTOPLANKTON					
I4	740101	.25	741231	.25	-1		
I2		0 TRIB 3 - RM 40 - CBOD					
I4	740101	0.5	741231	0.5	-1		
I2		0 TYPICAL NH3 - N					
I4	740101	.03	741231	.03	-1		
I2		0 TRIB 3 - RM 40 - DO					
I4	740101	12.6	740115	12.7	740215	13.0	740315 12.6
I4	740415	11.5	740515	9.1	740615	8.6	740715 7.7
I4	740815	7.7	740915	9.0	741015	9.7	741115 11.1
I4	741215	12.6	741231	12.6	-1		
I2		0 TRIB 4 INFLOW RATE - RM 30					
I4	740101	-1	741231	-1.	-1		
I2	1	0 TRIB 4 - RM 30.. TEMP					
I4	740101	-1.5	740408	-1.5	740422	-3.0	740708 -6.
I4	740826	-5.	741231	-1.5	-1		

I2		0	TRIB 4 - RM 30 - TDS	
I4	740101	160.	741231 160.	-1
I2		0	TYPICAL NO3 - N	
I4	740101	.10	741231 .10	-1
I2		0	TYPICAL PO4 - P	
I4	740101	.03	741231 .03	-1
I2		0	TYPICAL PHYTOPLANKTON	
I4	740101	.25	741231 .25	-1
I2		0	TRIB 4 - RM 30 - CBOD	
I4	740101	0.6	741231 0.6	-1
I2		0	TYPICAL NH3 - N	
I4	740101	.03	741231 .03	-1
I2	-1	0	TRIB 4 - RM 30 - DO	
I4	740101	100.	741231 100.	-1
ER				

## TEST PROBLEM 5 - Tandem Reservoirs with Steady State Option

The system simulated in this test of the water quality module consists of the same reservoir and stream configuration as Test Problem 2. The unique input to this test problem, includes selecting the steady state option (J9 card, Field 3), and specifying the time series (IN cards) and reservoir releases (QA cards) on a monthly basis (BF card, Fields 2 and 6 = 5's and Field 7 = 720 hours).

A complete listing of the input data deck is given below. A complete output listing is included with the computer source code distribution.

```

T1  TESTING HEC5Q WATER QUALITY SIMULATION CAPABILITY
T2  TANDEM RIVER SYSTEM...STEADY STATE CONDITIONS
T3  TEST PROBLEM 5
J1   0      5      5      3      4      2      0      0
J2   0      0      0      0      0      0      0
J9           1      0
RL  10 1200000      0 100000 200000 1500000 1600000
RO   3      20      30      40
RS   7      100     6300   31300   88000   188000   563000 1688000
RQ   7      0     20000   30000   40000   50000   50000   50000
RA   7      10      500    1500    3000    5000    10000   20000
RE   7      800     825     850     870     900     950    1030
R3   2      2      2      2      99     99     99     99     99     99
R3   99     99
CP  10     15000     300     200
IDCP10-HAYES DAM
RT  10      20      2.2     .25     12      0
CP  20     12000     300     200
ID  CP20 ** RM60
RT  20      30      2.2     .25     12      0
CP  30     12000     300     200
ID  CP30 ** RM40
RT  30      40      2.2     .25     12      0
RL  40     550000      0     2000  550000  952000 1130000
RO   1      50
RS   8     2000   20000   52000  113000  209000  320000  550000  800000 1130000
RQ   8      0     5680   5680   5680   5680   5680   29180   59680  104980
RA   8     150     2100   4500   7600   11800   17000   22400   28600   37200
RE   8     892     910     920     930     940     950   962.5     970     980
R3   2      2      2      2      99     99     99     99     99     99
R3   99     99
CP  40     10000     300     200
IDCP40-DAVIS DAM
RT  40      50      2.2     .25     12      0
CP  50     50000     300     200
IDCP50 ** RM24.2
RT  50      0      0      0      0      0
ED
BF   0      5      0      074050100      5      720
NOLIST
IN  10  1MAY74   2524   2426   2099   759   3154
IN  20  1MAY74   913    716    642   170   1203
IN  30  1MAY74   913    716    642   167   1203
IN  50  1MAY74  4641   1361   2134   726   2991
QA  10  1MAY74  2380   2347   2128   673   2898
EJ
TI  FICTITIOUS TANDEM RIVER BASIN TEST OF HEC-5Q WITH WATER QUALITY
TI  RESERVOIRS ARE FICTITIOUS ALSO ** C.P. OF 10, 20, 30, 40 AND 50
TI  CONSTITUENTS ARE TEMPERATURE, TDS, CARBONACEOUS BOD AND OXYGEN
JA  740501 740828      5      2      F      0
EZ  -1

```



ET	121	64.06	138.8	2385.6	12.35
ET	122	62.44	111.4	2409.1	10.31
ET	123	65.44	126.3	2385.9	10.60
ET	124	60.66	107.7	2456.1	10.34
ET	125	63.36	102.6	2457.1	9.35
ET	126	57.60	124.1	2466.3	12.60
ET	127	58.75	89.7	2507.6	8.88
ET	128	66.16	90.8	2484.1	7.72
ET	129	66.36	138.3	2446.0	11.48
ET	130	67.68	96.1	2494.6	7.85
ET	131	70.23	130.1	2473.9	10.09
ET	132	66.18	147.4	2470.1	12.21
ET	133	62.56	144.1	2518.4	13.40
ET	134	72.00	149.0	2492.1	11.23
ET	135	71.49	175.2	2472.3	13.02
ET	136	74.91	133.5	2480.6	9.06
ET	137	78.21	176.4	2413.2	10.65
ET	138	75.06	127.7	2486.3	8.59
ET	139	72.84	131.9	2525.7	9.60
ET	140	73.33	118.8	2544.2	8.55
ET	141	81.63	95.9	2508.9	5.46
ET	142	77.95	142.0	2476.5	8.68
ET	143	73.94	148.7	2521.6	10.31
ET	144	68.99	151.9	2563.9	12.01
ET	145	67.24	99.2	2614.1	8.21
ET	146	69.55	97.3	2617.0	7.72
ET	147	64.69	119.9	2640.5	10.76
ET	148	71.17	97.5	2626.2	7.47
ET	149	73.54	145.0	2558.2	10.02
ET	150	80.04	107.4	2543.5	6.31
ET	151	77.13	137.9	2528.9	8.64
ET	152	70.47	132.4	2598.9	10.09
ET	153	72.09	120.6	2629.7	9.06
ET	154	78.21	86.5	2621.4	5.50
ET	155	79.57	99.9	2598.9	6.09
ET	156	76.06	133.5	2597.6	8.93
ET	157	77.65	133.5	2579.1	8.50
ET	158	75.63	175.0	2568.3	11.63
ET	159	78.80	137.6	2562.9	8.34
ET	160	82.00	138.6	2539.4	7.67
ET	161	77.77	212.1	2535.9	13.02
ET	162	69.73	170.9	2626.5	13.27
ET	163	71.67	119.4	2644.6	8.88
ET	164	73.76	105.8	2658.3	7.56
ET	165	79.68	93.8	2632.5	5.75
ET	166	72.72	153.5	2601.4	10.85
ET	167	71.62	145.3	2627.1	10.72
ET	168	71.26	110.0	2663.7	8.34
ET	169	73.63	124.3	2646.5	8.88
ET	170	77.79	129.1	2600.1	8.21
ET	171	82.04	144.8	2542.0	8.05
ET	172	77.67	199.4	2553.1	12.44
ET	173	81.25	107.0	2592.8	6.22
ET	174	72.32	143.9	2625.9	10.51

ET	175	71.35	151.0	2647.8	11.52
ET	176	71.62	129.3	2649.1	9.80
ET	177	77.68	96.6	2622.1	6.13
ET	178	75.09	129.3	2628.7	8.93
ET	179	74.39	127.5	2615.1	8.88
ET	180	74.98	130.1	2601.1	8.84
ET	181	74.88	210.0	2568.0	14.18
ET	182	80.55	135.6	2566.8	8.01
ET	183	80.89	185.1	2524.8	10.67
ET	184	83.64	204.0	2486.3	10.76
ET	185	83.70	200.2	2483.8	10.56
ET	186	82.60	140.0	2503.8	7.58
ET	187	83.17	106.5	2566.4	5.97
ET	188	89.10	87.1	2546.7	4.14
ET	189	89.42	102.4	2502.9	4.72
ET	190	86.77	141.1	2467.9	6.85
ET	191	82.85	165.3	2461.5	8.77
ET	192	77.04	165.3	2538.5	10.65
ET	193	79.90	105.1	2557.9	6.38
ET	194	87.21	86.2	2531.5	4.30
ET	195	82.40	168.8	2466.9	9.26
ET	196	78.49	168.8	2498.7	10.43
ET	197	76.98	140.4	2528.0	9.08
ET	198	85.08	91.6	2508.9	4.79
ET	199	83.80	141.6	2436.7	7.47
ET	200	81.34	201.3	2425.6	11.30
ET	201	77.05	147.3	2496.5	9.51
ET	202	77.18	127.0	2509.5	8.30
ET	203	82.02	109.7	2467.6	6.22
ET	204	79.34	124.5	2445.3	7.29
ET	205	80.82	119.4	2435.2	6.85
ET	206	84.99	86.9	2450.7	4.50
ET	207	89.44	81.8	2408.1	3.71
ET	208	88.47	90.9	2398.6	4.25
ET	209	82.58	133.1	2372.5	7.18
ET	210	78.96	151.3	2377.3	8.93
ET	211	77.41	150.5	2393.2	9.42
ET	212	79.23	127.3	2391.3	7.67
ET	213	83.59	103.3	2373.8	5.55
ET	214	84.94	111.8	2329.0	5.68
ET	215	79.84	175.7	2297.5	10.04
ET	216	76.86	172.7	2324.9	10.85
ET	217	75.70	118.1	2364.3	7.76
ET	218	79.32	102.2	2340.8	6.09
ET	219	84.34	95.9	2296.2	4.97
ET	220	83.50	107.5	2261.9	5.59
ET	221	83.93	98.9	2259.4	5.08
ET	222	78.15	134.9	2266.7	8.19
ET	223	78.78	161.9	2230.5	9.64
ET	224	83.66	114.8	2198.0	5.88
ET	225	82.54	122.9	2195.5	6.55
ET	226	79.68	132.4	2210.7	7.76
ET	227	81.79	96.2	2219.6	5.35
ET	228	85.68	86.2	2188.8	4.25

ET	229	79.77	152.6	2150.0	8.77			
ET	230	87.04	73.6	2159.9	3.42			
ET	231	86.54	73.1	2158.0	3.47			
ET	232	90.10	67.8	2142.1	2.93			
ET	233	85.53	89.0	2121.1	4.38			
ET	234	85.12	89.0	2106.5	4.43			
ET	235	84.78	95.2	2088.7	4.77			
ET	236	82.42	110.2	2072.5	5.88			
ET	237	87.62	71.2	2069.9	3.22			
ET	238	86.02	88.3	2042.6	4.21			
ET	239	80.53	159.8	2012.4	8.88			
ET	240	79.48	145.3	2004.1	8.19			
ET	241	79.11	149.2	1979.7	8.48			
ET	242	80.02	122.7	1985.4	6.89			
ET	-243	77.29	150.1	1973.6	9.06			
QC	1	0	0	0	1	0	1	
TQTOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY								
TQCARBONACEOUS BOD IN MG/L								
TQDISSOLVED OXYGEN IN MG/L								
L1	1	1						
L2	10	5	10	.6	2	1		
LR	1	10000						
L3		.01	1.-6	1.-4	0	-.7		
L5	50	50000	825					
L7	10	2000	820	860	900	940		
L7	10	2000	840	880	920	960		
L8		200	400	800	1400	2000	3000	5000
PL	0.25	100		-4.00				
PL	0.05	100		-0.20				
PL	0.20	100		-8.00				
PL	0.25	100	3.2	-0.70	0.10	-0.05		
L9		40	41	42	43	45	48	60
C1		105.	105.	105.	105.	105.	105.	105.
C5		0.5	0.5	0.5	0.5	0.5	0.5	0.5
C7		9.1	9.1	9.1	9.1	9.1	9.1	9.1
SA		100	100	100	100	100	100	100
DK			0.1		1.463			
L2	40	2	60000	5	.6	2	1	
LR								
L3		.01	1.-6	1.-4	0	-.7		
L5	1	10	895.5					
L6	870	99300	962.5					
L7	7.9	2840	895.5	909.5	923.5	937.5		
L7	7.9	2840	902.5	916.5	930.5	944.5		
L8		410	460	500	550	600	650	700
PL	0.25	100		-4.00				
PL	0.05	100		-0.20				
PL	0.20	100		-8.00				
PL	0.25	100	3.2	-0.70	0.10	-0.05		
L9		54	55	57	57	57	57	57
C1		160	190	190	190	190	190	190
C5		.3	.3	.3	.3	.3	.3	.3
C7		8.4	8.7	9.2	9.2	9.2	9.2	9.2
SA		100	100	100	100	100	100	100

DK			.2		1.463		
CR		1.047	1.047	1.047	1.0159		
S1		1	1	-1	8	20	1
S2	10	65.5	20	60	1.5		
S2	20	60.0	30	40	1.5		
S2	0	0	0	0			
S2	40	32	50	24.2	1.975	30	4
SR	10	20	1	2			
SR	20	30	1	2			
SR	-40	50	1	2			
S3	10	65.5	844.0	0.	0.	0.	.050
S3		65.5	844.2	0.	.21	5.0	.050
S3		65.5	844.6	4.0	.35	20.0	.050
S3		65.5	845.0	14.0	.61	29.0	.050
S3		65.5	846.0	54.0	1.04	50.0	.050
S3		65.5	847.0	114.0	1.40	67.0	.050
S3		65.5	848.0	194.0	1.55	99.0	.050
S3		65.5	849.0	305.0	1.84	121.0	.050
S3		65.5	850.0	440.0	2.02	152.0	.050
S3		65.5	851.0	605.0	2.20	185.0	.050
S3		65.5	852.0	827.0	2.17	264.0	.050
S3		65.5	853.0	1100.0	2.52	279.0	.050
S3		65.5	854.0	1384.0	2.87	288.0	.050
S3		65.5	855.0	1677.0	3.15	301.0	.050
S3		65.5	856.0	1985.0	3.40	316.0	.050
S3		65.5	857.0	2308.0	3.67	326.0	.050
S3		65.5	858.0	2634.0	3.99	326.0	.050
S3		65.5	859.0	2960.0	4.30	326.0	.050
S3		65.5	861.0	3612.0	4.88	326.0	.050
S3		65.5	863.0	4264.0	5.41	326.0	.050
S3	20	60.0	825.4	0.	0.	0.	.050
S3		60.0	825.6	1.0	.22	9.0	.050
S3		60.0	826.0	10.0	.43	33.0	.050
S3		60.0	826.4	27.0	.64	52.0	.050
S3		60.0	827.4	92.0	1.13	77.0	.050
S3		60.0	828.4	179.0	1.51	96.0	.050
S3		60.0	829.4	287.0	1.79	119.0	.050
S3		60.0	830.4	418.0	2.08	138.0	.050
S3		60.0	831.4	563.0	2.38	152.0	.050
S3		60.0	832.4	723.0	2.65	166.0	.050
S3		60.0	833.4	893.0	2.95	174.0	.050
S3		60.0	834.4	1071.0	3.23	183.0	.050
S3		60.0	835.4	1258.0	3.48	191.0	.050
S3		60.0	836.4	1455.0	3.64	207.0	.050
S3		60.0	837.4	1675.0	3.68	234.0	.050
S3		60.0	838.4	1922.0	3.83	253.0	.050
S3		60.0	839.4	2175.0	4.16	253.0	.050
S3		60.0	840.4	2428.0	4.48	253.0	.050
S3		60.0	842.4	2934.0	5.08	253.0	.050
S3		60.0	844.4	3440.0	5.65	253.0	.050
S3	30	40.0	765.0	0.	0.	0.	.050
S3		40.0	765.2	1.0	.22	9.0	.050
S3		40.0	765.6	10.0	.43	33.0	.050
S3		40.0	766.0	27.0	.64	52.0	.050

2  
3

S3		40.0	767.0	92.0	1.13	77.0	.050
S3		40.0	768.0	179.0	1.51	96.0	.050
S3		40.0	769.0	287.0	1.79	119.0	.050
S3		40.0	770.0	418.0	2.08	138.0	.050
S3		40.0	771.0	563.0	2.38	152.0	.050
S3		40.0	772.0	723.0	2.65	166.0	.050
S3		40.0	773.0	893.0	2.95	174.0	.050
S3		40.0	774.0	1071.0	3.23	183.0	.050
S3		40.0	775.0	1258.0	3.48	191.0	.050
S3		40.0	776.0	1455.0	3.64	207.0	.050
S3		40.0	777.0	1675.0	3.68	234.0	.050
S3		40.0	778.0	1922.0	3.83	253.0	.050
S3		40.0	779.0	2175.0	4.16	253.0	.050
S3		40.0	780.0	2428.0	4.48	253.0	.050
S3		40.0	782.0	2934.0	5.08	253.0	.050
S3		40.0	784.0	3440.0	5.65	253.0	.050
S3	40	32.0	730.6	0.	0.	0.	.050
S3		32.0	730.8	0.	.21	2.0	.050
S3		32.0	731.2	2.0	.44	6.0	.050
S3		32.0	731.6	6.0	.45	19.0	.050
S3		32.0	732.6	74.0	.84	96.0	.050
S3		32.0	733.6	177.0	1.37	109.0	.050
S3		32.0	734.6	291.0	1.80	120.0	.050
S3		32.0	735.6	421.0	2.12	135.0	.050
S3		32.0	736.6	565.0	2.44	147.0	.050
S3		32.0	737.6	715.0	2.74	155.0	.050
S3		32.0	738.6	878.0	2.99	168.0	.050
S3		32.0	739.6	1050.0	3.26	176.0	.050
S3		32.0	740.6	1230.0	3.51	184.0	.050
S3		32.0	741.6	1418.0	3.74	193.0	.050
S3		32.0	742.6	1618.0	3.83	212.0	.050
S3		32.0	743.6	1844.0	3.86	239.0	.050
S3		32.0	744.6	2094.0	4.05	253.0	.050
S3		32.0	745.6	2347.0	4.37	253.0	.050
S3		32.0	747.6	2853.0	4.98	253.0	.050
S3		32.0	749.6	3359.0	5.55	253.0	.050
S3	50	30.4	722.9	0.	0.	0.	.030
S3		30.4	723.1	2.0	.22	15.0	.030
S3		30.4	723.5	14.0	.45	45.0	.030
S3		30.4	723.9	37.0	.64	74.0	.030
S3		30.4	724.9	130.0	1.12	111.0	.030
S3		30.4	725.9	271.0	1.43	167.0	.030
S3		30.4	726.9	462.0	1.72	218.0	.030
S3		30.4	727.9	701.0	2.04	257.0	.030
S3		30.4	728.9	978.0	2.34	287.0	.030
S3		30.4	729.9	1275.0	2.59	310.0	.030
S3		30.4	730.9	1599.0	2.79	337.0	.030
S3		30.4	731.9	1964.0	2.71	418.0	.030
S3		30.4	732.9	2394.0	2.98	444.0	.030
S3		30.4	733.9	2851.0	3.24	469.0	.030
S3		30.4	734.9	3342.0	3.39	518.0	.030
S3		30.4	735.9	3887.0	3.54	571.0	.030
S3		30.4	736.9	4482.0	3.74	610.0	.030
S3		30.4	737.9	5100.0	4.01	627.0	.030

S3		30.4	739.9	6390.0	4.49	662.0	.030
S3		30.4	741.9	7745.0	4.96	692.0	.030
S3	50	28.4	725.3	0.	0.	0.	.030
S3		28.4	725.5	4.0	.23	30.0	.030
S3		28.4	725.9	22.0	.48	59.0	.030
S3		28.4	726.3	51.0	.67	90.0	.030
S3		28.4	727.3	167.0	1.13	139.0	.030
S3		28.4	728.3	375.0	1.37	249.0	.030
S3		28.4	729.3	644.0	1.75	289.0	.030
S3		28.4	730.3	946.0	2.13	313.0	.030
S3		28.4	731.3	1271.0	2.46	336.0	.030
S3		28.4	732.3	1617.0	2.76	357.0	.030
S3		28.4	733.3	1985.0	3.03	379.0	.030
S3		28.4	734.3	2387.0	3.20	428.0	.030
S3		28.4	735.3	2831.0	3.41	463.0	.030
S3		28.4	736.3	3311.0	3.55	497.0	.030
S3		28.4	737.3	3824.0	3.73	527.0	.030
S3		28.4	738.3	4370.0	3.86	575.0	.030
S3		28.4	739.3	4985.0	3.99	634.0	.030
S3		28.4	740.3	5632.0	4.20	659.0	.030
S3		28.4	742.3	7002.0	4.58	709.0	.030
S3		28.4	744.3	8458.0	5.02	742.0	.030
S3	50	26.3	722.7	0.	0.	0.	.030
S3		26.3	722.8	1.0	.22	9.0	.030
S3		26.3	723.2	8.0	.45	26.0	.030
S3		26.3	723.7	22.0	.62	45.0	.030
S3		26.3	724.7	92.0	1.00	94.0	.030
S3		26.3	725.7	219.0	1.22	167.0	.030
S3		26.3	726.7	436.0	1.38	265.0	.030
S3		26.3	727.7	751.0	1.58	365.0	.030
S3		26.3	728.7	1158.0	1.86	441.0	.030
S3		26.3	729.7	1628.0	2.17	496.0	.030
S3		26.3	730.7	2254.0	2.19	729.0	.030
S3		26.3	731.7	3038.0	2.44	809.0	.030
S3		26.3	732.7	3867.0	2.74	858.0	.030
S3		26.3	733.7	4756.0	3.00	913.0	.030
S3		26.3	734.7	5699.0	3.23	981.0	.030
S3		26.3	735.7	6697.0	3.45	1022.0	.030
S3		26.3	736.7	7750.0	3.68	1067.0	.030
S3		26.3	737.7	8825.0	3.97	1083.0	.030
S3		26.3	739.7	11032.0	4.51	1117.0	.030
S3		26.3	741.7	13278.0	5.08	1129.0	.030
S3	50	24.2	721.6	0.	0.	0.	.030
S3		24.2	721.8	6.0	.22	56.0	.030
S3		24.2	722.2	50.0	.47	150.0	.030
S3		24.2	722.6	118.0	.69	190.0	.030
S3		24.2	723.6	354.0	1.13	270.0	.030
S3		24.2	724.6	656.0	1.41	358.0	.030
S3		24.2	725.6	1079.0	1.60	484.0	.030
S3		24.2	726.6	1606.0	1.88	568.0	.030
S3		24.2	727.6	2215.0	2.16	648.0	.030
S3		24.2	728.6	2903.0	2.41	730.0	.030
S3		24.2	729.6	3687.0	2.62	834.0	.030
S3		24.2	730.6	4563.0	2.87	914.0	.030

S3	24.2	731.6	5511.0	3.10	994.0	.030	
S3	24.2	732.6	6555.0	3.32	1081.0	.030	
S3	24.2	733.6	7684.0	3.50	1191.0	.030	
S3	24.2	734.6	8885.0	3.80	1211.0	.030	
S3	24.2	735.6	10105.0	4.09	1229.0	.030	
S3	24.2	736.6	11341.0	4.38	1242.0	.030	
S3	24.2	738.6	13849.0	4.93	1266.0	.030	
S3	24.2	740.6	16405.0	5.45	1289.0	.030	
S4	854	835	775	743	742	741	740
S4	739.5						
KR		0.10		1.463			
KR		0.15		1.463			
KR		0.25		1.463			
CT	10	740101	40.	3.	0.		
CT		740318	45.	3.	0.		
CT		740723	50.	3.	0.		
CT		741017	45.	3.	0.		
CT		741206	40.	3.	0.		
CT		-741231	40.	3.	0.		
CT		740101	150.	1.	0.		
CT		-741231	150.	1.	0.		
CT		740101	0.1	1.	0.		
CT		-741231	0.1	1.	0.		
CT		740101	5.	0.	30.		
CT		-741231	5.	0.	30.		
CT	20	740101	45	4	0		
CT		740318	50	4	0		
CT		740723	55	4	0		
CT		741017	50	4	0		
CT		741206	45	4	0		
CT		-741231	42	4	0		
CT		740101	160	.8	0		
CT		-741231	160	.8	0		
CT		740101	.05	.15	0		
CT		-741231	.05	.15	0		
CT		740101	4	0	50		
CT		-741231	4	0	50		
CT	30	740101	45.	3.	0.		
CT		740510	50.	3.	0.		
CT		740531	60.	3.	0.		
CT		741001	55.	3.	0.		
CT		-741231	45.	3.	0.		
CT		740101	160.	1.	0.		
CT		-741231	160.	1.	0.		
CT		740101	.15	4.	0.		
CT		-741231	.15	4.	0.		
CT		740101	4.5	4.	0.		
CT		-741231	4.5	4.	0.		
CT	40	740101	45.	3.	0.		
CT		740504	50.	3.	0.		
CT		740514	55.	3.	0.		
CT		740515	60.	3.	0.		
CT		741005	55.	3.	0.		
CT		741109	50.	3.	0.		

CT	741214	45.	3.	0.			
CT	-741231	45.	3.	0.			
CT	740101	170.	1.	0.			
CT	-741231	170.	1.	0.			
CT	740101	0.2	1.	0.			
CT	-741231	0.2	1.	0.			
CT	740101	5.5	0.	30.			
CT	-741231	5.5	0.	30.			
CT	50 740101	50.	3.	0.			
CT	740506	55.	3.	0.			
CT	740510	60.	3.	0.			
CT	740515	65.	3.	0.			
CT	740708	70.	3.	0.			
CT	740924	65.	3.	0.			
CT	741018	60.	3.	0.			
CT	741112	55.	3.	0.			
CT	741206	50.	3.	0.			
CT	-741231	50.	3.	0.			
CT	740101	190.	1.	0.			
CT	-741231	190.	1.	0.			
CT	740101	0.3	1.	0.			
CT	-741231	0.3	1.	0.			
CT	740101	6.0	0.	30.			
CT	-741231	6.0	0.	30.			
I1	740101	741231					
I2		0	TRIB 1 INFLOW RATE - RES #1				
I4	740101	-1	741231	-1.	-1		
I2	1	0	HAYES INFLOW				
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0	HAYES INFLOW - TOTAL DISSOLVED SOLIDS				
I4	740101	105.	741231	105.	-1		
I2		0	HAYES INFLOW - CARBONACEOUS BOD				
I4	740101	0.5	741231	0.5	-1		
I2		0	HAYES INFLOW - DISSOLVED OXYGEN				
I4	740101	12.8	740115	13.1	740215	12.4	740315 11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715 8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115 11.0
I4	741215	12.4	741231	12.8	-1		
I2		0	TRIB 2 INFLOW RATE - RM 60				
I4	740101	-1	741231	-1.	-1		
I2	1	0	TRIB 2 - RM 60				
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0	TRIB 2 - RM 60 - TDS				
I4	740101	150.	741231	150.	-1		
I2		0	TRIB 2 - RM 60 - CBOD				
I4	740101	0.5	741231	0.5	-1		
I2		0	TRIB 2 - RM 60 - DO				
I4	740101	12.6	740115	12.7	740215	13.0	740315 12.6
I4	740415	11.5	740515	9.1	740615	8.6	740715 7.7
I4	740815	7.7	740915	9.0	741015	9.7	741115 11.1
I4	741215	12.6	741231	12.6	-1		
I2		0	TRIB 3 INFLOW RATE - RM 40				
I4	740101	-1	741231	-1.	-1		



I2	1	0 TRIB 3 - RM 40						
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708	-8.
I4	740826	-5.	741231	-1.5	-1			
I2		0 TRIB 3 - RM 40 - TDS						
I4	740101	150.	741231	150.	-1			
I2		0 TRIB 3 - RM 40 - CBOD						
I4	740101	0.5	741231	0.5	-1			
I2		0 TRIB 3 - RM 40 - DO						
I4	740101	12.6	740115	12.7	740215	13.0	740315	12.6
I4	740415	11.5	740515	9.1	740615	8.6	740715	7.7
I4	740815	7.7	740915	9.0	741015	9.7	741115	11.1
I4	741215	12.6	741231	12.6	-1			
I2		0 TRIB 4 INFLOW RATE - RM 30						
I4	740101	-1	741231	-1.	-1			
I2	1	0 TRIB 4 - RM 30						
I4	740101	-1.5	740408	-1.5	740422	-3.0	740708	-6.
I4	740826	-5.	741231	-1.5	-1			
I2		0 TRIB 4 - RM 30 - TOTAL DISSOLVED SOLIDS						
I4	740101	160.	741231	160.	-1			
I2		0 TRIB 4 - RM 30 - CARBONACEOUS BOD						
I4	740101	0.6	741231	0.6	-1			
I2	-1	0 TRIB 4 - RM 30 - DISSOLVED OXYGEN						
I4	740101	100.	741231	100.	-1			

ER

TEST PROBLEM 6 - Tandem Reservoirs with Steady State Option and Flow  
Augmentation

The system simulated in this test of the water quality module consists of the same reservoir and stream configuration as Test Problem 2. The unique input to this test problem, includes selecting the steady state and flow augmentation options (J9 card, Fields 2 and 3) and specifying the same input changes as Test Problem 5.

A complete listing of the input data deck is given below. A complete output listing is included with the computer source code distribution.

```

T1  TESTING HEC5Q WATER QUALITY SIMULATION CAPABILITY
T2  TANDEM RIVER SYSTEM...STEADY STATE CONDITIONS...FLOW AUGMENTATION OPTION
T3  TEST PROBLEM 6
J1   0      5      5      3      4      2      0      0
J2   0      0      0      0      0      0      0
J9   1      1      0
RL  10 1200000      0 100000 200000 1500000 1600000
RO   3      20      30      40
RS   7      100     6300   31300   88000  188000  563000 1688000
RQ   7      0    20000   30000   40000   50000   50000   50000
RA   7      10      500    1500    3000    5000   10000   20000
RE   7      800     825     850     870     900     950    1030
R3   2      2      2      2     99     99     99     99     99     99
R3  99     99
CP  10    15000     300     200
IDCP10-HAYES DAM
RT  10      20     2.2     .25     12      0
CP  20    12000     300     200
ID  CP20 ** RM60
RT  20      30     2.2     .25     12      0
CP  30    12000     300     200
ID  CP30 ** RM40
RT  30      40     2.2     .25     12      0
RL  40  550000      0    2000  550000  952000 1130000
RO   1      50
RS   8      2000   20000   52000  113000  209000  320000  550000  800000 1130000
RQ   8      0    5680   5680   5680   5680   5680   29180   59680  104980
RA   8      150   2100   4500   7600   11800   17000   22400   28600   37200
RE   8      892    910    920    930    940    950   962.5    970    980
R3   2      2      2      2     99     99     99     99     99     99
R3  99     99
CP  40    10000     300     200
IDCP40-DAVIS DAM
RT  40      50     2.2     .25     12      0
CP  50    50000     300     200
IDCP50 ** RM24.2
RT  50      0      0      0      0      0
ED
BF   0      5      0    074050100      5      720
NOLIST
IN  10  1MAY74   2524   2426   2099   759   3154
IN  20  1MAY74    913    716    642   170   1203
IN  30  1MAY74    913    716    642   167   1203
IN  50  1MAY74   4641   1361   2134   726   2991
QA  10  1MAY74   2380   2347   2128   673   2898
EJ
TI  FICTICIOUS TANDEM RIVER BASIN TEST OF HEC-5Q WITH WATER QUALITY
TI  RESERVOIRS ARE FICTICIOUS ALSO ** C.P. OF 10, 20, 30, 40 AND 50
TI  CONSTITUENTS ARE TEMPERATURE, TDS, CARBONACEOUS BOD AND OXYGEN
JA  740501 740828      5      2      F      0
EZ  -1

```

ET	121	64.06	138.8	2385.6	12.35
ET	122	62.44	111.4	2409.1	10.31
ET	123	65.44	126.3	2385.9	10.60
ET	124	60.66	107.7	2456.1	10.34
ET	125	63.36	102.6	2457.1	9.35
ET	126	57.60	124.1	2466.3	12.60
ET	127	58.75	89.7	2507.6	8.88
ET	128	66.16	90.8	2484.1	7.72
ET	129	66.36	138.3	2446.0	11.48
ET	130	67.68	96.1	2494.6	7.85
ET	131	70.23	130.1	2473.9	10.09
ET	132	66.18	147.4	2470.1	12.21
ET	133	62.56	144.1	2518.4	13.40
ET	134	72.00	149.0	2492.1	11.23
ET	135	71.49	175.2	2472.3	13.02
ET	136	74.91	133.5	2480.6	9.06
ET	137	78.21	176.4	2413.2	10.65
ET	138	75.06	127.7	2486.3	8.59
ET	139	72.84	131.9	2525.7	9.60
ET	140	73.33	118.8	2544.2	8.55
ET	141	81.63	95.9	2508.9	5.46
ET	142	77.95	142.0	2476.5	8.68
ET	143	73.94	148.7	2521.6	10.31
ET	144	68.99	151.9	2563.9	12.01
ET	145	67.24	99.2	2614.1	8.21
ET	146	69.55	97.3	2617.0	7.72
ET	147	64.69	119.9	2640.5	10.76
ET	148	71.17	97.5	2626.2	7.47
ET	149	73.54	145.0	2558.2	10.02
ET	150	80.04	107.4	2543.5	6.31
ET	151	77.13	137.9	2528.9	8.64
ET	152	70.47	132.4	2598.9	10.09
ET	153	72.09	120.6	2629.7	9.06
ET	154	78.21	86.5	2621.4	5.50
ET	155	79.57	99.9	2598.9	6.09
ET	156	76.06	133.5	2597.6	8.93
ET	157	77.65	133.5	2579.1	8.50
ET	158	75.63	175.0	2568.3	11.63
ET	159	78.80	137.6	2562.9	8.34
ET	160	82.00	138.6	2539.4	7.67
ET	161	77.77	212.1	2535.9	13.02
ET	162	69.73	170.9	2626.5	13.27
ET	163	71.67	119.4	2644.6	8.88
ET	164	73.76	105.8	2658.3	7.56
ET	165	79.68	93.8	2632.5	5.75
ET	166	72.72	153.5	2601.4	10.85
ET	167	71.62	145.3	2627.1	10.72
ET	168	71.26	110.0	2663.7	8.34
ET	169	73.63	124.3	2646.5	8.88
ET	170	77.79	129.1	2600.1	8.21
ET	171	82.04	144.8	2542.0	8.05
ET	172	77.67	199.4	2553.1	12.44
ET	173	81.25	107.0	2592.8	6.22
ET	174	72.32	143.9	2625.9	10.51

ET	175	71.35	151.0	2647.8	11.52
ET	176	71.62	129.3	2649.1	9.80
ET	177	77.68	96.6	2622.1	6.13
ET	178	75.09	129.3	2628.7	8.93
ET	179	74.39	127.5	2615.1	8.88
ET	180	74.98	130.1	2601.1	8.84
ET	181	74.88	210.0	2568.0	14.18
ET	182	80.55	135.6	2566.8	8.01
ET	183	80.89	185.1	2524.8	10.67
ET	184	83.64	204.0	2486.3	10.76
ET	185	83.70	200.2	2483.8	10.56
ET	186	82.60	140.0	2503.8	7.58
ET	187	83.17	106.5	2566.4	5.97
ET	188	89.10	87.1	2546.7	4.14
ET	189	89.42	102.4	2502.9	4.72
ET	190	86.77	141.1	2467.9	6.85
ET	191	82.85	165.3	2461.5	8.77
ET	192	77.04	165.3	2538.5	10.65
ET	193	79.90	105.1	2557.9	6.38
ET	194	87.21	86.2	2531.5	4.30
ET	195	82.40	168.8	2466.9	9.26
ET	196	78.49	168.8	2498.7	10.43
ET	197	76.98	140.4	2528.0	9.08
ET	198	85.08	91.6	2508.9	4.79
ET	199	83.80	141.6	2436.7	7.47
ET	200	81.34	201.3	2425.6	11.30
ET	201	77.05	147.3	2496.5	9.51
ET	202	77.18	127.0	2509.5	8.30
ET	203	82.02	109.7	2467.6	6.22
ET	204	79.34	124.5	2445.3	7.29
ET	205	80.82	119.4	2435.2	6.85
ET	206	84.99	86.9	2450.7	4.50
ET	207	89.44	81.8	2408.1	3.71
ET	208	88.47	90.9	2398.6	4.25
ET	209	82.58	133.1	2372.5	7.18
ET	210	78.96	151.3	2377.3	8.93
ET	211	77.41	150.5	2393.2	9.42
ET	212	79.23	127.3	2391.3	7.67
ET	213	83.59	103.3	2373.8	5.55
ET	214	84.94	111.8	2329.0	5.68
ET	215	79.84	175.7	2297.5	10.04
ET	216	76.86	172.7	2324.9	10.85
ET	217	75.70	118.1	2364.3	7.76
ET	218	79.32	102.2	2340.8	6.09
ET	219	84.34	95.9	2296.2	4.97
ET	220	83.50	107.5	2261.9	5.59
ET	221	83.93	98.9	2259.4	5.08
ET	222	78.15	134.9	2266.7	8.19
ET	223	78.78	161.9	2230.5	9.64
ET	224	83.66	114.8	2198.0	5.88
ET	225	82.54	122.9	2195.5	6.55
ET	226	79.68	132.4	2210.7	7.76
ET	227	81.79	96.2	2219.6	5.35
ET	228	85.68	86.2	2188.8	4.25

ET	229	79.77	152.6	2150.0	8.77			
ET	230	87.04	73.6	2159.9	3.42			
ET	231	86.54	73.1	2158.0	3.47			
ET	232	90.10	67.8	2142.1	2.93			
ET	233	85.53	89.0	2121.1	4.38			
ET	234	85.12	89.0	2106.5	4.43			
ET	235	84.78	95.2	2088.7	4.77			
ET	236	82.42	110.2	2072.5	5.88			
ET	237	87.62	71.2	2069.9	3.22			
ET	238	86.02	88.3	2042.6	4.21			
ET	239	80.53	159.8	2012.4	8.88			
ET	240	79.48	145.3	2004.1	8.19			
ET	241	79.11	149.2	1979.7	8.48			
ET	242	80.02	122.7	1985.4	6.89			
ET	-243	77.29	150.1	1973.6	9.06			
QC	1	0	0	0	1	0	1	
TQTOTAL DISSOLVED SOLIDS IN MG/L, COMPUTED AS 0.62 X CONDUCTIVITY								
TQCARBONACEOUS BOD IN MG/L								
TQDISSOLVED OXYGEN IN MG/L								
L1	1	1						
L2	10	5	10	.6	2	1		
LR	1	10000						
L3		.01	1.-6	1.-4	0	-.7		
L5	50	50000	825					
L7	10	2000	820	860	900	940		
L7	10	2000	840	880	920	960		
L8		200	400	800	1400	2000	3000	5000
PL	0.25	100	-4.00					
PL	0.05	100	-0.20					
PL	0.20	100	-8.00					
PL	0.25	100	3.2	-0.70	0.10	-0.05		
L9		40	41	42	43	45	48	60
C1		105.	105.	105.	105.	105.	105.	105.
C5		0.5	0.5	0.5	0.5	0.5	0.5	0.5
C7		9.1	9.1	9.1	9.1	9.1	9.1	9.1
SA		100	100	100	100	100	100	100
DK			0.1	1.463				
L2	40	2	60000	5	.6	2	1	
LR								
L3		.01	1.-6	1.-4	0	-.7		
L5	1	10	895.5					
L6	870	99300	962.5					
L7	7.9	2840	895.5	909.5	923.5	937.5		
L7	7.9	2840	902.5	916.5	930.5	944.5		
L8		410	460	500	550	600	650	700
PL	0.25	100	-4.00					
PL	0.05	100	-0.20					
PL	0.20	100	-8.00					
PL	0.25	100	3.2	-0.70	0.10	-0.05		
L9		54	55	57	57	57	57	57
C1		160	190	190	190	190	190	190
C5		.3	.3	.3	.3	.3	.3	.3
C7		8.4	8.7	9.2	9.2	9.2	9.2	9.2
SA		100	100	100	100	100	100	100

DK			.2		1.463		
CR		1.047	1.047	1.047	1.0159		
S1		1	1	-1	8	20	1
S2	10	65.5	20	60	1.5		2
S2	20	60.0	30	40	1.5		3
S2	0	0	0	0			
S2	40	32	50	24.2	1.975	30	4
SR	10	20	1	2			
SR	20	30	1	2			
SR	-40	50	1	2			
S3	10	65.5	844.0	0.	0.	0.	.050
S3		65.5	844.2	0.	.21	5.0	.050
S3		65.5	844.6	4.0	.35	20.0	.050
S3		65.5	845.0	14.0	.61	29.0	.050
S3		65.5	846.0	54.0	1.04	50.0	.050
S3		65.5	847.0	114.0	1.40	67.0	.050
S3		65.5	848.0	194.0	1.55	99.0	.050
S3		65.5	849.0	305.0	1.84	121.0	.050
S3		65.5	850.0	440.0	2.02	152.0	.050
S3		65.5	851.0	605.0	2.20	185.0	.050
S3		65.5	852.0	827.0	2.17	264.0	.050
S3		65.5	853.0	1100.0	2.52	279.0	.050
S3		65.5	854.0	1384.0	2.87	288.0	.050
S3		65.5	855.0	1677.0	3.15	301.0	.050
S3		65.5	856.0	1985.0	3.40	316.0	.050
S3		65.5	857.0	2308.0	3.67	326.0	.050
S3		65.5	858.0	2634.0	3.99	326.0	.050
S3		65.5	859.0	2960.0	4.30	326.0	.050
S3		65.5	861.0	3612.0	4.88	326.0	.050
S3		65.5	863.0	4264.0	5.41	326.0	.050
S3	20	60.0	825.4	0.	0.	0.	.050
S3		60.0	825.6	1.0	.22	9.0	.050
S3		60.0	826.0	10.0	.43	33.0	.050
S3		60.0	826.4	27.0	.64	52.0	.050
S3		60.0	827.4	92.0	1.13	77.0	.050
S3		60.0	828.4	179.0	1.51	96.0	.050
S3		60.0	829.4	287.0	1.79	119.0	.050
S3		60.0	830.4	418.0	2.08	138.0	.050
S3		60.0	831.4	563.0	2.38	152.0	.050
S3		60.0	832.4	723.0	2.65	166.0	.050
S3		60.0	833.4	893.0	2.95	174.0	.050
S3		60.0	834.4	1071.0	3.23	183.0	.050
S3		60.0	835.4	1258.0	3.48	191.0	.050
S3		60.0	836.4	1455.0	3.64	207.0	.050
S3		60.0	837.4	1675.0	3.68	234.0	.050
S3		60.0	838.4	1922.0	3.83	253.0	.050
S3		60.0	839.4	2175.0	4.16	253.0	.050
S3		60.0	840.4	2428.0	4.48	253.0	.050
S3		60.0	842.4	2934.0	5.08	253.0	.050
S3		60.0	844.4	3440.0	5.65	253.0	.050
S3	30	40.0	765.0	0.	0.	0.	.050
S3		40.0	765.2	1.0	.22	9.0	.050
S3		40.0	765.6	10.0	.43	33.0	.050
S3		40.0	766.0	27.0	.64	52.0	.050

S3		40.0	767.0	92.0	1.13	77.0	.050
S3		40.0	768.0	179.0	1.51	96.0	.050
S3		40.0	769.0	287.0	1.79	119.0	.050
S3		40.0	770.0	418.0	2.08	138.0	.050
S3		40.0	771.0	563.0	2.38	152.0	.050
S3		40.0	772.0	723.0	2.65	166.0	.050
S3		40.0	773.0	893.0	2.95	174.0	.050
S3		40.0	774.0	1071.0	3.23	183.0	.050
S3		40.0	775.0	1258.0	3.48	191.0	.050
S3		40.0	776.0	1455.0	3.64	207.0	.050
S3		40.0	777.0	1675.0	3.68	234.0	.050
S3		40.0	778.0	1922.0	3.83	253.0	.050
S3		40.0	779.0	2175.0	4.16	253.0	.050
S3		40.0	780.0	2428.0	4.48	253.0	.050
S3		40.0	782.0	2934.0	5.08	253.0	.050
S3		40.0	784.0	3440.0	5.65	253.0	.050
S3	40	32.0	730.6	0.	0.	0.	.050
S3		32.0	730.8	0.	.21	2.0	.050
S3		32.0	731.2	2.0	.44	6.0	.050
S3		32.0	731.6	6.0	.45	19.0	.050
S3		32.0	732.6	74.0	.84	96.0	.050
S3		32.0	733.6	177.0	1.37	109.0	.050
S3		32.0	734.6	291.0	1.80	120.0	.050
S3		32.0	735.6	421.0	2.12	135.0	.050
S3		32.0	736.6	565.0	2.44	147.0	.050
S3		32.0	737.6	715.0	2.74	155.0	.050
S3		32.0	738.6	878.0	2.99	168.0	.050
S3		32.0	739.6	1050.0	3.26	176.0	.050
S3		32.0	740.6	1230.0	3.51	184.0	.050
S3		32.0	741.6	1418.0	3.74	193.0	.050
S3		32.0	742.6	1618.0	3.83	212.0	.050
S3		32.0	743.6	1844.0	3.86	239.0	.050
S3		32.0	744.6	2094.0	4.05	253.0	.050
S3		32.0	745.6	2347.0	4.37	253.0	.050
S3		32.0	747.6	2853.0	4.98	253.0	.050
S3		32.0	749.6	3359.0	5.55	253.0	.050
S3	50	30.4	722.9	0.	0.	0.	.030
S3		30.4	723.1	2.0	.22	15.0	.030
S3		30.4	723.5	14.0	.45	45.0	.030
S3		30.4	723.9	37.0	.64	74.0	.030
S3		30.4	724.9	130.0	1.12	111.0	.030
S3		30.4	725.9	271.0	1.43	167.0	.030
S3		30.4	726.9	462.0	1.72	218.0	.030
S3		30.4	727.9	701.0	2.04	257.0	.030
S3		30.4	728.9	978.0	2.34	287.0	.030
S3		30.4	729.9	1275.0	2.59	310.0	.030
S3		30.4	730.9	1599.0	2.79	337.0	.030
S3		30.4	731.9	1964.0	2.71	418.0	.030
S3		30.4	732.9	2394.0	2.98	444.0	.030
S3		30.4	733.9	2851.0	3.24	469.0	.030
S3		30.4	734.9	3342.0	3.39	518.0	.030
S3		30.4	735.9	3887.0	3.54	571.0	.030
S3		30.4	736.9	4482.0	3.74	610.0	.030
S3		30.4	737.9	5100.0	4.01	627.0	.030



S3		30.4	739.9	6390.0	4.49	662.0	.030
S3		30.4	741.9	7745.0	4.96	692.0	.030
S3	50	28.4	725.3	0.	0.	0.	.030
S3		28.4	725.5	4.0	.23	30.0	.030
S3		28.4	725.9	22.0	.48	59.0	.030
S3		28.4	726.3	51.0	.67	90.0	.030
S3		28.4	727.3	167.0	1.13	139.0	.030
S3		28.4	728.3	375.0	1.37	249.0	.030
S3		28.4	729.3	644.0	1.75	289.0	.030
S3		28.4	730.3	946.0	2.13	313.0	.030
S3		28.4	731.3	1271.0	2.46	336.0	.030
S3		28.4	732.3	1617.0	2.76	357.0	.030
S3		28.4	733.3	1985.0	3.03	379.0	.030
S3		28.4	734.3	2387.0	3.20	428.0	.030
S3		28.4	735.3	2831.0	3.41	463.0	.030
S3		28.4	736.3	3311.0	3.55	497.0	.030
S3		28.4	737.3	3824.0	3.73	527.0	.030
S3		28.4	738.3	4370.0	3.86	575.0	.030
S3		28.4	739.3	4985.0	3.99	634.0	.030
S3		28.4	740.3	5632.0	4.20	659.0	.030
S3		28.4	742.3	7002.0	4.58	709.0	.030
S3		28.4	744.3	8458.0	5.02	742.0	.030
S3	50	26.3	722.7	0.	0.	0.	.030
S3		26.3	722.8	1.0	.22	9.0	.030
S3		26.3	723.2	8.0	.45	26.0	.030
S3		26.3	723.7	22.0	.62	45.0	.030
S3		26.3	724.7	92.0	1.00	94.0	.030
S3		26.3	725.7	219.0	1.22	167.0	.030
S3		26.3	726.7	436.0	1.38	265.0	.030
S3		26.3	727.7	751.0	1.58	365.0	.030
S3		26.3	728.7	1158.0	1.86	441.0	.030
S3		26.3	729.7	1628.0	2.17	496.0	.030
S3		26.3	730.7	2254.0	2.19	729.0	.030
S3		26.3	731.7	3038.0	2.44	809.0	.030
S3		26.3	732.7	3867.0	2.74	858.0	.030
S3		26.3	733.7	4756.0	3.00	913.0	.030
S3		26.3	734.7	5699.0	3.23	981.0	.030
S3		26.3	735.7	6697.0	3.45	1022.0	.030
S3		26.3	736.7	7750.0	3.68	1067.0	.030
S3		26.3	737.7	8825.0	3.97	1083.0	.030
S3		26.3	739.7	11032.0	4.51	1117.0	.030
S3		26.3	741.7	13278.0	5.08	1129.0	.030
S3	50	24.2	721.6	0.	0.	0.	.030
S3		24.2	721.8	6.0	.22	56.0	.030
S3		24.2	722.2	50.0	.47	150.0	.030
S3		24.2	722.6	118.0	.69	190.0	.030
S3		24.2	723.6	354.0	1.13	270.0	.030
S3		24.2	724.6	656.0	1.41	358.0	.030
S3		24.2	725.6	1079.0	1.60	484.0	.030
S3		24.2	726.6	1606.0	1.88	568.0	.030
S3		24.2	727.6	2215.0	2.16	648.0	.030
S3		24.2	728.6	2903.0	2.41	730.0	.030
S3		24.2	729.6	3687.0	2.62	834.0	.030
S3		24.2	730.6	4563.0	2.87	914.0	.030

S3		24.2	731.6	5511.0	3.10	994.0	.030
S3		24.2	732.6	6555.0	3.32	1081.0	.030
S3		24.2	733.6	7684.0	3.50	1191.0	.030
S3		24.2	734.6	8885.0	3.80	1211.0	.030
S3		24.2	735.6	10105.0	4.09	1229.0	.030
S3		24.2	736.6	11341.0	4.38	1242.0	.030
S3		24.2	738.6	13849.0	4.93	1266.0	.030
S3		24.2	740.6	16405.0	5.45	1289.0	.030
S4		854	835	775	743	742	741
S4		739.5					740
KR			0.10		1.463		
KR			0.15		1.463		
KR			0.25		1.463		
CT	10	740101	40.	3.	0.		
CT		740318	45.	3.	0.		
CT		740723	50.	3.	0.		
CT		741017	45.	3.	0.		
CT		741206	40.	3.	0.		
CT		-741231	40.	3.	0.		
CT		740101	150.	1.	0.		
CT		-741231	150.	1.	0.		
CT		740101	0.1	1.	0.		
CT		-741231	0.1	1.	0.		
CT		740101	5.	0.	30.		
CT		-741231	5.	0.	30.		
CT	20	740101	45	4	0		
CT		740318	50	4	0		
CT		740723	55	4	0		
CT		741017	50	4	0		
CT		741206	45	4	0		
CT		-741231	42	4	0		
CT		740101	160	.8	0		
CT		-741231	160	.8	0		
CT		740101	.05	.15	0		
CT		-741231	.05	.15	0		
CT		740101	4	0	50		
CT		-741231	4	0	50		
CT	30	740101	45.	3.	0.		
CT		740510	50.	3.	0.		
CT		740531	60.	3.	0.		
CT		741001	55.	3.	0.		
CT		-741231	45.	3.	0.		
CT		740101	160.	1.	0.		
CT		-741231	160.	1.	0.		
CT		740101	.15	4.	0.		
CT		-741231	.15	4.	0.		
CT		740101	4.5	4.	0.		
CT		-741231	4.5	4.	0.		
CT	40	740101	45.	3.	0.		
CT		740504	50.	3.	0.		
CT		740514	55.	3.	0.		
CT		740515	60.	3.	0.		
CT		741005	55.	3.	0.		
CT		741109	50.	3.	0.		

CT	741214	45.	3.	0.			
CT	-741231	45.	3.	0.			
CT	740101	170.	1.	0.			
CT	-741231	170.	1.	0.			
CT	740101	0.2	1.	0.			
CT	-741231	0.2	1.	0.			
CT	740101	5.5	0.	30.			
CT	-741231	5.5	0.	30.			
CT	50 740101	50.	3.	0.			
CT	740506	55.	3.	0.			
CT	740510	60.	3.	0.			
CT	740515	65.	3.	0.			
CT	740708	70.	3.	0.			
CT	740924	65.	3.	0.			
CT	741018	60.	3.	0.			
CT	741112	55.	3.	0.			
CT	741206	50.	3.	0.			
CT	-741231	50.	3.	0.			
CT	740101	190.	1.	0.			
CT	-741231	190.	1.	0.			
CT	740101	0.3	1.	0.			
CT	-741231	0.3	1.	0.			
CT	740101	6.0	0.	30.			
CT	-741231	6.0	0.	30.			
I1	740101	741231					
I2		0	TRIB 1 INFLOW RATE - RES #1				
I4	740101	-1	741231	-1.	-1		
I2	1	0	HAYES INFLOW				
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0	HAYES INFLOW - TOTAL DISSOLVED SOLIDS				
I4	740101	105.	741231	105.	-1		
I2		0	HAYES INFLOW - CARBONACEOUS BOD				
I4	740101	0.5	741231	0.5	-1		
I2		0	HAYES INFLOW - DISSOLVED OXYGEN				
I4	740101	12.8	740115	13.1	740215	12.4	740315 11.8
I4	740415	11.7	740515	9.3	740615	8.9	740715 8.2
I4	740815	7.8	740915	9.7	741015	10.0	741115 11.0
I4	741215	12.4	741231	12.8	-1		
I2		0	TRIB 2 INFLOW RATE - RM 60				
I4	740101	-1	741231	-1.	-1		
I2	1	0	TRIB 2 - RM 60				
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708 -8.
I4	740826	-5.	741231	-1.5	-1		
I2		0	TRIB 2 - RM 60 - TDS				
I4	740101	150.	741231	150.	-1		
I2		0	TRIB 2 - RM 60 - CBOD				
I4	740101	0.5	741231	0.5	-1		
I2		0	TRIB 2 - RM 60 - DO				
I4	740101	12.6	740115	12.7	740215	13.0	740315 12.6
I4	740415	11.5	740515	9.1	740615	8.6	740715 7.7
I4	740815	7.7	740915	9.0	741015	9.7	741115 11.1
I4	741215	12.6	741231	12.6	-1		
I2		0	TRIB 3 INFLOW RATE - RM 40				
I4	740101	-1	741231	-1.	-1		

I2	1	0 TRIB 3 - RM 40						
I4	740101	-1.5	740408	-1.5	740422	-5.0	740708	-8.
I4	740826	-5.	741231	-1.5	-1			
I2		0 TRIB 3 - RM 40 - TDS						
I4	740101	150.	741231	150.	-1			
I2		0 TRIB 3 - RM 40 - CBOD						
I4	740101	0.5	741231	0.5	-1			
I2		0 TRIB 3 - RM 40 - DO						
I4	740101	12.6	740115	12.7	740215	13.0	740315	12.6
I4	740415	11.5	740515	9.1	740615	8.6	740715	7.7
I4	740815	7.7	740915	9.0	741015	9.7	741115	11.1
I4	741215	12.6	741231	12.6	-1			
I2		0 TRIB 4 INFLOW RATE - RM 30						
I4	740101	-1	741231	-1.	-1			
I2	1	0 TRIB 4 - RM 30						
I4	740101	-1.5	740408	-1.5	740422	-3.0	740708	-6.
I4	740826	-5.	741231	-1.5	-1			
I2		0 TRIB 4 - RM 30 - TOTAL DISSOLVED SOLIDS						
I4	740101	160.	741231	160.	-1			
I2		0 TRIB 4 - RM 30 - CARBONACEOUS BOD						
I4	740101	0.6	741231	0.6	-1			
I2	-1	0 TRIB 4 - RM 30 - DISSOLVED OXYGEN						
I4	740101	100.	741231	100.	-1			

ER

EXHIBIT 2  
DESCRIPTION OF PROGRAM INPUT

HEC-5  
SIMULATION OF FLOOD CONTROL AND CONSERVATION SYSTEMS

APPENDIX ON WATER QUALITY ANALYSIS

TABLE OF CONTENTS  
EXHIBIT 2  
DESCRIPTION OF PROGRAM INPUT

	<u>RECORD</u>	<u>PAGE</u>
1	HEC-5 INSERT	
	1.1 J9 RECORD	2
2	TITLE INFORMATION	
	2.1 TI RECORD	3
3	JOB CONTROL INFORMATION	
	3.1 JA RECORD	4
4	WATER SURFACE HEAT EXCHANGE DATA	
	4.1 EZ RECORD	5
	4.2 ET RECORD	5
5	CONSTITUENT IDENTIFICATION DATA	
	5.1 QC RECORD	6
	5.2 TQ RECORD	6
6	RESERVOIR DATA	
	6.1 L1 RECORD	7
	6.2 L2 RECORD	8
	6.3 LR RECORD	10
	6.4 L3 RECORD	11
	6.5 L4 RECORD	12
	6.6 L5 RECORD	12
	6.7 L6 RECORD	13
	6.8 L7 RECORD	13
	6.9 L8 RECORD	14
	6.10 PL RECORD	14
	6.11 L9 RECORD	14
	6.12 C1 RECORD	15
	6.13 C2 RECORD	15
	6.14 C3 RECORD	15
	6.15 C4 RECORD	16
	6.16 C5 RECORD	16
	6.17 C6 RECORD	16
	6.18 C7 RECORD	17
	6.19 SA RECORD	17

HEC-5  
SIMULATION OF FLOOD CONTROL AND CONSERVATION SYSTEMS

APPENDIX ON WATER QUALITY ANALYSIS

TABLE OF CONTENTS  
EXHIBIT 2  
DESCRIPTION OF PROGRAM INPUT

	<u>RECORD</u>	<u>PAGE</u>
	6.20 SB RECORD	17
	6.21 SC RECORD	18
	6.22 K1 RECORD	19
	6.23 K2 RECORD	20
	6.24 K3 RECORD	20
	6.25 DK RECORD	21
	6.26 CR RECORD	22
7	STREAM DATA	
	7.1 S1 RECORD	23
	7.2 S2 RECORD	24
	7.3 SR RECORD	26
	7.4 SK RECORD	26
	7.5 S3 RECORD	27
	7.6 S4 RECORD	28
	7.7 KR RECORD	29
	7.8 CT RECORD	30
8	INFLOW TEMPERATURE AND WATER QUALITY	
	8.1 I1 RECORD	31
	8.2 I2 RECORD	32
	8.3 I3 RECORD	32
	8.4 I4 RECORD	33
9	GATE OPERATIONS DATA	
	9.1 G1 RECORD	34
	9.2 G2 RECORD	35
10	ER RECORD	36

## EXHIBIT 2

### DESCRIPTION OF PROGRAM INPUT

This exhibit contains a detailed description of each variable on each input record. The summary of input at the end of this exhibit shows the sequential arrangement of records and also serves as a "table of contents" by showing, in Field 10, the page numbers where the variables are described in this exhibit.

Variable locations for each input record are shown by field number. The records are normally divided into ten fields of eight columns each except Field 1. Variables occurring in Field 1 may normally only occupy columns 3-8 since columns 1 and 2 are reserved for the required identification characters. The different values a variable may assume and the conditions for each are described for each variable. Some variables simply indicate whether a program option is to be used or not by using numbers such as -1, 0, 1. Other variables contain numbers which express the variable magnitude. For these a + sign is shown in the description under "value" and the numerical value of the variable is entered as input. Where the variable value is to be zero, the variable may be left blank since a blank field is read as zero.

If decimal points are not provided in the data, all numbers must be right justified in the field. Any number without a sign is considered positive.

Locations of variables on records are sometimes referred to by an abbreviated designation, such as JA.4 representing the fourth field of the JA record.



## 1. HEC-5 INSERT

### 1.1 J9 RECORD

This record is inserted into the Water Quantity Simulation input file and is used to indicate that a water quality simulation is to be performed. If the J9 record is absent, no water quality simulation will be performed.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	IFLOAG	0	No flow alteration computations will performed.
		+	Flow alteration computations will be performed.
3	ISTEADY	0	Annual simulation mode (daily analysis) will be used.
		+	Long term simulation mode (monthly analysis) will be used.
4	ICALIB	0	Calibration mode is not to be used.
		+	Calibration mode is to be used.

NOTE: The longer term simulation mode and the flow alteration options are disabled when the calibration mode is being used

## 2. TITLE INFORMATION

### 2.1 TI RECORD

Three job title records required. Both alphabetic and numeric information may be used. This information will be printed as job titles on the first page of the water quality analysis output.

NOTE: The Water Quality Simulation input records follow the EJ record of the Water Quantity Simulation input file. The J9 record is inserted into the Water Quantity Simulation input file between the J8/JZ and the RL records.

### 3. JOB CONTROL INFORMATION

#### 3.1 JA RECORD

Required job control.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	IDAY	+	First day of water quality simulation; year, month and day (e.g., 740501). The first day of simulation must be on or after the first day of flow simulation (FLDAT, J3.3 or BF.5).
3	LDAY	+	Last day of water quality simulation; year, month and day.
4	NCP*	+	Number of stream control points to be used in the water quality simulation.
5	NRES*	+	Number of reservoirs used in the quality simulation.
6	IC	F	Input and output water temperatures are in degrees Fahrenheit.
		C	Input and output water temperatures are in degrees Celsius.
7	IP5	0	Do not print data transferred between Water Quantity and Water Quality Simulation modules
		1	Print data transferred between Water Quantity and Water Quality Simulation modules via the file interface.
8	IHRC	+	Time interval in hours for water quality objectives and weights data (CT Record).
		0	No variation in water quality objectives and weights during any day.
9	IHRG	+	Time interval in hours for gate operation data (G2 Record).
		0	No variation in gate operation during any day.
10	NTS	+	Maximum number of time steps increments during any day.

0      24 hour quality time step will be used during  
the simulation. Omit JB cards.

---

\* The number of control points and reservoirs used in the quality simulation may be less than the number used in the flow simulation module; however, the system defined by the water quality data must represent a portion of the larger system beginning at the upstream limits. The number of reservoirs must include any dummy reservoirs.

### 3.2 JB RECORD

Optional quality time step control. Required if NTS (JA.10) is greater than zero. A maximum of 12 periods may be defined.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	IT1	+	Date (year, month and day) through which the time step increments apply.
		-	Negative date indicates final JB card.
3	ITSI(1)	+	Time step increment <sup>1</sup> in hours for first quality time step during the day.
4	ITSI(2)	+	Time step increment <sup>1</sup> in hours for second quality time step during the day.
.	.		
.	.		
.	.		
.	ITSI(NTS) <sup>2</sup>		

---

<sup>1</sup> Time step increments may vary throughout the day, however, they must be compatible with the time step within the quantity simulation. For example, if the quantity simulation time steps are 6 hours, quality time steps of 6, 6, 6 and 6; 12 and 12; and 6, 12 and 6 would all be acceptable. Quality time steps of 8, 8 and 8 would not be acceptable. The sum of all values of ITSI for each day must equal 24 hours.

<sup>2</sup> NTS (JA.10) values are required for each period (including zeros if fewer than NTS times steps are required for a particular period). If NTS is greater than 8, a continuation of the JB card is required with ITSI(9) being defined in field 3.

#### 4. WATER SURFACE HEAT EXCHANGE DATA

##### 4.1 EZ RECORD

Required meteorological zone definition. One record must precede each set of ET records. Up to 5 zones may be specified.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	METZON	+	Meteorological zone number.
		-	Meteorological zone number. Negative value indicates final data set.
3	MINT	+	Meteorological data interval in hours.
		0	No variation in meteorological data during the day.

#### 4.2 ET RECORD\*

Required weather data. One set of ET records representing meteorological conditions is required for each day of simulation. The number of ET records required per day is controlled by MINT (EZ.3) (e.g., number of records/day = 24/MINT).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	ITIME	+	Julian date. The first observation must be on or before the first day of simulation (JA.2).
		-	Julian date; however, the negative time denotes the final ET record. The final observation must be on or after the last day of simulation (JA.3).
3	XTE	+	Equilibrium temperature in degrees Fahrenheit corresponding to ITIME (ET.2).
4	XKE	+	Coefficient of surface heat exchange in BTU/sq.ft./day/°F, corresponding to ITIME (ET.2).
5	XQNS	+	Short wave solar radiation in BTU/sq.ft./day, corresponding to ITIME (ET.2).
6	XWIND	+	Wind speed in mph, corresponding to ITIME (ET.2).

---

\* The ET records for daily data can be easily prepared using the HEC program WEATHER (HEC, 1986) and HEATX (Corps, 1974), which are described in EXHIBIT 5 and 6, respectively. For diurnal data, an undocumented HEC utility program can be obtained by request.

## 5. CONSTITUENT IDENTIFICATION DATA

### 5.1 QC RECORD

Required for constituent identification if more than temperature is being simulated.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	ID	QC	Only if "QC" is inserted in the first two columns will a water quality simulation for constituents other than temperature occur.
2-8	CONID	1 or 0	If CONID=1, the indicated constituent will be simulated. There are seven possible constituents. Fields 2-4 are reserved for conservative constituents; Fields 5-7 are reserved for nonconservative constituents. The eighth field is reserved for dissolved oxygen. If dissolved oxygen is simulated, it is assumed that the second nonconservative constituent is carbonaceous BOD (or other oxygen consuming material) and the third nonconservative constituent is nitrogenous BOD (or other oxygen consuming material). If the third nonconservative constituent is not used for an oxygen consuming material, the CONID value (Field 7) must be zero. It can not be used for a non-oxygen consuming material.
9	IPHTYO	1	The phytoplankton option will be used. Under this option the following constituents are simulated.  1. Total dissolved solids 2. Nitrate as nitrogen 3. Phosphate as phosphorus 4. Phytoplankton 5. Carbonaceous BOD 6. Ammonia as nitrogen 7. Dissolved oxygen
		0	The number of constituents simulated is defined by CONID above.

### 5.2 TQ RECORD

Required constituent identification. Up to seven records, each describing a water quality constituent that is being simulated.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1-10	CONTTL		Alphanumeric title for each constituent that is simulated. One record is inserted for each constituent for which CONID (QC record) equals 1. No TQ record should be inserted for temperature. If the phytoplankton option is selected, these records must be omitted.



## 6. RESERVOIR DATA

### 6.1 L1 RECORD

Required printout control.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	IPRT	+	Printout interval. Reservoir simulation results will be printed on those days when the Julian date (Exhibit 3) is a multiple of IPRT.
3	IVAL	+	Printout interval. Reservoir simulation results will be printed for the IVALth space step. If IVAL=2, results for every other reservoir layer will be printed

## 6.2 L2 RECORD

Required miscellaneous physical constants.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	IRCP	+	Control point ID of the reservoir.
2	SDZ	+	Thickness of vertical layer in feet or meters. The thickness of the elements is normally about 1 meter; however, thickness less than 1 meter may be required to achieve the correct representation of stratification. In some instances, elements as thick as 3 meters may be used if the reservoir is deep and a relatively rough simulation is acceptable. The number of elements is also determined by the element thickness. The number of elements equals the maximum reservoir depth divided by SDZ. A maximum of 50 elements is allowed. The computer time requirement for the reservoir simulation is approximately inversely proportional to the element thickness (i.e., proportional to the number of elements).
3	RLEN(6)	+	Effective length of reservoir in feet or meters for a tandem reservoir only. This value is divided into the element surface area to obtain the width for use in the allocation of inflow to the individual elements. This width is used to allocate inflow from the upstream reach for tandem reservoirs only. <u>Width for other reservoir inflows is defined on the following LR record.</u> A discussion of how this width is used to allocate inflow waters is provided in Paragraph 2.2.2.
		-	The inflow will be allocated uniformly to all elements down to the level of like density within the lake.
4	EDMAX	+	Mean Secchi disk reading in feet or meters during the period when the reservoir is stratified. The Secchi disk depth is the measure of light transparency. It effects the distribution of light energy with depth and influences the location of the thermocline.
5	XQPCT	+	Fraction of the solar radiation absorbed in the top XQDEP (L2.6) depth. Usually $XQPCT = .265 (.087 - .73 \ln \text{EDMAX}_{\text{meters}}) + .614$ .

6.2 L2 RECORD (continued)

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
6	XQDEP	+	Depth in which XQPCT (L2.5) of the solar radiation is absorbed in feet or meters (usually .6 m or 1.9686 ft).
7	METL	+	Meteorological zone number. Must be one of the values of METZON (EZ.2).

NOTE: Records L2 through DK should be repeated successively in contiguous groups for each reservoir in the system being simulated by the water quality simulation module. A reservoir is required above each upstream reach. An upstream reservoir, however, may be a dummy which only identifies the control point and tributary identification number (e.g., only L2 and LR required). When a J5 record is inserted in the Water Quantity Simulation input file, the standard reservoir quality data need not be altered. All unnecessary data will be skipped.

### 6.3 LR RECORD

Required tributary identification and effective reservoir length. Zero through five tributary inflows and return flow increments are allowed at each reservoir in addition to the inflow from the upstream section for tandem reservoirs (L2.3). The same tributary identification may be used for more than one reservoir or stream location. This allows the user to input the same flow fraction and quality to any number of reservoirs or stream location. Up to 50 inflow types may be assigned, including inflow to tandem reservoirs from upstream reaches. Each tandem reservoir and each return flow reduces the number of allowable tributary identifications by one (e.g., four tandem reservoirs and two return flows would make the maximum allowable value of NRREF=44. The reduction due to return flow is in addition to the return flow increments specified by a negative tributary identification).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	NRREF(1,I)	+	Tributary identification number. This number relates the tributary to the inflow quality data (records I2 through I4) (e.g., NRREF=2 would indicate the second inflow data set would apply to this tributary).
		-	Tributary identification number for return flow to the reservoir. The temperature and quality entered on the I3 or I4 records will be treated as an increment to the ambient quality, computed at the end of the previous time step at the point of withdrawal (DRTFR, DR.1). A negative value must be entered if the reservoir is specified in field 2 on any DR card. If a dummy reservoir heads a reach (i.e., reservoir removed by a J5 record), the negative tributary identification must appear in field 3. Field 1 is reserved for a normal tributary which will be ignored if the local flow is zero.
2	RLEN(I,1)	+	Effective reservoir length in feet or meters at the inflow location (see L2.3).
3,5,7,9	NRREF(2-5,I)	+,-	Tributary identification numbers for remaining tributaries and returns.
4,6,8,10	NRLEN(I,2-5)	+	Effective reservoir lengths for remaining tributaries and returns.

#### 6.4 L3 RECORD

Effective diffusion, stability method only; one L3 record or one L4 record, but not both, is required. A discussion of theory and typical data values are provided in Paragraph 2.2.4.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	GMIN	+	Water column minimum stability in kg/cu.m./water. The water column minimum stability is the density gradient below which mixing of the water column will occur. The value is usually between 0 and 0.01 kg/m <sup>2</sup> /meter. Larger positive values will cause the thermocline to form more quickly and delay destratification.
3	GSWH	+	Water column critical stability in kg/cu.m./meter.
4	A1	+	Diffusion coefficient when the water column stability is less than GSWH (L3.3) in sq.m./second.
5			Not used.
6	A3	-	Empirical constant for computing diffusion coefficients based on density gradients.

## 6.5 L4 RECORD

Effective diffusion, wind method only; one L3 or one L4 record, but not both, is required. A discussion of theory and typical data values are provided in Paragraph 2.2.4.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	GMIN	+	Water column minimum stability in kg/cu.m./meter. The water column minimum stability is the density gradient below which mixing of the water column will occur. The value is usually between zero and 0.01 kg/m <sup>2</sup> /meter. Larger positive values will cause the thermocline to form more quickly and delay destratification.
3	GSWH	+	Minimum allowable diffusion coefficient in sq.m./second.
4	A1	+	Empirical constant for computing diffusion coefficients based on wind speed.
5	A2	+	Empirical constant for computing diffusion coefficients based on wind speed.
6	A3	+	Maximum allowable diffusion coefficient, in sq.m./second.

## 6.6 L5 RECORD

Flood control outlet characteristics; optional record but at least one L5, L6 or L7 record is required.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	WOUT	+	Virtual width of the flood control outlet in feet or meters. The virtual width is the actual outlet area divided by the depth of a vertical layer, SDZ (L2.2).
2	QSMAX	+	Maximum allowable flow rate through the flood control outlet in cfs or m <sup>3</sup> /sec.
3	ELDP	+	Center-line elevation of the flood control outlet in feet or meters. The lowest elevation specified on the L5, L6 and L7 records must be greater than the minimum elevation of the reservoir elevation table (RE.2).

#### 6.7 L6 RECORD

Uncontrolled spillway characteristics; optional record but at least one L5, L6 or L7 record is required.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	WOUT	+	Virtual width of the uncontrolled spillway in feet or meters. The virtual width is the actual outlet area divided by the depth of a vertical layer, SDZ (L2.2).
2	QSMAX	+	Maximum allowable flow rate over the uncontrolled spillway in cfs or m <sup>3</sup> /sec.
3	ELSP	+	Center-line elevation of the uncontrolled spillway in feet or meters. The lowest elevation specified on the L5, L6 and L7 records must be greater than the minimum elevation of the reservoir elevation table (RE.2).

#### 6.8 L7 RECORD

Wet well characteristics (a maximum of two wet wells is allowed). Optional record but at least one L5, L6 or L7 record is required.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	WOUT	+	Virtual width of each wet well port in feet or meters. The virtual width is the actual outlet area divided by the depth of a vertical layer, SDZ (L2.2). All ports within a single wet well are assumed to have the same virtual width.
2	QWMAX	+	Maximum discharge through the wet well structure with one port open in cfs or m <sup>3</sup> /sec.
3-10	ELWW	+	Center-line elevations of the wet well ports in feet or meters beginning with the lowest port and progressing to the highest. The lowest elevation specified on the L5, L6 and L7 cards must be greater than the minimum elevation of the reservoir elevation table (RE.2).

## 6.9 L8 RECORD

Required reservoir widths.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	WIDE	+	Effective reservoir withdrawal width at elevations EL (RE.2 - RE.10) in feet or meters (normally the dam width at elevation EL). NK (RE.1) values.
Use a second L8 record if more than 9 widths are required.			

## 6.10 PL RECORD

Required outlet constituent suboptimization objective function parameters.

One PL record is required for temperature and additional water quality constituent being simulated.

PL records must appear in the order specified on the QC record.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	WEIT	0	The parameter will not be considered in the outlet quality optimization.
		+	Relative weight between parameters for outlet regulation optimization.
2-7	PLYNML	+ or -	a through f values for outlet constituent suboptimization objective function parameters. A discussion of the parameters for the outlet constituent suboptimization is provided in Paragraph 2.6.3.

## 6.11 L9 RECORD\*

Required initial reservoir temperature profile.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	TEM1	+	Initial reservoir temperature at elevations EL (RE.2 - RE.10) in degrees Fahrenheit or Celsius. NK (RE.1) values.
Use a second L9 record if more than 9 values are required.			



#### 6.12 C1 RECORD\*

Initial reservoir conservative constituent #1 profile; required record if CONID(1) = 1 (QC.2) or required TDS profile if IPHYTO = 1 (QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	CONS(1,J)	+	Initial concentrations for conservative constituent #1 or TDS, in appropriate units, at elevations EL (RE.2 - RE.10). NK (RE.1) values.  Use a second C1 record if more than 9 values are required.

#### 6.13 C2 RECORD\*

Initial reservoir conservative constituent #2 profile; required record if CONID(2) = 1 (QC.3) or required nitrate-nitrogen profile if IPHYTO = 1 (QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	CONS(2,J)	+	Initial concentrations for conservative constituent #2 or nitrate-nitrogen, in appropriate units, at elevation EL (RE.2 - RE.10). NK (RE.1) values.  Use a second C2 record if more than 9 values are required.

#### 6.14 C3 RECORD\*

Initial reservoir conservative constituent #3 profile; required record if CONID(3) = 1 (QC.4) or required phosphate-phosphorus profile if IPHYTO = 1 (QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	CONS(3,J)	+	Initial concentrations for conservative constituent #3 or phosphate-phosphorus, in appropriate units, at elevations EL (RE.2 - RE.10). NK (RE.1) values.  Use a second C3 record if more than 9 values are required.

\*The initial constituent concentration for the top elevation EL must be for a level such that the difference between the top EL and the bottom EL is evenly divisible by SDZ (L2.2).

#### 6.15 C4 RECORD\*

Initial reservoir nonconservative constituent #1 profile; required record if CONID(4) = 1 (QC.5) or required phytoplankton profile if IPHYTO = 1 (QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	CONNON(J)	+	Initial concentrations for nonconservative constituent #1 or phytoplankton, in appropriate units, at elevations (RE.2 - RE.10). NK (RE.1) values.

Use a second C4 record if more than 9 values are required.

#### 6.16 C5 RECORD\*

Initial reservoir nonconservative constituent #2 profile; required record if CONID(5) = 1 (QC.6) or required carbonaceous BOD profile if IPHYTO = 1 (QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	CBOD(J)	+	Initial concentrations for nonconservative constituent #2 or carbonaceous BOD, in appropriate units, at elevations EL (RE.2 - RE.10). NK (RE.1) values.

Use a second C5 record if more than 9 values are required.

#### 6.17 C6 RECORD\*

Initial reservoir nonconservative constituent #3 profile; required record if CONID(6) = 1 (QC.7) or required ammonia-nitrogen profile if IPHYTO = 1 (QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	BODN(J)	+	Initial concentrations for nonconservative constituent #3 or ammonia-nitrogen, in appropriate units, at elevations EL(RE.2 - RE.10). NK (RE.1) values.

Use a second C6 record if more than 9 values are required.

\*The initial constituent concentration for the top elevation EL must be for a level such that the difference between the top EL and the bottom EL is evenly divisible by SDZ (L2.2).

#### 6.18 C7 RECORD\*

Initial reservoir dissolved oxygen profile; required record if CONID(7) = 1 (QC.8) or IPHYTO = 1 (QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	OXY(J)	+	Initial concentrations for dissolved oxygen, in milligrams per liter, at elevations EL (RE.2 - RE.10). NK (RE.1) values.

Use a second C7 record if more than 9 values are required.

#### 6.19 SA RECORD

Dissolved oxygen benthic demand profile; required record if CONID(7) = 1 (QC.8) or IPHYTO = 1 (QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	SSOXY(J)	+	Rate at which dissolved oxygen is consumed by the decay of benthic material in $\text{mg/m}^2/\text{day}$ at elevations EL (RE.2 - RE.10). NK (RE.1) values.

Use a second SA record if more than 9 values are required.

#### 6.20 SB RECORD

Ammonia-nitrogen benthic source profile; required record if IPHYTO=1(QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	SSNH3(J)	+	Rate at which ammonia-nitrogen is released by the decay of benthic material in $\text{mg/m}^2/\text{day}$ at elevations EL (RE.2 - RE.10). NK (RE.1) values.

Use a second SB record is more than 9 values are required.

\*The initial constituent concentration for the top elevation EL must be for a level such that the difference between the top EL and the bottom EL is evenly divisible by SDZ (L2.2).

## 6.21 SC RECORD

Phosphate-phosphorous benthic source profile; required record if IPHTYO = 1(QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	SSP04(J)	+	Rate at which phosphate-phosphorus is released by the decay of benthic material in mg/m <sup>2</sup> /day at elevations EL (RE.2 - RE.10). NK (RE.1) values.

Use a second SC record if more than 9 values are required.

## 6.22 K1 RECORD

Phytoplankton model coefficients; required if IPHYTO=1(QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	PMAX	+	Phytoplankton maximum growth rate in 1/day.
		-1	Default is 2.0.
3	PRESP	+	Phytoplankton respiration rate in 1/day.
		-1	Default is 0.15.
4	PSETL	+	Phytoplankton settling velocity in meters/day.
		-1	Default is 0.15.
5	PS2L	+	Light half saturation constant for algae growth in kcal/m <sup>2</sup> /sec.
		-1	Default of 0.0035.
6	PS2N	+	Nitrogen half saturation constant for algae growth in mg/l.
		-1	Default of 0.06.
7	PS2P	+	Phosphorus half saturation constant for algae growth in mg/l.
		-1	Default of 0.03.
8	EXTINP	+	Phytoplankton shading/light attenuation constant 1/m/mg/l.
		-1	Default of 0.2.
9	XLAT	+	Latitude of the reservoir in degrees.

## 6.23 K2 RECORD

Phytoplankton model coefficients; required if IPHYTO = 1(QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	PMORT(1-9)	+	Phytoplankton mortality rate for January through September in 1/day. The mortality rate is designed to account for zooplankton grazing, chemical treatment and other factors which affect phytoplankton adversely.

Use a second K2 record for October, November and December mortality rates in Fields 2-4.

## 6.24 K3 RECORD

Phytoplankton model coefficients; required if IPHYTO=1(QC.9).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	ALGT1	+	Lower temperature limit at which phytoplankton will grow at 0.1 of their maximum rate in degrees Celsius.
		-1	Default of 5.
3	ALGT2	+	Lower temperature limit at which phytoplankton will grow at 0.98 of their maximum rate in degrees Celsius.
		-1	Default of 22.
4	ALGT3	+	Upper temperature limit at which phytoplankton will grow at 0.98 of their maximum rate in degrees Celsius.
		-1	Default of 30.
5	ALGT4	+	Upper temperature limit at which phytoplankton will grow at 0.1 of their maximum rate in degrees Celsius.
		-1	Default of 40.

## 6.25 DK RECORD

Decay coefficients and settling rate controls for reservoirs. This record is required only if constituents other than temperature are being simulated.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	UNCNDK	+	Decay rate at 20°C standard temperature for nonconservative constituent #1 in reservoir waters. Will be set to zero under the phytoplankton option.
3	BODDK	+	Decay rate at 20°C standard temperature for nonconservative constituent #2 (carbonaceous BOD or oxygen demanding material #1) in reservoir waters (usually 0.1).
4	BODNDK	+	Decay rate at 20°C standard temperature for nonconservative constituent #3 (nitrogenous BOD or oxygen demanding material #2 or ammonia decay rate under the phytoplankton option) in reservoir waters (usually 0.05).
5	CONVR1	+	Factor to convert input nonconservative constituent #2 concentrations to ultimate oxygen demand if dissolved oxygen is being simulated. The value of CONVR1 depends on the constituent being represented. If ultimate carbonaceous BOD is represented, CONVR1 should be 1.0. If 5-day carbonaceous BOD is represented, CONVR1 should be 1.463 (default) which assumes a bottle BOD decay rate of 0.23 per day.
6	CONVR2	+	Factor to convert input nonconservative constituent #3 concentrations to ultimate oxygen demand if dissolved oxygen is being simulated. The value of CONVR2 depends on the constituent being represented. CONVR2 should be 1.0 for ultimate nitrogenous BOD, 2.54 (default) for 5-day NBOD (assuming bottle decay rate of 0.1 per day), and 4.57 for ammonia.
7-10	NXC	0	Not a particulate parameter.
		1	Read settling rates and light extraction coefficients. Settling rates and extinction coefficient may be specified for each conservative parameter (NXC1, NXC2 and NXC3), and the first nonconservative parameter (NXC4) to represent three inorganic and one organic particulate parameter. One DS record is required for each positive value.

# 6.25a DS RECORD

Suspended Solids Settling Rate and Light Extraction Coefficient\*  
One record is required for each non zero value of NXC (DK.7-10).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	T1(1)		Three pairs of settling velocity in cm/sec (T1) versus temperature in °C (T2) for suspended solids. These three points define the curve from which settling velocities will be calculated for the ambient water temperature.
3	T2(1)		
4	T1(2)		
5	T2(2)	+	
6	T1(3)		
7	T2(3)		
8	EXTINC	+	Shading/light attenuation constant in 1/m/mg/l. This constant relates light energy attenuation within the reservoir to the particulate material concentration.

\* Settling rates and light attenuation constants for inorganic solids vary with particle size. Typical value recommendations by Dr. Michael Gee, HEC, are tabulated below. Volatile solids of similar size will have lower settling velocities due to smaller densities.

<u>Class</u>	<u>Particle Size (mm)</u>	<u>Temperature* (°C)</u>	<u>Settling Velocity* (cm/sec)</u>	<u>Light Attenuation Constant (1/m/mg/l)</u>
Colloidal	.001	--	0.000	.20-.50
Very fine silt	.004-.008	5	0.006	.10-.20
		20	0.008	
		35	0.010	
Fine silt	.008-.016	5	0.012	.05-.10
		20	0.019	
		35	0.024	
Medium silt	.016-.031	5	0.041	.02-.05
		20	0.068	
		35	0.086	
Coarse silt	.031-.0625	5	0.110	.01-.02
		20	0.180	
		35	0.230	



## 6.26 CR RECORD

Thermal correction factors. The CR record is required only if constituents other than temperature are being simulated. These factors adjust the decay rates and reaeration rates for ambient temperatures other than 20°C. These factors apply to both reservoir and stream computations.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	QUNCON	+	Thermal correction factor for nonconservative constituent #1 decay rate.
		-1	Default is 1.047.
3	QCBOD	+	Thermal correction factor for nonconservative constituent #2 (or carbonaceous BOD or oxygen demanding #1) decay rate.
		-1	Default of 1.047.
4	QNBOD	+	Thermal correction factor for nonconservative constituent #3 (or nitrogenous BOD or oxygen demanding material #2) decay rate.
		-1	Default of 1.047.
5	QREAIR	+	Thermal correction factor for dissolved oxygen reaeration rate.
		-1	Default of 1.0159.

## 7 STREAM DATA

### 7.1 S1 RECORD

Required stream data controls.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	IPRT	+	Temporal printout interval. Stream simulation results will be printed on those days when the Julian date (Exhibit 3) is a multiple of IPRT.
3	IVAL	+	Spatial printout interval. If IVAL = 1, computed results will be printed for every stream volume element. If IVAL = 2, computed results will be printed for every other volume element. (Recommended value: +1.)
4	IGEDA	1	Stream channel cross section geometry data will be printed. These are needed to evaluate stream hydraulic computations for depth.
		0	Channel geometry data will not be printed.
5	NBPP	+	Number of input channel cross section geometry tables; minimum of 2 and maximum of 300.
6	NELEV	+	Number of elevations defining the channel cross section data; minimum of 2 and maximum of 21.
7	VWR	+	Scaling factor (default value of 1.0) to adjust all channel cross section widths.

## 7.2 S2 RECORD

Reach definition and local inflow location. One record is required for each reach (i.e., I=1, NREACH). A stream reach is defined as any stream segment bounded by two control points. The reach that contains a reservoir, in a tandem reservoir system, should be characterized by a required blank S2 record.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	ICP(1,I)	+	Control point number at the upstream end of Reach I.
2	RCP(1,I)	+	River mile or kilometer at the upstream end of Reach I.
3	ICP(2,I)	+	Control point number at the downstream end of Reach I.
4	RCP(2,I)	+	River mile or kilometer at the downstream end of Reach I.
5	ELEN(I)	+	Length of stream elements for Reach I. The stream element length must be such that there are at least two computational elements in each reach and not more than 49. All stream reaches ending at the upstream end of a tandem reservoir must end with a control point that is not the confluence of two streams (junction control point).
6	RQI(1,I) <sup>1</sup>	+	River mile or kilometer location of local inflow point.
7	NSREF(1,I) <sup>1</sup>	+	Tributary identification number for inflow at location RQI(1,I) (S2.6).

---

<sup>1</sup>The local flow (i.e., local flow for control point ICP(2,I), S2.3) may be allocated to three locations within the reach. The location of the first two local inflow points are specified by RQI. The third (i.e., NSREF(3,I), S2.10) is allocated at location RCP(2,I), S2.4. The same tributary identification may be used for more than one stream inflow location or reservoir inflow. This allows the user to input the same flow fraction and quality at any number of stream locations and reservoirs. Up to 50 inflow types may be assigned, including inflow to tandem reservoirs from upstream reaches. Each tandem reservoir reduces the number of allowable tributary identifications by one (e.g., 4 tandem reservoirs would make the maximum allowable value of NSREF - 46).

## 7.2 S2 RECORD (continued)

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
8	RQI(2,I)1	+	River mile or kilometer location of local inflow point.
9	RSREF(2,I) <sup>1</sup>	+	Tributary identification number for inflow at location RQI(2,I) (S2.8).
10	NSREF(3,I) <sup>1</sup>	+	Tributary identification number for inflow at the downstream control point ICP(2,I) (S2.3).
		-	Tributary identification number for return flow to the downstream control point. The temperature and quality entered on the I3 or I4 records will be treated as an increment to the ambient quality computed at the end of the previous time step at the point of withdrawal (DRTFR,DR.1). A negative value must be entered if the control point is specified in field 2 on any DR record.

<sup>1</sup> The local flow (i.e., local flow for control point ICP(2,I), S2.3) may be allocated to three locations within the reach. The location of the first two local inflow points are specified by RQI. The third (i.e., NSREF(3,I), S2.10) is allocated at location RCP(2,I), S2.4. If a return flow is indicated by a negative value of NSREF(3,I) (S2.10), the location of normal tributaries (maximum of 2) must be specified by RQI. The same tributary identification may be used for more than one stream inflow location or reservoir inflow. This allows the user to input the same flow fraction and quality at any number of stream locations and reservoirs. Up to 50 inflow types may be assigned, including inflow to tandem reservoirs from upstream reaches. Each tandem reservoir reduces the number of allowable tributary identifications by one (e.g., four tandem reservoirs and two return flows would make the maximum allowable value of NRREF=44. The reduction due to return flow is in addition to the return flow increments specified by a negative tributary identification).

### 7.3 SR RECORD

Required reaeration option, meteorological zone definition and diffusion coefficient specification

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	L1	+	Upstream control point from which data apply.
		-	Upstream control point. Negative value indicates final SR record.
2	L2	+	Downstream control point to which data apply.
3	METZON	+	Meteorological zone number. Must be one of the values of METZON (EZ.2).
4	KZOPP	+	Oxygen reaeration control. One of the following may be specified:
		1	Churchill, et al.
		2	O'Conner and Dobbins
		3	Owens, et al.
		4	Langbien and Durum
		5	Thackston and Krenkel
		6	Tsivoglou and Wallace
		7	Input reaeration coefficient directly. One or more SK records will be required.
		8	Reduce oxygen deficit at location RK2MI (SR.5) by the fraction RK2 (SR.6)
5	RK2MI	+	Location where the oxygen deficit will be reduced by the fraction RK2. If the reduction in the oxygen deficit is desired at a control point, the input location should be slightly below and upstream control point or slightly above a downstream control point.
		0	KZOPP (SR.4) is other than 8.
6	RK2	+	Fraction by which the oxygen deficit will be reduced.
		0	KZOPP (SR.4) is other than 8.
7	DCC	+	Diffusion coefficient in $\text{ft}^2/\text{sec}$ or $\text{m}^2/\text{sec}$ . This coefficient will apply to all stream elements between L1(SR.1) and L2(SR.2).
		0	No diffusion between stream elements.

## SK RECORD

Element reaeration coefficient definition. SK records are required following any SR record for which direct input of the reaeration coefficient is specified (KZOPP=7, SR.4). Nine values may be specified per SK record. Repeat as necessary to define all elements bounded by L1 and L2 (SR.1 and SR.2).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	SK2	+	Reaeration coefficient, 1/day, for each element.

## 7.5 S3 RECORD\*

Channel cross section geometry. NELEV (S1.6) records are required for each of NBPP (S1.5) cross sections.

Records must be in upstream to downstream order, with a minimum of one cross section for each control point. At control points making the confluence of a tributary stream branch, a cross section must be provided for both the mainstem and the terminus of the tributary stream branch. Intermediate cross sections may be furnished. For parallel systems, cross section data are ordered from the most upstream mainstem control point to, and including, the confluence control point; then tributary control point cross section data are entered. Following the tributary cross section data, the cross section data for the mainstem downstream of the control point at the confluence are entered.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	NCPX	+	Control point at the cross section or the first control point downstream for cross sections not at a control point. The NCPX is required on only the first record of the data for each cross section.
2	XXM	+	River mile or kilometer location of cross section.
3	ELEV	+	Elevation in feet or meters. The elevation increments (between layers) must be identical on all cross sections.
4	A	+	Cross section flow area in sq. ft. or sq. m. below elevation ELEV (S3.2).
5	R23	+	Hydraulic radius to the $2/3$ power at elevation ELEV (S3.2).
6	WD	+	Surface width in feet or meters at elevation ELEV. All cross section widths will be multiplied by VWR (S1.7).
7	AMAN	+	Manning's n at elevation ELEV (S3.2).
8	QST	+	Flow in cfs of $m^3/sec$ at elevation ELEV (S3.3). If QST is left blank, the flow will be computed assuming normal depth.

NOTE: Dimension limitations are 50 cross sections per reach (between 2 adjacent control points) and 300 cross sections per job.

---

\*The S3 records can be easily prepared using HEC program GEDA [HEC 1981] which is described in Exhibit 5.

## 7.6 S4 RECORD

Required energy grade line elevation. S4 records should be ordered as described on the previous page for the S3 records.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2-10	ELEV	+	Stream channel energy grade line elevation in feet or meters at each channel cross section. Elevation must be input in the same order as the S3 record sets (i.e. upstream to downstream). Repeat S4 record as necessary to input NBPP (S1.5) elevations. Invert elevations may be used as an approximation of the energy grade line elevations if normal flow conditions prevail throughout the stream section. Elevations which result in negative slopes are not allowed.



## 7.7 KR RECORD

Decay coefficients for streams. These records are required only if nonconservative constituents other than temperature are being simulated. One record should appear for each stream reach.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	UNCONDK	+	Decay rate for nonconservative constituent #1 at standard temperature of 20°C.
		0	Phytoplankton option.
3	BODCDK	+	Decay rate for nonconservative constituent #2 at standard temperature of 20°C.
4	BODNDK	+	Decay rate for nonconservative constituent #3 (ammonia under phytoplankton option) at standard temperature of 20°C.
5	CONVR1	+	Factor to convert input nonconservative constituent #2 concentrations to ultimate oxygen demand. If dissolved oxygen is not being simulated, a value of 1.0 must appear. If dissolved oxygen is being simulated, the value of CONVR1 depends on the constituent represented by nonconservative constituent #2. If ultimate carbonaceous BOD is represented, CONVR1 should be 1.0. If 5-day carbonaceous BOD is represented, CONVR1 should be 1 .463. This factor assumes a bottle BOD decay rate K1 of 0.23 per day.
6	CONVR2	+	Factor to convert input nonconservative constituent #3 concentrations to ultimate oxygen demand. If dissolved oxygen is not being simulated, a value of 1.0 must appear. If dissolved oxygen is being simulated, the value of CONVR2 depends on the constituent represented by nonconservative constituent #2. If nitrogenous BOD is represented, CONVR2 should be 1.0. If ammonia is represented, CONVR2 should be 4.57.

## 7.8 CT RECORD

Stream water quality objectives and constituent weights are required for non-calibration simulations (ie., ICALIB(JA.4)=0) and are optional for calibration simulations. One set of CT records are provided for each constituent being simulated at each control point. Records must be entered by ascending time, constituent and control point. In other words, all temporal targets and weights for temperature at control point #1 must be entered before proceeding to the next parameters. After all targets and weights for each parameters are defined for control point #1, proceed to define targets and weights for the next control point. The time of the first set of water quality objectives and weights must be on or before the first day of simulation (JA.2), and will apply until overridden by subsequent sets. The number of CT records per day is controlled by IHRC (JA.8) (ie., number of records/day = 24/IHRC).

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	ID	+	Control point ID number. The ID is only required on the first temperature objective record for each control point.
2	ITIMCP	+	Time that the target becomes effective, year, month and day e.g., 740501). Objectives and weights are held constant until respecified by subsequent CT records.
3		-	Negative date indicates the final set of CT cards in each temporal data set.
3	CONMAX	+	Target value for temperature or constituent concentration.
4	WEITUP	+	Relative weight assigned to violation caused by exceeding the target value.
5	WEITDN	+	Relative weight assigned to violation caused by not exceeding the target value.
6-10	JREG	+	Reservoirs to be operated to meet water quality target during flow augmentation. Up to 10 upstream reservoirs may be specified for each control point on the first and second temperature records only.

## 8. INFLOW TEMPERATURE AND WATER QUALITY

One I1 record followed by sets of I2 and I3 records, or I2 and I4 records, are required for each tributary or reservoir inflow. The total number of data sets must equal the maximum value of NRREF (LR.1, 3, 5, 7 and 9) or NSREF (S2.7, 9 and 10). Data are ordered by time and by constituent for each control point, as was done with the CT records.

### 8.1 I1 RECORD

Required inflow water quality record length and input data control. The length of record can be longer than the simulation period but must include the simulation period as a minimum.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	IIDAY	+	First day of inflow water quality data; year, month and day.
3	LLDAY	+	Last day of inflow water quality data; year, month and day.
4	I3HR	0	I3 record data frequency will be based on daily time increment.
		1	I3 record data frequency will be based on hourly time increment.
5	I4HR	0	I4 record time data will be entered as yr/mo/day.
		1	I4 record time data will be entered as yr/mo/dy/hr

## 8.2 I2 RECORD

Required inflow data control and identification.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	IEQ	+	Meteorological zone number, must be one of the values of METZON (EZ.2). Inflow temperature will be computed as the departure from the equilibrium temperature.
		100+	Meteorological zone number plus 100. Inflow temperatures will be computed by a factor times the equilibrium temperature (i.e., a value of 104 would indicate that inflow temperature would be based on Zone 4 equilibrium temperatures).
		-1	Dissolved oxygen will be input as a percent of saturation.
		0	All other constituents or temperature or dissolved oxygen to be entered in standard units.
3	IDINT	+	Local inflow rate or quality data update interval in days or hours (see I1.4). Inflow data are input using a series of I3 cards under this option.
		0	Local flow inflow rate or quality data are input at variable time intervals using a series of I4 cards under this option.
4-8	CON	ALPHA	Description of inflow data.
9	RTO	+	Proportionality constant (units = 1/hr) for dampening the change in temperature or dissolved oxygen if IEQ (I2.2) is non zero.* If RTO times the time step increment exceeds 1, no dampening will occur.

\* The inflow temperature is determined by:

$$T = (T_o(1-RTO \cdot \Delta T) + (T_e + \Delta T)RTO \cdot \Delta T)$$

$$0 < RTO \cdot \Delta T \leq 1$$

where

- T = inflow temperature
- T<sub>o</sub> = inflow temperature for previous time step
- ΔT = time step in hours
- T<sub>e</sub> = equilibrium temperature
- ΔT = departure from equilibrium temperature

Dissolved oxygen concentrations are determined in a similar fashion. Dampening should be used when short meteorological data intervals (MINT, EZ.3 less than 24 hours) result in large diurnal changes in equilibrium temperature.

### 8.3 I3 RECORD

Inflow rate and water quality data at constant time interval (i.e., positive IDINT, I2.3). The number of I3 records is determined by the length of inflow water quality record (I1.2 and I1.3) and the inflow data update interval (I2.3). (Examples: If I3HR (I1.4) is zero, 72 days of record with 4 day update interval would require  $1 + 72/4 = 19$  values and a total of 2 records; If I3HR (I1.4) is one, 72 days of record with 6 hour update interval would require  $1 + 72 \cdot 24/6 = 289$  values and a total of 29 records. Optional record.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1-10	CONC	+ or -	Inflow rate or water quality constituent concentration, in appropriate units. Inflow may be input as a rate (positive values of CONC) or as a fraction of the total local flow (negative values of CONC) (i.e., CONC = -.5 would indicate that one-half of the local flow would be allocated to the inflow). Temperatures may be input directly, as departures from the equilibrium temperature or as a ratio of the equilibrium temperature. Dissolved oxygen may be input as a percent of saturation. The types of data are controlled by IEQ (I2.2). Straight line interpolation is used to determine water quality constituent concentrations at intermediate times.

#### 8.4 I4 RECORD

Inflow rate and water quality data at variable time intervals (i.e., IDINT, I2.3 = 0); optional record.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1			Not used.
2	ITIME	+	Time of observation. The first time of observation must be on or before IIDAY (I1.2) and the last observation on or after LLDAY (I1.3). This record may be repeated as necessary to include the entire inflow period.
		-1	Denotes the end of the data set.
3	CONC	+ or -	Inflow rate or water quality constituent concentrations, in appropriate units. Inflow may be input as a rate (positive values of CONC) or as a fraction of the total local flow (negative values of CONC) (i.e., CONC = -.5 would indicate that one-half of the local flow would be allocated to the inflow). Temperatures may be input directly, as departures from the equilibrium temperature or as a ratio of the equilibrium temperature. Dissolved oxygen may be input as a percent of saturation. The types of data are controlled by IEQ (I2.2). Straight line interpolation is used to determine water quality constituent concentrations at intermediate days.
4	ITIME	+ or -1	Sets of time and corresponding local
5	CONC	+ or -	inflow rate or water quality data.
6	ITIME		
7	CONC		
8	ITIME		
9	CONC		

If 14HR (I1.5) is zero, the time (beginning of the day) is entered as year, month and day. If 14HR is one, the time (end of the hour) is entered as year, month, day and hour (e.g., 7050112).

## 9 GATE OPERATIONS DATA

One G1 record, followed by as many G2 records as necessary, are required when the calibration mode is being used. These records are only needed for the calibration mode.

### 9.1 G1 RECORD

Length of gate operations record. The length of record can be longer than the simulation period but must include the simulation period as a minimum. Required record for the calibration mode.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	IDAY	+	First day of gate operations data, year, month and day expressed as YRMODA (e.g., 760501).
2	LDAY	+	Last day of gate operations data, year, month and day expressed as YRMODA.

## 9.2 G2 RECORD

Optional gate operations data for model calibration (required if ICALIB (J9.4) = 1). The gate operations data on these records must start and stop on the dates given on the G1 record for all reservoirs in the system. The number of G2 records per day is controlled by IHRG (JA.9) (i.e., number of records/day = 24/IHRG).


<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
1	RESNO	+	Control point number for reservoir to which data pertain.
2	IIDAY	+	Starting day of period for which data on this record is applicable (YRMODA) (e.g., 760501).
3	LLDAY	+	Final day of period for which data on this record is applicable (YRMODA).
		-	Final day on last G2 record requires a negative LLDAY.
4	QFCI	+	Flow through flood control outlet for period.
5	QSPI	+	flow through spillway for period.
6	QWW1I	+	Flow through wet well #1 for period.
7	GATE1I	+	Number of the gate in wet well #1 through which flow QWW1I (G2.6) passes, numbered from bottom gate upward.
8	QWW2I	+	Flow through wet well #2 for period.
9	GATE2I	+	Number of the gate in wet well #2 through which flow GWW2I (G2.8) passes, numbered from bottom gate upward.



10 ER RECORD

The simulation will end with the appearance of an ER record.

REC-5 WATER QUALITY SIMULATION MODULE  
SUMMARY OF INPUT





	1	2	3	4	5	6	7	8	9	10
FIELD	1	2	3	4	5	6	7	8	9	10
***ER										
(13) C2	RESNO	1DAY	LLDAY	QCCT	QSP1	QW11	CATE11	QW11	CATE21	
(13) C1	1DAY	LLDAY								
(12) 14	ITIM(1)	CONC(1)	- - - 4 sets of values per record							
(12) 13	CONC(1)	- - - 1 + (1 + LDAY - 1DAY) / 10INT values, 10 per record								
(12) **12	IEQ	10INT	CON(1)	- - - title, fields 4-8						NTU
**11	1DAY	LLDAY	13HR	14HR						
(11) **C7	10	ITIMCP	CONMAX	WEITUP	WEITDN	JREC				
(9) **ER	UNCONDK	BOODCK	BOODCK	CONV1	CONV2					
**56	ELEV(1)	- - - HSPF values (81.5)								
(10) **53	MCPX	RHX	ELEV	A	R23	10	AMAN	QST		
SK	SK2 - - - 8 value for each element of the reach, 9 per record, fields 2-10									
**ER	L1	L2	NETZON	R20PP	RK2M1	RK2	DCC			
(9) **52	ICP	ICP	ICP	ICP	ELEN	RQ1	MSREF	RQ1	MSREF	MSREF
**51	IPRT	IVAL	ICEDA	HSPF	HELEV	VWR				
(8) CR	QUNCON	QCBOD	QWBOB	QREATR						
(8) DS	T1	T2	T1	T2	T1	T2	EXTINC			
(8) DE	UNCONDK	BOODCK	BOODCK	CONV1	CONV2	NKC(1)	NKC(2)	NKC(3)	NKC(4)	
(7) E3	ALCT1	ALCT2	ALCT3	ALCT4						
(7) E2	PHOXT(1) - - - 12 monthly values; 3 in fields 2-4 on second record									
(7) E1	PMAX	PRESF	PSETL	PS2L	PS2H	PS2P	EXTIMP	ELAT		
(4)(7) SC	SSPO4(J) - - - MK values (82.1)									
(4)(7) SB	SSNH3 - - - MK values (82.1)									
(4)(6) SA	SSOXY(J) - - - MK values (82.1)									
(4)(5) C7	OXY(J) - - - MK values (82.1)									
(4)(5) C6	DOH(J) - - - MK values (82.1)									
(4)(5) C5	CDOB(J) - - - MK values (82.1)									
Fields	1	2	3	4	5	6	7	8	9	10

- \*\* Required records.
- (5) Required only if constituent is being simulated.
- (6) Required if CONID(7) = 1 (QC.8).
- (7) Required if IPHYIO = 1 (QC.9).
- (8) Should not appear if only temperature is being simulated.
- (9) One record is required for each reach (i.e., one fewer than the number of control points).
- (10) One set of HELEV record cards required for each of HSPF cross sections.
- (11) One record for each target, constituent and control point.
- (12) One 12 record combined with sets of 13 or sets of 14 records are required for each constituent including flow and for each local inflow point.
- (13) Required if CALIB = 1 (JP.4).

2

EXHIBIT 3  
JULIAN CALENDAR

# JULIAN DATE CALENDAR

(PERPETUAL)

Day	Jan	Feb	Mar	Apr	May	June	July	Aug	Sep	Oct	Nov	Dec	Day
1	001	032	060	091	121	152	182	213	244	274	305	335	1
2	002	033	061	092	122	153	183	214	245	275	306	336	2
3	003	034	062	093	123	154	184	215	246	276	307	337	3
4	004	035	063	094	124	155	185	216	247	277	308	338	4
5	005	036	064	095	125	156	186	217	248	278	309	339	5
6	006	037	065	096	126	157	187	218	249	279	310	340	6
7	007	038	066	097	127	158	188	219	250	280	311	341	7
8	008	039	067	098	128	159	189	220	251	281	312	342	8
9	009	040	068	099	129	160	190	221	252	282	313	343	9
10	010	041	069	100	130	161	191	222	253	283	314	344	10
11	011	042	070	101	131	162	192	223	254	284	315	345	11
12	012	043	071	102	132	163	193	224	255	285	316	346	12
13	013	044	072	103	133	164	194	225	256	286	317	347	13
14	014	045	073	104	134	165	195	226	257	287	318	348	14
15	015	046	074	105	135	166	196	227	258	288	319	349	15
16	016	047	075	106	136	167	197	228	259	289	320	350	16
17	017	048	076	107	137	168	198	229	260	290	321	351	17
18	018	049	077	108	138	169	199	230	261	291	322	352	18
19	019	050	078	109	139	170	200	231	262	292	323	353	19
20	020	051	079	110	140	171	201	232	263	293	324	354	20
21	021	052	080	111	141	172	202	233	264	294	325	355	21
22	022	053	081	112	142	173	203	234	265	295	326	356	22
23	023	054	082	113	143	174	204	235	266	296	327	357	23
24	024	055	083	114	144	175	205	236	267	297	328	358	24
25	025	056	084	115	145	176	206	237	268	298	329	359	25
26	026	057	085	116	146	177	207	238	269	299	330	360	26
27	027	058	086	117	147	178	208	239	270	300	331	361	27
28	028	059	087	118	148	179	209	240	271	301	332	362	28
29	029		088	119	149	180	210	241	272	302	333	363	29
30	030		089	120	150	181	211	242	273	303	334	364	30
31	031		090		151		212	243		304		365	31

FOR LEAP YEAR USE REVERSE SIDE

# JULIAN DATE CALENDAR

FOR LEAP YEARS ONLY

Day	Jan	Feb	Mar	Apr	May	June	July	Aug	Sep	Oct	Nov	Dec	Day
1	001	032	061	092	122	153	183	214	245	275	306	336	1
2	002	033	062	093	123	154	184	215	246	276	307	337	2
3	003	034	063	094	124	155	185	216	247	277	308	338	3
4	004	035	064	095	125	156	186	217	248	278	309	339	4
5	005	036	065	096	126	157	187	218	249	279	310	340	5
6	006	037	066	097	127	158	188	219	250	280	311	341	6
7	007	038	067	098	128	159	189	220	251	281	312	342	7
8	008	039	068	099	129	160	190	221	252	282	313	343	8
9	009	040	069	100	130	161	191	222	253	283	314	344	9
10	010	041	070	101	131	162	192	223	254	284	315	345	10
11	011	042	071	102	132	163	193	224	255	285	316	346	11
12	012	043	072	103	133	164	194	225	256	286	317	347	12
13	013	044	073	104	134	165	195	226	257	287	318	348	13
14	014	045	074	105	135	166	196	227	258	288	319	349	14
15	015	046	075	106	136	167	197	228	259	289	320	350	15
16	016	047	076	107	137	168	198	229	260	290	321	351	16
17	017	048	077	108	138	169	199	230	261	291	322	352	17
18	018	049	078	109	139	170	200	231	262	292	323	353	18
19	019	050	079	110	140	171	201	232	263	293	324	354	19
20	020	051	080	111	141	172	202	233	264	294	325	355	20
21	021	052	081	112	142	173	203	234	265	295	326	356	21
22	022	053	082	113	143	174	204	235	266	296	327	357	22
23	023	054	083	114	144	175	205	236	267	297	328	358	23
24	024	055	084	115	145	176	206	237	268	298	329	359	24
25	025	056	085	116	146	177	207	238	269	299	330	360	25
26	026	057	086	117	147	178	208	239	270	300	331	361	26
27	027	058	087	118	148	179	209	240	271	301	332	362	27
28	028	059	088	119	149	180	210	241	272	302	333	363	28
29	029	060	089	120	150	181	211	242	273	303	334	364	29
30	030		090	121	151	182	212	243	274	304	335	365	30
31	031		091		152		213	244		305		366	31

(USE IN 1964, 1968, 1972, etc.)

EXHIBIT 4


PROGRAM WEATHER USERS MANUAL



**US Army Corps  
of Engineers**

The Hydrologic  
Engineering Center

---



**GENERALIZED COMPUTER PROGRAM**

**WEATHER**

**USERS MANUAL**

**January 1986**



WEATHER

USERS MANUAL

JANUARY 1986

US ARMY CORPS OF ENGINEERS  
WATER RESOURCES SUPPORT CENTER

HYDROLOGIC ENGINEERING CENTER  
609 SECOND STREET  
DAVIS, CALIFORNIA 95616

(916) 551-1748  
FTS 460-1748

WEATHER  
USERS MANUAL

TABLE OF CONTENTS

<u>TITLE</u>	<u>PAGE</u>
1. Introduction	1
1.1 Purpose of Program	1
1.2 Origin of Program	1
1.3 Hardware Requirements	1
2. Program Concepts	1
3. Input	2
4. Output	3
Appendix I. National Weather Service, CD144 Reference Manual	4
Appendix II. Example Input for HEC-5Q Interface	19
Appendix III. Example Input for WQRRS Interface	19
Appendix IV. Example Output for HEC-5Q Interface	20
Appendix V. Example Output for WQRRS Interface	21

# WEATHER

## 1. INTRODUCTION

### 1.1 Purpose of Program

Program WEATHER was developed to assist the user of the WQRRS and the HEC-5Q models with the preparation of the required input weather data. The program reads a NOAA National Climatic Center weather data file and outputs a file in the proper input format for either the WQRRS or the HEC-5Q program.

### 1.2 Origin of Program

The WEATHER program was originally written by Mr. Alfred Onodera in 1974 to provide the WQRRS user with input assistance. The program has been modified by Mr. R.G. Willey to provide more flexibility of time scales and output capability for both WQRRS and HEC-5Q.

### 1.3 Hardware Requirements

This program is written in FORTRAN 77 without machine dependencies. The program has been tested on HARRIS and CDC equipment. There should be little, if any, problem in compilation on other computers.

## 2. PROGRAM CONCEPTS

The WEATHER program reads a National Climatic Center data file of hourly or three hourly weather data. The file contains air (dry bulb) temperature, wet bulb temperature, dew point temperature, wind speed, barometric pressure, and cloud cover in addition to other weather parameters. Some stations, during some years, only have three hourly data but the general format is considered to be hourly.

The WQRRS model can use hourly weather data or any multiple of hourly that divides evenly into 24 hours. The HEC-5Q model can only use daily average data. The cloud cover, which is used to predict the amount of solar radiation reaching the ground, should be averaged only during day-light hours.

The model needs an initial input record which specifies which program options the user wants to use. Based on the input from this header record, the program provides either hourly (or multiples of hourly) weather data for the WQRRS model, or the averaged daily data for either the WQRRS or the HEC-5Q models. The formats and types of weather parameters used are different for each model.

### 3. INPUT

The input begins with three title cards having any alpha character in columns 1-80, although it is suggested that the first two columns be used for a card I.D. Following the three titles, the initial header record contains the following:

Columns	Description
1-2	Card identification (e.g. C1).
3-8	Starting year; two digits
9-16	Starting month.
17-24	Starting day.
25-32	Last year of simulation; two digits.
33-40	Last month of simulation.
41-48	Last day of simulation.
49-56	Index which equals 1 for WQRRS output format or 0 for HEC-5Q output format.
57-64	Index which equals 1 for wet bulb input or 0 for dew point input. Only needed for WQRRS interface.

The title records and the header record are read from unit 5. The remaining input is from the National Climatic Center containing weather data in their "CD144" format. This data may need to be unblocked to 80-character (card-image) records before processing. Appendix I defines the type of available data and its format. National Climatic Center data can be ordered from Asheville, North Carolina, for non-Corps offices and from Scott Air Force Base, Illinois for Corps offices. The Corps offices should refer to Army Pamphlet 115-1 "Requests for Climatological Support to Army Activities," dated June 1983. Both offices' addresses and phone numbers are given below:

#### For Corps Offices

Commander  
USFA Environmental Technical  
Applications Center  
ETAC/DO  
Scott AFB, IL 62225  
(FTS) 672-0404\*  
(704) 259-0404\*

#### For Non-Corps Offices

National Climatic Center  
Federal Building  
Asheville, NC 28801  
(704) 259-0682

Example inputs are shown in Appendices II and III.

\*This phone connects with Air Force Staff located at Asheville, NC. They can answer your questions, although you must order your data from Scott AFB.

#### 4. OUTPUT

The program output is weather data for the input station for the exact period of interest in a format for either the WQRRS or the HEC-5Q (actually HEC-5Q type output is input to a preprocessor called HEATX, which provides output for HEC-5Q input format). The results are written to unit 7. Example outputs for unit 7 are shown in Appendices IV and V.

If your execution is unsuccessful, the following messages (from unit 6) may be helpful for editing your data:

<u>Message</u>	<u>Remarks</u>
STOP 55	Starting hour must be 01 for three hour intervals and 00 for all other intervals.
STOP 200	Program read an end of file.

**APPENDIX I**

**NATIONAL WEATHER SERVICE**

**CD144 REFERENCE MANUAL**

[illegible]

TESTSET DATA: Blanks in appropriate columns are used to indicate missing data. Identification cards were punched for missing observations at AWS stations unless a whole month's record was missing. Punching of ID cards for AWS stations was phased out from Sep-Dec 1988.

COLUMNS AND ELEMENTS PUNCHED: Columns 1-79 are punched.  
Elements punched are: (Index on page 14)

PERIOD OF RECORD: Navy Apr 1945- Weather Bureau Jan 1948- Air Force Jan 1949-  
Note: Some prior periods are included in this deck. A status of the period of  
record for each station is maintained at the National Climatic Center,  
Asheville, North Carolina.

**OBSERVATION TIME:** Local Standard Time (LST). For information relating to changes in time of observation, refer to SUPPLEMENTARY NOTE A, page 9. Beginning 1 Jan 65, the Weather Bureau reduced the number of hourly observations punched from 24 to 8 per day. These 3-hourly observations correspond to record observations at 0000, 0300, 0600, 0900, 1200, 1500, 1800, and 2100 GMT. As a result of special studies, some WB stations may have 24 observations per day punched.

**CODES:** WBAN and WMD

**SOURCE:** WEAN Forms 10A, 10B and 10 or similar forms. In addition to WEAN Forms 10A, 10B and 10, the Air Force and Navy, those of FAA and Signal Corps are included. Effective 1 apr 70, forms redesignated as NF 1-10A, 1-10B and 1-10C. NF indicates Meteorological Form.

**ADDITIONAL REMARKS:** Card content is generally for recent years. Prior punching or processing procedures are described in "Remarks Column" or in SUPPLEMENTARY NOTES.

Effective 1 Jan 68, the Air Force began the use of the METAR Code at nearly all stations located outside the North American Continent. Observations for these stations are not available on punched cards but on magnetic tape only.

Decks with similar data are listed on page 14.

**CORRECTIONS:** Any errors detected in this manual should be called to the attention of the Director, National Climatic Center, Environmental Data Service, NOAA; or Chief, Data Processing Division, Environmental Technical Applications Center, USAF. Please give specific instances of error and correct information if available.

CARD CONTENT				
COLUMN	ITEM OR ELEMENT	SYMBOLIC LETTER	CARD CODE	CARD CODE DEFINITION
21-79	Missing Data	B	Blank	Unknown
1-5	Station Number WBAN		00001-99999	WBAN Number
6-7	Year		00-99	Last two digits of year
8-9	Month		01-12	01 Jan to 12 Dec
10-11	Day		01-31	Day of month
12-13	Hour		00-23	LST
14-16	Ceiling Height	hhh	000-990 XXX 888	Hundred of feet 0-99,000 feet Unlimited Cirroform ceiling, height unknown
17-20	Sky Condition First Sky Cover Layer Second Sky Cover Layer Third Sky Cover Layer Fourth Sky Cover Layer		0 1 2 4 5 7 8 Blank X	Effective 1 Sep 56. Punching of 888 for Cirroform ceiling, height unknown, was discontinued on 1 Apr 70. Four column field for up to 4 layers. 0 in unused columns. Thin sky cover is a designation given any layer for which the ratio of transparency to total sky cover at that level is $\frac{1}{2}$ or more. Prior to September 1956 dark scattered, dark broken, and dark overcast were coded 3, 6, and 9, respectively. Reporting practices of sky conditions, etc. are described in more detail in SUPPLEMENTARY NOTE C, pages 9-10.



CARD CONTENT					REMARKS	
COLUMN	ITEM OR ELEMENT	SYMBOLIC LETTER	CARD CODE	CARD CODE DEFINITION		
21-23	Visibility	VW	000-006 006-020 026-027 027-030 030-150 150-950 950	0 - 3/8 miles 3/8 - 2 miles 2 - 2 1/2 miles 2 1/2 - 3 miles 3 - 15 miles 15 - 95 miles 100 miles or more Visibilities reported other than standard punched for next lower value.	1/16 mile increments Refer to Code 3 on page 12. 1/8 mile increments 1/4 mile increments 1/2 mile increments 1 mile increments 5 mile increments	Effective 1 Apr 70, visibilities greater than 7 miles will not be recorded unless a marker is located at a distance greater than 7 miles.
24-31	Weather and/or Obstruction to Vision				*7/8 was not reported prior to Jul 52; and 1 1/8, 1 3/8, 1 5/8 and 1 7/8 until May 53. 1 1/8, 1 3/8, and 1 5/8 were punched as 1, 1 1/4, and 1 1/2 until Jan 56. 7/8 and 1 7/8 are punched as 3/4 and 1 3/4.	
24	Thunderstorm Heavy/Severe Thunderstorm Tornado Waterspout Squall	T T+ Tor Q	0 1 2 3 5	None Thunderstorm Heavy thunderstorm/ Severe thunderstorm Tornado - Land Waterspout - Water Squall	See page 8 for intensity definition Columns 24-31.	
25	Liquid Precipitation	R- R R+ RW- RW RW+ ZR- ZR ZR+	0 1 2 3 4 5 6 7 8 9	None Light rain Moderate rain Heavy rain Light rain showers Moderate rain showers Heavy rain showers Light freezing rain Moderate freezing rain Heavy freezing rain	See note, page 8, on thunderstorm intensities. Heavy thunderstorm redefined Severe Thunderstorm 1 Jul 66. Reported as rain or snow squalls (RQ, SQ) before 1949. Intensity reported prior to 1 Jun 51. Definition is given on page 8.	
26	Liquid Precipitation	L- L L+ ZL- ZL ZL+	0 4 5 6 7 8 9	None Light drizzle Moderate drizzle Heavy drizzle Light freezing drizzle Moderate freezing drizzle Heavy freezing drizzle	Codes 1, 2 and 3, light, moderate and heavy rain squalls reported prior to 1949. Drizzle intensity explained in SUPPLEMENTARY NOTE D, page 10.	

REFERENCE MANUAL

CARD CONTENT					
COLUMN	ITEM OR ELEMENT	SYMBOLIC LETTER	CARD CODE	CARD CODE DEFINITION	REMARKS
27	Frozen Precipitation	S- S S+ SP- SP SP+ IC	0 1 2 3 4 5 6 8	None Light snow Moderate snow Heavy snow Light snow pellets Moderate snow pellets Heavy snow pellets Ice crystals	ode 7, IC - and code 9, IC +; intensity reported prior to 1 Apr 63
28	Frozen Precipitation	SW- SW SW+ SG- SG SQ+	0 1 2 3 7 8 9	None Light snow showers Moderate snow showers Heavy snow showers Light snow grains Moderate snow grains Heavy snow grains	Codes 4, 5 and 6, light, moderate and heavy snow squalls reported prior to 1949.
29	Frozen Precipitation	IP- IP IP+ A AP	0 1 2 3 5 8	None Light Ice Pellets Moderate Ice Pellets Heavy Ice Pellets Hail Small Hail	Prior to 1 Apr 70 Ice Pellets were coded as Sleet (E-, E, E+). On this date Sleet and Small Hail were redefined as Ice Pellets. Ice Pellet Showers (IPW) are coded as Ice Pellets; Sleet Showers were coded as Sleet. Hail intensities reported prior to 1 Sep 56: Codes 4, 6, 7, and 9, A-, A+, AP- and AP+. Deleted 1 Apr 70; redefined as Ice Pellets.
30	Obstructions to Vision	F IF GF BD BN	0 1 2 3 4 5	None Fog Ice fog Ground fog Blowing dust Blowing sand	SUPPLEMENTARY NOTE E, Page 10 explains the reporting practices of these elements. OBSTRUCTIONS TO VISION are recorded only when the visibility is less than 7 miles.
31	Obstructions to vision	K H KH D BS BY	0 1 2 3 4 5 6	None Smoke Haze Smoke and haze Dust Blowing snow Blowing spray	Effective 1 Jul 52.

# REFERENCE MANUAL

## CARD CONTENT

COLUMN	ITEM OR ELEMENT	SYMBOLIC LETTER	CARD CODE	CARD CODE DEFINITION	REMARKS
32-35	Sea Level Pressure	PPPP	0000-9999	Millibars and tenths 0000 = 1000.0 mb 9999 = 999.9 mbs.	Thousands digit not punched. Antarctic stations, see SUPPLEMENTARY NOTE H, page 11. AWS punched 3-hourly only effective 1 Jul 58.
36-38	Dew Point Temperature	T <sup>T</sup> d <sup>d</sup> d <sup>d</sup>	000-099 X01-X99	0 to 199 Whole degrees °. -1 to -99 X in Column 36 for negative values.	Before 1949, dew point was computed with respect to ice if temperature was below 32°F. Beginning Jan 49, it was computed with respect to water regardless of temperature.
39-40	Wind Direction	dd	00-36	True direction, in tens of degrees, from which wind is blowing (Code 1, page 12 eff. 1 Jan 64)	Prior to 1964, wind directions were reported according to Code 2, page 12. See SUPPLEMENTARY NOTE H, page 11, for punching procedures at Admudsen-Scott Station, Antarctica.
41-42	Wind Speed	ff	00-99 X/	Knots X overpunch in Column 41 indicates 100 or more knots	Prior to Jan 55 in miles per hour at AF and WB stations; in knots at most Navy stations.
43-46	Station Pressure	PPPP	1000-3999	10.00 to 39.99 inches to Hundreds H <sub>g</sub> .	Station pressure is the pressure at the assigned station elevation. AWS punched 3-hourly only effective 1 Jul 58, 6-hourly effective 1 Jan 64, and 3-hourly eff. on receipt of order dated 1 Jun 65.
47-49	Dry Bulb Temperature	TTT	000-199 X01-X99 X - X 100 199	Whole degrees F. 0 to 199 -1 to -99 -100 to -199	Column 47 punched X or X overpunch for values below zero.
50-52	Wet Bulb Temperature		000-199 X01-X99	Whole degrees F. 0 to 199 -1 to -99	Column 50 punched X for minus. AWS began phasing out punching wet bulb data 1 Jul 58. WB and Navy discontinued punching wet bulb data 1 Jan 65. See SUPPLEMENTARY NOTE F, page 10 for hygrometer input. For methods of computation of wet bulb temperature and relative humidity, refer to page 13.
53-55	Relative Humidity	RH	000-100	0 to 100 whole percent Cols.	AWS discontinued punching Columns 53-55 1 Jul 58. WB discontinued punching Columns 53-55 1 Jan 65. AWS, effective 1 Apr 70, RH is punched only when entered on Form 1-108; entry of RH on form is optional. Relative humidity computations respect to ice, etc. reporting practices explained in SUPPLEMENTARY NOTE F, page 10.
56-79	Clouds and Obscuring Phenomena Total Sky Cover			Tenths 10 Tenths	See SUPPLEMENTARY NOTE G, page 11 for information on cloud layers.

REFERENCE MANUAL

WBAN HOURLY SURFACE OBSERVATIONS 144

CARD CONTENT					REMARKS
COLUMN	ITEM OR ELEMENT	SYMBOLIC LETTER	CARD CODE	CARD CODE DEFINITION	
57	Amount of Lowest Layer		0-9	Tenths	Weather Bureau stations reported detailed cloud observations (Cols. 56-78) only every 3 hours, based upon the time of synoptic observations, until June 1951 and Jan 1965-present. Only Col. 56, Total Sky Cover, was punched for the intermediate observations. Beginning Jun 51, complete cloud observations were reported and punched (Cols. 56-79) for every record obs. as was the practice with Air Force and Navy stations. In all cards of FAA(CAA) stations, Cols. 57-78 are not punched. Note: Air Force stations coverage beginning 1 Jul 58, Cols. 57-79 were reduced from hourly to 3-hourly punching. Except for Korean and down range stations, punching of Cols. 58-61 and 63-79 was discontinued on 1 Jan 64 and Cols. 57 and 62 on 1 Jul 65. SF was contraction prior to 1 Apr 70. Fs (Fractostratus) prior to 1 May 61. Cf was contraction prior to 1 Apr 70. Fc (Fractocumulus) prior to 1 May 61. Cm was contraction prior to 1 Apr 70.
58	Type of Cloud		X	None/clear	
		F	0	Fog	
		St	1	Stratus	
		Sc	2	Stratocumulus	
		Cu	3	Cumulus	
		Cb	4	Cumulonimbus	
		As	5	Altostratus	
		Ac	6	Altostratus	
		Ci	7	Cirrus	
		Cs	8	Cirrostratus	
		Sf	9	Stratus Fractus	
		Cf	X	Cumulus Fractus	
		Cm	X	Cumulonimbus mamma	
		Ns	X	Nimbostratus	
		Acc	X	Altostratus castellanus	
		Cc	X	Cirrocumulus	
			X	Obscuring phenomenon other than fog	
59-61	Height of Lowest Layer		000-990	Hundreds of feet	Effective 1 Sep 56 through 31 Mar 70. Clear, no clouds reported or surface based partial obscuring phenomena (first layer only).
			888	0 to 99,000 ft.	
			XXX	Unknown height of a cirroform layer	
				Unlimited vertical visibility	
62	Amount of Second Layer		0-9	Tenths	
			X	10 tenths	
63	Type of Second Layer		0-9	See Column 58	
			X/	See Columns 59-61	
64-66	Height of Second Layer				

DATA PROCESSING DIVISION, ETAC, USAF  
NATIONAL CLIMATIC CENTER, NOAA

REFERENCE MANUAL WBAN HOURLY SURFACE OBSERVATIONS 144

CARD CONTENT					
COLUMN	ITEM OR ELEMENT	SYMBOLIC LETTER	CARD CODE	CARD CODE DEFINITION	REMARKS
67	Summation Amount at Second Layer		0-9 X	Tenths 10 tenths	
68	Amount of Third Layer		0-9 X	Tenths 10 tenths	
69	Type of Third Layer		0-9 X/	See Column 58	
70-72	Height of Third Layer			See Columns 59-61	
73	Summation Amount at Third Layer		0-9 X	Tenths 10 tenths	
74	Amount of Fourth Layer		0-9 X	Tenths 10 tenths	
75	Type of Fourth Layer		0-9 X/	See Column 58	
76-78	Height of Fourth Layer			See Columns 59-61	
79	Total Opaque Sky Cover		0-9 X	Tenths 10 tenths	Effective Jun 51. 1 Jun 62 - Opaque Sky Cover was re-defined: Those portions of cloud layers or obscurations which hide the sky and/or higher clouds. Translucent sky cover which hides the sky but through which the sun and moon (not stars) may be dimly visible will be considered as opaque. 1 Apr 70 - Opaque Sky Cover: The amount (to the nearest tenth) of cloud layers or obscuring phenomena (aloft or surface-based) that completely hides all or a portion of the sky and/or higher clouds that may be present.
80	Not used				

## METHODS FOR DETERMINING INTENSITY OF WEATHER

THUNDERSTORM		
1945 -		
THUNDERSTORM - Characterized by occasional or fairly frequent flashes of lightning; weak to loud peals of thunder; rain, if any, light or moderate, and rarely heavy; hail, if any, light or moderate; wind not in excess of 40 miles per hour or 35 knots; and no large temperature drop with passage of the storm. Note: Wind speed changed to knots on 1 Jan 1955. 1 Jul 68 - Redefined. A thunderstorm is a local storm produced by cumulonimbus cloud, and is always accompanied by lightning and thunder, usually with strong gusts of wind, and sometimes with hail. The intensity of a thunderstorm is based on the following characteristics, observed within the previous 15 minutes: Wind gusts less than 50 knots and hail, if any, less than 3/4 inch in diameter. HEAVY THUNDERSTORM - Characterized by nearly incessant, sharp lightning; loud peals of almost continuous thunder; heavy rain showers; hail of any intensity; wind in excess of 40 mph (35 knots) as the storm passes overhead; and a rapid drop of temperature, as much as 20°F in 5 minutes with the passage of the storm. 1 Jul 68 - Redefined as SEVERE THUNDERSTORM. The intensity is based on the following characteristics, observed within the previous 15 minutes: Wind gusts of 50 knots or greater or hail, 3/4 inch or greater.		
GUSTS OF WIND		
1945 - 1951 *RAIN SQUALLS, *SNOW SQUALLS, SQUALLS Light - Gusts of 24 mph or less (21 knots) Moderate - Gusts of 25-39 mph (22-34 knots) Heavy - Gusts of 40 mph or more (35 knots) *Squalls reported separately after 1948. Intensity of squalls discontinued 1 Jun 51		
GUSTS OF WIND (CONTINUED)		
1 Jun 51 - A SQUALL is a strong wind that increases suddenly in speed, maintains a peak speed of 19 mph (16 knots) or more over a period of two or more minutes, and decreases in speed; similar fluctuations will occur at succeeding intervals. (Reported if occurred within 15 minutes of time of observation) 1 Apr 70 - A SQUALL is a sudden increase of wind speed by at least 16 knots and remaining to 22 kts or more and lasting for at least one minute. (Reported if occurred within 10 min. of obs)		
RATE OF FALL		
1945 - RAIN, RAIN SHOWERS, FREEZING RAIN Also DRIZZLE (1945-1946), SNOW, SNOW SHOWERS, SNOW PELLETS, when accompanied by other precipitation or obstructions to vision. Light - Trace to 0.10 inch per hour; maximum 0.01 inch in six minutes. Moderate - 0.11 to 0.30 inch per hour; more than 0.01 to 0.03 inch in six min. Heavy - More than 0.30 inch per hour; more than 0.03 inch in six minutes. When measurement of rate of fall was impracticable, the intensity was determined visually. Jan 47-May 51, whether alone or not, and after May 51, when accompanied by other precipitation or obstructions to vision. DRIZZLE, FREEZING DRIZZLE Light - Trace to 0.01 inch per hour Moderate - More than 0.01 to 0.02 inch/hour Heavy - More than 0.02 inch per hour.		
RATE OF FALL AND ACCUMULATION		
1946 - HAIL, *SMALL HAIL, *SLEET, *ICE PELLETS 1 Apr 70 - *Sleet and *Small Hail redefined as *Ice Pellets Light - Few pellets falling with no appreciable accumulation. Moderate - Slow accumulation. Heavy - Rapid accumulation.		
VISIBILITY PRECIPITATION		
SNOW, SNOW SHOWERS, SNOW PELLETS, DRIZZLE, FREEZING DRIZZLE, SNOW GRAINS (when occurring alone) Light - Visibility 5/8 mile or greater Moderate - Visibility 5/16 - 1/2 mile, inclusive Heavy - Visibility 1/4 mile or less 1946 - For all forms of snow, when occurring alone, intensity was determined by visibility, as shown above. Intensity of drizzle, when occurring alone, was determined by visibility in 1945-1946 and after May 1951 - ICE CRYSTALS with an intensity of greater than "very light" will be rarely observed. Above criteria were referred to if needed. 1 Apr 63 - Reporting of intensities of ICE CRYSTALS was discontinued.		
HAZE		
1945 - HAZE - Visibility 6 miles or less, but rarely below 3 miles. DAMP HAZE - Visibility 6 miles or less, but rarely as low as 1 1/4 miles. Not reported after 1948. NOTE: The intensity "Very light" (less than "Light") was not used before June 1951. It is punched as "Light" for all elements.		

## SUPPLEMENTARY NOTE A: OBSERVATION TIME Columns 14-15

The time punched is that of the record observations, taken within 10 minutes prior to the hour punched (ex. 1355 punched 14). Prior to Jun 57, obs. were taken within 10 minutes prior to the half hour; minutes are disregarded in punching (ex. 0222 punched 02; 1428, 14. All "War Times" and "Standard Meridian Times" were converted to Local Standard Time before punching. For Air Force stations in the United States, the times were punched in accordance with the established time zones. Time entries for Air Force stations outside the United States were edited prior to punching and where necessary converted to the Local Standard Time of the nearest meridian evenly divisible by 15 degrees.

## SUPPLEMENTARY NOTE B: CEILING HEIGHT Columns 14-16

Ceiling was recorded in hundreds of feet above the ground to nearest 100 feet up to 5000 feet, to nearest 500 feet up to 10,000 feet, to nearest 1000 feet above that. Before 1949, Air Force stations recorded ceilings up to and including 20,000 feet, above which point the ceiling was classified as unlimited; Weather Bureau and Navy stations recorded ceiling only up to and including 9,500 feet, above which point the ceiling was considered unlimited. Beginning in 1949, ceiling was re-defined to include the vertical visibility into obscuring phenomena not classified as thin, that, in summation with all lower layers, cover 6/10 or more of the sky. Also at that time all limits to height of ceiling were removed, so that unlimited ceiling became simply less than 6/10 sky cover, not including thin obscuration. Then, beginning 1 Jun 51, ceiling heights were no longer established solely on the basis of coverage. The ascribing of ceilings to thin broken or overcast layers was eliminated. A layer became classified as "thin" if the ratio of transparency to total coverage at that level is  $\frac{1}{2}$  or more.

## SUPPLEMENTARY NOTE C: SKY CONDITIONS Columns 17-20

Jan 1945-Dec 1948: If there is only one cloud symbol, except for low scattered and obscured, Column 17 was punched with appropriate code, Cols. 18-19 with "X" and Col. 20 was left blank. If clouds were high (above 9,500 ft.) Col. 17 was X overpunched. If clouds were low scattered, "0" was punched in Col. 17, height in Cols. 18-19, and code in Col. 20. Cols. 18-19 were left blank if height was missing. When two cloud symbols were reported, the higher cloud was punched in Col. 17 and the lower in Col. 20. In 1946, obscured (continued on next page)

TABLE OF SKY CONDITIONS

The table below shows the punching practices in Columns 17-20 for the periods Jan 45 through Dec 48, and Jan 49 through May 51.

SKY CONDITION	REMARKS	1945-1948 17181920	1949-5/51 17181920
Clear ○		0 X X 0	0 X X 0
Low Scattered ○ at 2500 ft		0 2 5 2	0 2 5 2
High Scattered ○ /over 9500 ft)		X X X	0 9 9 2
HI Sctd Lwr Sctd ○ /95 ○ at 9500 ft		X X X 2	2 9 5 2
Broken at 12000 ft 12 ○		5 X X	0 X X 5
High Brkn Lwr Brkn ○ /Ceiling 5000 ft		X X X 5	5 X X 5
High Ovc Lwr Sctd at 2500 ft ○ /○		X 2 5 2	8 2 5 2
High Ovc Lwr Brkn ○ /○		X X X 5	8 X X 5
Overcast ○		8 X X	0 X X 8
Ovc Sctd at 3000 ft ○ 30 ○		8 3 0 2	8 3 0 2
Ovc Brkn at 2500 ft ○ 25 ○		8 X X 5	8 X X 5
Obscured X		0 X X X	0 X X X
Thin Obscured -X		0 X X	0 X X

## SUPPLEMENTARY NOTE C (Continued)

sky was reported only when heavy obstructions to vision and/or heavy precipitation reduced the ceiling to zero and/or the visibility to less than  $\frac{1}{2}$  mile; and when the visibility was  $\frac{1}{2}$  mile or more, a sky symbol was always reported. Effective 1 Jan 47, the symbol "X", for obscured sky, received the same latitude of usage as all other symbols. "X" then represented sky cover of 6/10 or more, obscured by precipitation or obstructions to vision either alone or in combination with lower clouds, and irrespective of higher clouds and ceiling and/or visibility limits. In August 1947, the use of "X", for thin obscured, was authorized. In 1946 if a layer of scattered clouds above a layer of broken clouds was clearly observable, it was so reported. In 1947 and 1948, symbols corresponding to higher cloud layers indicated the amount of sky covered not only by their respective layers, but by all layers below them. In all years, the presence of few clouds (less than 1/10) was recorded in Remarks.

Jan 49 through May 51: When only one sky symbol was reported it was punched in Col. 20. The use of an "X" overpunch for high (/) layers was discontinued. (/ indicates over 9500 ft). The height of scattered clouds above 9500 ft was punched in Cols. 18-19 as 99.

Effective 1 Jun 51, the reporting of height of low scattered was discontinued, and provision was made to report any number of sky condition symbols, with the height of each. The ceiling layer was not reported separately as before, but was identified by the entry of a ceiling classification letter immediately preceding the height. Sky condition symbols were reported in ascending order of height, and were punched in that order, unless more than four were reported. In that case, the last (highest) symbol was punched in Column 20, and the first three in Columns 17-19, unless the ceiling symbol was thereby excluded. In the latter case, the first two symbols were punched in Columns 17-18, the ceiling symbol in Column 19, and the highest symbol in Column 20. No symbols were reported in Remarks, as was the practice before June 1951.

Sky condition symbols were also re-defined so that obscuring phenomena aloft and clouds were reported in the same manner (i.e., obscuring phenomena aloft were reported by O, 0, and 0, rather than X and -X). X and -X were used only to indicate the amount

of sky hidden by surface-based phenomena. -X was re-defined as partial obscuration (1/10 to less than 10/10 sky hidden). The symbols X and -X unlike O, 0, and 0, were defined by the amount of the sky hidden by surface-based phenomena, and -X did not indicate the amount of sky covered. The meaning of "thin" was re-defined. If the total opaque cover created by any layer in combination with lower layers was  $\frac{1}{2}$  or less of the summation total cover at that level, the layer was classified as thin. Note that the minus sign, when applied to O, 0 or 0 means "thin"; when applied to X, means "partial".

## SUPPLEMENTARY NOTE D: INTENSITY OF DRIZZLE Column 26

In 1947, intensity determined by visibility (as for smoke) only if drizzle occurred alone. When drizzle was accompanied by other forms of precipitation and/or obstructions to vision, its intensity was determined by rate of fall. In 1947, visibility limitations were dropped, and intensity was determined by rate of fall, even though drizzle occurred alone. In June 1951, previous visibility limits were re-instituted. Intensity of freezing drizzle determined in same manner as for drizzle. See page 8 for limits of intensities.

## SUPPLEMENTARY NOTE E: OBSTRUCTIONS TO VISION Columns 30-31

Intensity of light, moderate, or heavy were assigned to obstructions to vision, through 1946. Effective Jan 47, the reporting and punching of all intensities of obstructions to vision were discontinued. Prior to 1 Jan 49, the distinction between F and GF was arbitrary, but beginning with that date an objective distinction was established. If the sky was not hidden above an angle of  $33^\circ$  from horizontal (less than 0.6 hidden), the fog was reported as ground fog (GF). Effective 1 Apr 70, Fog (F)-Ground Fog (GF): This hydrometer is reported as F when it hides more than half (0.5-1.0) of the sky or extends upward into existing cloud layers. Otherwise it is reported as GF.

## SUPPLEMENTARY NOTE F: WET BULB TEMP. &amp; RH Columns 50-55

From Aug 60 - Dec 64 at WB stations with a hygrothermometer, wet-bulb temp. was computed and punched at NCC when instrument was operational above  $-35^\circ\text{F}$ ; when non-operational or  $-35^\circ\text{F}$  and lower, the wet-bulb temp. was punched at the station from values obtained from standby equipment. At stations not equipped with a hygrothermometer, the wet bulb temperature is considered to be the same as the dry bulb temperature whenever the dry bulb temperature is below  $-35^\circ\text{F}$ . The same value is entered in parenthesis on the WBAN with dew point being computed in



SUPPLEMENTARY NOTE F (Continued)

respect to water and this value punched into WBAN Card. The relative humidity would then be computed by machine, same as for stations equipped with a hygrometer.

Prior to Jan 49, relative humidity computed with respect to ice if the dry bulb temperature was less than 32°F. Beginning Jan 49, computed with respect to water, regardless of temperature. Relative humidity machine calculated from 1 Aug 60. RH was not punched for FAA (CAA) stations except in special cases.

SUPPLEMENTARY NOTE G: CLOUD LAYERS Columns 56-79

Provisions are made for punching as many as four layers of clouds and/or obscuring phenomena existing at one time. If more than four layers existed, the data for levels above the fourth were entered in the Remarks portion of WBAN 10B, and were not punched. Their presence is indicated by the entry for total sky cover. Layers were punched in ascending order of elevation. All fields above a layer which prevented observation were left blank. If two or more types of clouds were observed at the same height, only the predominating type was punched, their amounts being combined. For each layer, the amount, type, and height were punched, and for the second and third layer, the summation amount at the level involved was punched, reflecting the total amount of sky covered by that layer and those below it. The summation total is not necessarily the sum of the individual layers.

In addition to the total sky cover, provision was made in Jun 51 for recording and punching the total amount of opaque sky cover, which is the amount of sky hidden by clouds or obscuring phenomena, as distinguished from the total amount of sky cover.

The height of the layers of clouds or obscuring phenomena aloft was recorded in hundreds of feet, and for fully obscuring phenomena based on the ground, the vertical visibility into it was recorded, with no prescribed limit. All heights were recorded to the nearest 100 feet from the surface to 5,000 feet; to the nearest 500 feet between 5,000 and 10,000 feet; and to the nearest 1,000 feet above 10,000 feet. For obscuring phenomena prescribed as "thin", a condition reportable from Aug 47 through May 51, the height of the base was punched, and in the case of thin fog, was always zero. Before Jan 47, obscuration was not reportable as a cloud type.

SUPPLEMENTARY NOTE G (Cont.) Columns 56-79

Some Weather Bureau and Navy cards in this deck were punched from the old type of reporting form (the WBAN 10 with which deck 144 is aligned) and in which five cloud layers were reported with no summation totals. In these cases, the summation total columns were left blank, and the five layers, if reported, were condensed into four.

SUPPLEMENTARY NOTE H: ANTARCTICA STATION NOTES Columns 32-35, 39-40

## I. ADMUNDSEN-SCOTT STATION:

1. Wind Direction on all cards was punched according to the following system:

- A. A wind from 0° longitude was punched as N or 360.
- B. A wind from 90° east longitude was punched as E or 090.
- C. A wind from 180° longitude was punched as S or 180.
- D. A wind from 90° west longitude was punched as W or 270.

2. In place of sea level pressure (Column 32-35) the height of the 700 mb surface in whole meters was punched. This applies to the period 1 Dec 57 through Jan 66. Station pressure in millibars and tenths punched beginning Feb 66.

## II. BYRD STATION, ANTARCTICA

1. In place of sea-level pressure (Columns 32-35) the height of the 850 mb surface was punched in whole meters through Jan 66. Station pressure in millibars and tenths punched beginning Feb 66.

## III. PLATEAU STATION, ANTARCTICA 12/65-12/68

1. In place of sea-level pressure (Columns 32-35) the height of the 700 mb surface was punched in whole meters through Jan 66. Station pressure in millibars and tenths punched beginning Feb 66.

## CODE TABLES

When coding a meteorological report, symbolic letters are replaced by figures, which specify the value or the state of the corresponding element. In some cases, the specification of the symbolic letter (or group of letters) is sufficient to permit a direct transcription into figures (e.g., GG or FFF). In other cases, these figures are obtained by means of a special code table (or code, in short) for each element.

The codes elaborated to this end, as far as they are in world-wide use, are called international meteorological code tables. These code tables are used inversely for decoding observations and thus making available the information contained in them.

Besides the specifications given by the code tables in world-wide use, other sets of code tables are established by the WMO for regional use. Further arbitrary codes have been made necessary by the use of data in card decks which were never encoded into WMO forms.

Only codes pertinent to this card deck are included in the present manual. They appear in the order in which the elements were introduced in the description of the card content. They are numbered consecutively, and if applicable, the corresponding WMO code numbers are shown.

## Code 1

(1949 WMO Code 23)  
(1960 WMO Code 0877)

dd - True direction, in tens of degrees, of which wind is blowing (or will blow)

Code Figure	Code	Figure
00	Calm	19
01	5° - 14°	20
02	15° - 24°	21
03	25° - 34°	22
04	35° - 44°	23
05	45° - 54°	24
06	55° - 64°	25
07	65° - 74°	26
08	75° - 84°	27
09	85° - 94°	28
10	95° - 104°	29
11	105° - 114°	30
12	115° - 124°	31
13	125° - 134°	32
14	135° - 144°	33
15	145° - 154°	34
16	155° - 164°	35
17	165° - 174°	36
18	175° - 184°	

## Code 2

dd - Wind Direction

Code Figure	Code	Figure
00	Calm	
11	North	349° - 11°
12	North Northeast	12° - 33°
13	North	327° - 348°
22	Northeast	34° - 56°
32	East Northeast	57° - 78°
33	East	79° - 101°
34	East Southeast	102° - 123°
44	Southeast	124° - 146°
54	South Southeast	147° - 168°
55	South	169° - 191°
56	South Southwest	192° - 213°
66	Southwest	214° - 236°
76	West Southwest	237° - 258°
77	West	259° - 281°
78	West Northwest	282° - 303°
88	Northwest	304° - 326°

## Code 3

VVV - Visibility (Statute Miles)

Code	Miles	Code	Miles
000	0	012	1-1/8
001	1/16	014	1-1/4
002	1/8	016	1-3/8
003	3/16	017	1-1/2
004	1/4	018	1-5/8
005	5/16	019	1-3/4
006	3/8	020	2
007	1/2	024	2-1/4
008	5/8	027	2-1/2
009	3/4	030-150	3-15 * 1 mile
010	1	150-950	15-95 * 5 mile
		990	100 or more
			* increments

COMPUTATION OF WET BULB

Dry Bulb zero and above

$$TW = T - (.034N - .00072N (N - 1)) (T + Tdp - 2P + 1.7)$$

If temperature is less than 100°

$$TW \text{ Rounded} = TW + \begin{cases} .9 & \text{if col. 48 is 0, 1, 2} \\ .9 - .01(T + .9) & \text{if col. 48 is 3, 4} \\ .4 & \text{if col. 48 is 5 through 9} \end{cases}$$

If temperature is 100° or greater:

$$TW \text{ Rounded} = TW + .9.$$

for Dry Bulb temperatures less than zero:

$$TW = T - (.034N - .0006N^2) (.6(T + Tdp) - 2P + 108)$$

$$TW \text{ Rounded} = TW - .01Tdp$$

T = dry bulb temperature in °F

TW = wet bulb in °F

Tdp = dew point in °F

$$N = \frac{T - Tdp}{10}$$

P = Station pressure measured in inches of mercury

In all cases TW should be computed to at least two decimal places prior to applying the rounding factor.

COMPUTATION OF RELATIVE HUMIDITY

$$RH \approx \left( \frac{173 - .1T + Tdp}{173 + .9T} \right) 8$$

Where T = Air Temp. in °F  
T<sub>dp</sub> = Dew Point Temp. in °F

Reference to the above formula may be found in "An Approximation Formula to Compute Relative Humidity from Dry Bulb and Dew Point Temperatures" by Julius F. Bosen, Monthly Weather Review, Vol. 86, No. 12, Dec. 1958, page 486.

## OTHER CARD DECKS CONTAINING HOURLY OBSERVATIONS

## DECK

## GENERAL PERIOD

019	London Airport Hourly Surface	1948-1961
021	USAAF in Great Britain Surface	1942-1946
132	Canadian Hourly Surface Obs.	1946-1951
134	Canadian Hourly Surface Obs.	1951-1953
135	Canadian Hourly Surface Obs.	1950-1967
139	Japanese Airway Obs. Hourly Sfc.	1958-1961
141	WBAN Hourly Surface Obs.	1937-1945
142	WBAN Hourly Surface Obs.	1945-1948
146	British Hourly Obs.	1941-1948
157	Turkish Hourly Surface Obs.	1950-1959
158	German Hourly Obs. GZMO	1955-1961
158	German Hourly Obs. GZD	1962-1964
159	Korean Hourly Obs. ROK	1954-1964
159	Korean Hourly Obs. ROK	1965-1967
160	Azores Hourly Obs.	1951-1955
171	Nanking Hourly Obs.	1928-1937
172	Yungang Hourly Obs.	1938-1942
175	Taichung Hourly Obs.	1952-1956
928	Hourly Marine Sfc OSV's	1965-1970

## ELEMENTS (ITEMS) PUNCHED

CEILING	Page	SKY CONDITION	Page
	2		2
CLOUDS (4 layers)	6	STATION NUMBER	2
Amount, Type, Height			
Amount Total	5	TEMPERATURE	5
Amount Total Opaque	7	Dew Point	5
		Dry Bulb	5
DATE		Wet Bulb	5
Yr Mo Day Hour	2	VISIBILITY	3
HUMIDITY Relative %	5		
PRESSURE		WEATHER AND/OR	
Sea level	5	OBSTRUCTIONS TO VISION	3-4
Station	5	WIND	5

## CARD DECK 144 ACRONYMS

AF	Air Force
AFS	Air Weather Service
CAA	Civil Aeronautics Administration (same as FAA)
ESSA	Environmental Science Services Administration (NOAA after 3 Oct 1970)
ETAC	Environmental Technical Applications Center
FAA	Federal Aviation Administration (formerly CAA)
GZMO	German Zonal Meteorological Organization
GMT	Greenwich Mean Time
ID	Identification (cards)
METAF	Meteorological Aviation Routine Weather Report
MF	Meteorological Form
NCC	National Climatic Center (formerly National Weather Records Center (NARC))
NMW	NOAA National Weather Service (formerly WB)
NOAA	National Oceanic and Atmospheric Administration (eff. 3 Oct 1970)
NWS	Naval Weather Service
OSV	Ocean Station Vessel
ROK	Republic of Korea
USAF	United States Air Force
VB	Weather Bureau (changed to NNWS 3 Oct 1970)
VBAN	Weather Bureau - Air Force - Navy
WMO	World Meteorological Organization

## APPENDIX II. Example Input for HEC-5Q Interface

```

TI PROGRAM WEATHER INPUT
TI FOR HEC-5Q OUTPUT OPTION
TI MORGANTOWN WEATHER DATA TEST
C1      85      12      31      86      01      01      0      0
1373685123101---0--00400000000010315005760329060190170540
1373685123104---0--00300000000010308010000029040160150770
1373685123107  0--50600000000010295011540428990160150808
1373685123110---0991060000000010271024760428940380320572
13736851231131800--5150000000000230027760928840480390447
13736851231161400--810000000000021702977032879045038053-
13736851231191000--8050000000001019002534032871040034055-
13736851231220700--8060000000001016602434062866040034052-
13736860101010650--805001000001012203056082855046039053-
1373686010104018812203000400001009804155042848042041096-
13736860101070080--805000400001009804366102848044044096-
13736860101100088--5050000000001010504276102850045044089-
13736860101130120--812000000000010503956102850045042079-
13736860101160168--515000000000012203578092855042039076-
13736860101190230--807000000000014903276092862038035079-
13736860101220180--809000000000015902977082865034032082-

```

## APPENDIX III. Example Input for WQRRS Interface

```

TI PROGRAM WEATHER INPUT
TI FOR WQRRS OUTPUT OPTION
TI MORGANTOWN WEATHER DATA TEST
C1      85      12      31      86      01      01      1      0
1373685123101---0--00400000000010315005760329060190170540
1373685123104---0--00300000000010308010000029040160150770
1373685123107  0--50600000000010295011540428990160150808
1373685123110---0991060000000010271024760428940380320572
13736851231131800--5150000000000230027760928840480390447
13736851231161400--810000000000021702977032879045038053-
13736851231191000--8050000000001019002534032871040034055-
13736851231220700--8060000000001016602434062866040034052-
13736860101010650--805001000001012203056082855046039053-
1373686010104018812203000400001009804155042848042041096-
13736860101070080--805000400001009804366102848044044096-
13736860101100088--5050000000001010504276102850045044089-
13736860101130120--812000000000010503956102850045042079-
13736860101160168--515000000000012203578092855042039076-
13736860101190230--807000000000014903276092862038035079-
13736860101220180--809000000000015902977082865034032082-

```

# APPENDIX IV. Example Output for HEC-5Q Interface

```

10 61010 9 2 9 9 5 510 9 9 5 510 8 7 5101010 6 7101010 710101010 3 6
41010 810 3 9 9 410 110101010 4 5 910 6 4 8 9 2 5 4 8 910 8 9 5 4 9
10 8 5 910 3 5101010 8 5 9 3 0 4 8 4 9 210 710 810 310 1 5 3 5 1 2 8
0 1 2 6 6 0 2 1 6 7 5 3 410101010 5 310 6 8 6 61010 5 0 710 2 71010
8 910 8 6 6 3 7 4 910 3 81010 91010 5 3 3 9 4 3 2 3 5 6 7 5 810 6 4
91010 6 81010 7 0 5 8 710 3 7 8 3 61010 610 9 8 6 5 710 5 2 2 61010
9 9 8 010 8 810 9 7 5 1 1 910101010 8 3 7 7 810 7 4 1 2 0 0 2 5 5 7
9 8 8 7 2 41010 5 3 8 2 0 0 6 7 2 1 0 81010 9 7 5 9 8 3 510 7101010
6101010 5 4 1 8101010 7 2 1 4 0 3 7 9 1 910 8 2 81010 9 7 3 01010 4
4 8 2 9 3 8 9 6 81010 8 4 7 0 3 3 4 3 910 9 9 7 8 910 9 7 6 9 7 7 1
710 8 6 81010 5 0 7 7 9 0 71010 510 3 810 910 9 9 4
5 5 812 6 3 4 811 3 8 8 912 810 9 5 6 81111 410 711 6 910 6 61011 4
8 5 3 910 61111 8 9 612 8 91114 51211 912 9 8 7 7 9 6 7 9 8131011 7
7 7 6101210 6 810 6111112 7 4 8 7 614 7 7 7 610 8 5 9 7 7 5 8 7 6 9
7 5 3 7 5 4 4 4 4 710 6 6 810 8 7 5 4 4 911 8 9 8 8 3 5 5 8 5 4 6 5
6 7 8101110 4 5 6 4 3 4 6 7 3 8 6 5 7 7 5 4 4 3 4 5 7 5 6 7 6 8 4 4
6 4 3 4 4 4 7 4 4 5 6 9 9 7 7 4 3 3 6 4 3 51010 6 7 6 7 5 4 2 5 6 4
7 6 4 2 4 3 6 5 4 5 3 2 3 6 4 6 4 3 3 3 5 5 6 3 3 2 3 4 5 3 3 2 4 4
3 4 6 8 3 3 3 4 3 6 7 3 2 4 5 9 9 5 3 1 3 5 7 7 4 6 6 6 9 3 2 5 7 4
3 4 5 4 2 5 4 6 6 5 7 6 3 4 9 811 5 5 4 6 611 9 5 8 7 9 4 6 7 3 9 6
6 8 7 710 9 9 9 9 4 5 7 6 3 4 61110 5 6 8 9 5 911 8 6 9 8 711 2 6 3
6 7 9 810 4 8 8 6 6 611 6 710111011 6 9 8 9 911 610
31 39 35 14 11 23 36 15 4 12 31 26 39 31 27 31 14 7 20 33 25 17
23 47 40 55 27 22 33 29 30 35 7 22 36 27 22 14 24 24 51 43 39 50
32 54 58 58 57 46 42 57 41 25 46 57 56 51 54 60 58 64 68 68 63 36
40 36 31 36 39 48 39 35 42 36 20 33 56 64 51 35 40 54 52 58 60 47
55 63 55 41 35 47 48 39 48 48 41 36 44 40 33 44 53 64 70 71 75 72
72 73 62 62 67 62 39 36 43 48 52 50 57 45 45 60 67 52 43 48 58 56
48 60 70 69 65 60 45 44 60 65 56 54 56 50 49 57 64 62 65 68 65 62
62 64 63 55 65 69 69 71 72 76 75 76 75 73 69 72 72 61 62 71 72 71
69 70 70 72 74 69 62 66 66 66 67 66 63 67 68 63 75 68 64 68 76 69
67 66 70 75 74 75 75 74 68 69 70 75 75 75 70 66 63 66 68 71 72 69
63 65 68 71 74 74 71 68 68 64 68 70 69 70 70 71 76 78 75 73 72 71
58 61 66 64 65 69 66 58 63 68 70 58 59 67 68 69 65 63 63 65 63 61
59 53 62 59 59 65 66 55 54 54 57 59 61 61 66 66 55 52 50 49 51 52
63 53 63 50 46 40 49 51 44 42 43 52 54 43 35 35 43 45 48 41 43 50
43 35 42 44 30 39 45 39 36 33 34 36 33 40 44 51 38 36 31 30 27 41
56 57 40 21 14 27 25 13 31 28 38 36 21 25 45 39 44 27 33 41 38 34
35 45 45 20 23 29 17 37 31 24 36 21 21 15
27 28 29 5 3 9 20 11 -2 3 27 18 30 18 11 23 5 0 3 28 19 9
13 31 33 45 25 13 24 22 25 30 -6 11 23 22 17 7 16 15 26 30 19 40
15 35 50 44 47 31 27 30 34 13 21 25 32 28 24 30 37 43 50 51 46 17
17 17 19 25 25 31 30 17 22 22 5 18 35 43 40 15 21 26 38 43 43 27
31 50 46 32 29 32 37 20 29 27 20 15 20 23 12 18 22 38 49 49 45 45
46 51 44 41 42 47 24 18 24 27 27 36 37 25 19 31 44 47 31 33 38 49
33 42 56 60 60 54 42 32 43 48 40 41 42 45 45 45 46 52 57 60 61 63
49 42 42 48 52 54 55 56 59 62 63 63 65 62 60 62 64 61 60 61 61 63
64 60 60 62 62 59 54 53 57 57 55 58 60 62 58 57 66 59 51 56 66 64
54 51 54 60 64 65 66 63 53 53 61 65 65 67 64 56 48 50 53 58 64 65
57 56 58 59 62 65 61 61 54 52 56 56 51 54 56 59 63 65 65 66 65 55
43 45 54 58 55 57 55 45 43 54 59 48 43 49 51 54 55 59 58 57 54 57
49 39 40 48 44 58 61 48 45 50 53 55 54 51 52 54 52 48 45 37 38 38
47 26 38 32 30 24 25 41 28 20 23 45 49 28 21 21 20 31 42 26 22 31
20 25 22 23 16 15 30 26 24 21 20 21 19 20 23 25 19 23 19 14 20 28
35 48 35 13 4 11 17 2 20 19 19 32 9 12 24 31 38 10 11 19 26 21
18 27 35 6 5 13 0 15 23 8 24 7 6 0

```

# APPENDIX V. Example Output for WQRRS Interface

WEATH1	75 1 1 0	1.0	52.	50.	28.57	8.
WEATH1	75 1 1 1	1.0	50.	47.	28.57	6.
WEATH1	75 1 1 2	1.0	48.	46.	28.58	5.
WEATH1	75 1 1 3	1.0	47.	44.	28.60	9.
WEATH1	75 1 1 4	1.0	45.	42.	28.60	8.
WEATH1	75 1 1 5	1.0	43.	40.	28.62	9.
WEATH1	75 1 1 6	1.0	42.	40.	28.64	5.
WEATH1	75 1 1 7	1.0	42.	39.	28.65	11.
WEATH1	75 1 1 8	1.0	40.	37.	28.67	8.
WEATH1	75 1 1 9	1.0	40.	37.	28.67	9.
WEATH1	75 1 110	1.0	39.	38.	28.67	13.
WEATH1	75 1 111	1.0	39.	37.	28.66	14.
WEATH1	75 1 112	1.0	39.	36.	28.61	18.
WEATH1	75 1 113	1.0	39.	34.	28.58	11.
WEATH1	75 1 114	1.0	38.	34.	28.60	17.
WEATH1	75 1 115	1.0	37.	31.	28.60	17.
WEATH1	75 1 116	1.0	34.	31.	28.65	14.
WEATH1	75 1 117	0.9	32.	25.	28.69	18.
WEATH1	75 1 118	0.8	32.	24.	28.72	17.
WEATH1	75 1 119	1.0	31.	21.	28.77	17.
WEATH1	75 1 120	1.0	30.	18.	28.82	17.
WEATH1	75 1 121	1.0	29.	18.	28.84	14.
WEATH1	75 1 122	1.0	28.	18.	28.87	13.
WEATH1	75 1 123	1.0	27.	18.	28.91	11.
WEATH1	75 1 2 0	1.0	27.	18.	28.91	13.
WEATH1	75 1 2 1	1.0	27.	17.	28.95	13.
WEATH1	75 1 2 2	1.0	27.	18.	28.98	8.
WEATH1	75 1 2 3	1.0	26.	17.	29.02	10.
WEATH1	75 1 2 4	1.0	27.	17.	29.03	10.
WEATH1	75 1 2 5	1.0	27.	18.	29.04	9.
WEATH1	75 1 2 6	1.0	26.	19.	29.08	5.
WEATH1	75 1 2 7	1.0	27.	20.	29.10	6.
WEATH1	75 1 2 8	1.0	26.	20.	29.13	6.
WEATH1	75 1 2 9	1.0	28.	20.	29.15	4.
WEATH1	75 1 210	1.0	29.	21.	29.17	9.
WEATH1	75 1 211	0.8	30.	23.	29.17	5.
WEATH1	75 1 212	1.0	30.	22.	29.12	5.
WEATH1	75 1 213	0.4	31.	21.	29.08	4.
WEATH1	75 1 214	0.1	32.	21.	29.07	8.
WEATH1	75 1 215	0.2	34.	21.	29.10	9.
WEATH1	75 1 216	0.0	34.	21.	29.10	5.
WEATH1	75 1 217	0.1	32.	20.	29.09	4.
WEATH1	75 1 218	0.0	31.	20.	29.07	0.
WEATH1	75 1 219	0.0	29.	20.	29.06	0.
WEATH1	75 1 220	0.0	27.	21.	29.04	4.
WEATH1	75 1 221	0.0	27.	21.	28.98	5.
WEATH1	75 1 222	0.3	29.	21.	28.92	6.
WEATH1	75 1 223	0.7	29.	21.	28.89	5.
WEATH1	75 1 3 0	1.0	31.	21.	28.84	0.
WEATH1	75 1 3 1	1.0	34.	16.	28.81	9.
WEATH1	75 1 3 2	0.9	33.	21.	28.82	0.
WEATH1	75 1 3 3	1.0	31.	22.	28.79	0.
WEATH1	75 1 3 4	1.0	35.	16.	28.76	5.
WEATH1	75 1 3 5	1.0	30.	27.	28.75	4.

EXHIBIT 5  
THERMAL SIMULATION OF LAKES  
(HEATX and THERMS)



# THERMAL SIMULATION OF LAKES

## USERS MANUAL

PROGRAM NUMBERS

722-F5-E1010

722-F5-E1011

U.S. Army Engineer District, Baltimore  
NOVEMBER 1977

Distributed by U.S. Army Corps of Engineers  
Hydrologic Engineering Center  
December 1980

**THERMAL SIMULATION  
OF LAKES**

**USERS MANUAL**

**PROGRAM NUMBERS**

**722-FS-E1010  
722-FS-E1011**

**U.S. ARMY ENGINEER DISTRICT, BALTIMORE**

**NOVEMBER 1977**

**Distributed by U.S. Army Corps of Engineers  
Hydrologic Engineering Center  
December 1980**

## PREFACE

This computer program description as well as the associated source code were developed by Mr. Earl Eiker formerly of the U.S. Army Engineer District, Baltimore. Since he transferred from the District to the Office of the Chief of Engineers, the Hydrologic Engineering Center has been requested to distribute this program. Several versions of this program presently exist. The version HEC is distributing was obtained from the Ohio River Division. Some recent revisions have been made by HEC.

Extra copies of this publication and/or copies of the source code may be obtained from Ms. Penni Baker by calling (916) 551-1748. Questions regarding its application should be referred to one of the following:

<u>Contact</u>	<u>Office</u>	<u>Commercial</u>
R.G. Willey	HEC	(916) 551-1748
Pete Juhle	Baltimore	(301) 962-4893
Henry Jackson	ORD	(513) 684-3070

## TABLE OF CONTENTS

### TEXT

<u>Section No.</u>	<u>Title</u>	<u>Page</u>
1	Introduction	1
2	Conservation of Heat	1
3	Mathematical Formulation	3
4	Additional Considerations	5
5	Solution Technique	8
6	Computer Program	10
7	Heat Exchange	10
8	Thermal Simulation	10
9	Conclusion	11
10	References	12

### FIGURES

<u>Figure No.</u>	<u>Title</u>
1	Annual Cycle of Heating and Cooling - 1972
2	Lateral Temperature Variation
3	Longitudinal Temperature Profiles
4	Control Volume Representation

### APPENDICES

<u>Appendix</u>	<u>Title</u>
A	Heat Exchange Program
B	Thermal Simulation Program
C	Model Verification Studies

## I N T R O D U C T I O N

When a dam is built across a stream, a totally different regime is established which profoundly affects the water quality within and downstream of the impoundment for many miles. The temperature structure within the reservoir is the most important consideration when establishing a management plan for water quality control.

When a study of reservoir temperatures is undertaken, it is important that all of the physical and meteorological heat exchange processes are included, so that consideration of the overall heat balance of the reservoir is assured. A sound theoretical approach will insure this. The analysis should provide a realistic assessment of the inter-relationship between project operations and the thermal variations within the reservoir. The use of input data which cannot be measured "in situ" should be kept to a minimum in order to insure that possible bias in results is eliminated. Finally, application should be straightforward and follow standard accepted procedures in order to provide confidence and guarantee uniformity in results.

## C O N S E R V A T I O N   O F   H E A T

The simulation of the annual temperature variations within an impoundment begins with the formulation of a mathematical description of the pertinent heat transfer mechanisms. The solution of the mathematical formulation results in an accounting of the external and internal heat balance for the reservoir over the yearly cycle.

The annual temperature cycle of a reservoir is the result of a complex inter-relationship among the many hydrodynamic and thermodynamic processes by which heat enters, is distributed within, and leaves an impoundment. Strictly speaking, the only mathematical descriptions which would be universally applicable would be the three dimensional equations of conservation of heat and mass. However, solution of the three dimensional equations is virtually impossible. There are many instances, though, when the reservoir heat balance can be adequately determined by considering only the vertical distribution of heat and the heat transfer mechanisms associated with movement along the vertical axis. Prototype data are available to support this assumption. The annual temperature cycle for the Beltzville Reservoir in northeastern Pennsylvania is shown on figures 1 through 3. Examination of these figures shows that the assumption of horizontal isotherms (layers of equal temperatures) is indeed valid. Very little variation was measured in either the longitudinal or lateral directions at Beltzville. A large number of Corps reservoirs exhibit this same characteristic

and are readily analyzed by considering heat transfer in only the vertical dimension. It should be emphasized, however, that each impoundment is different and before this simplifying assumption is accepted, it should be scrutinized.

Some general guidance is available on the applicability of the one dimensional assumption to a particular reservoir. Orlob (15) has suggested a method of reservoir classification based on a ratio of inflow volume to storage volume in the reservoir.

1) Low flow/volume ratio. - Reservoirs in this class are extremely large and have detention times greater than one year. Little seasonal variation in storage occurs and outflow is generally from surface layers.

2) Medium flow/volume ratio. - Reservoirs in this class are large and detention times are in the range of from four months to one year. These reservoirs show strong patterns of stratification and variations in storage may be large.

3) High flow/volume ratio. - Reservoirs in this class are generally run of river types with detention times of less than four months. Patterns of stratification are difficult to access and longitudinal variations in temperature are common. Along with these longitudinal temperature variations, conditions of underflow may develop.

Reservoirs in the first and second class can be expected to exhibit a strong pattern of thermal stratification. In order to mathematically evaluate the applicability of the one dimensional assumption, Orlob (11) suggests the use of a densimetric Froude number computed as follows:

$$F_D = \frac{LQ}{HV} \sqrt{\frac{1}{g e}} \quad (1)$$

where:

$F_D$  = densimetric Froude number

$L$  = length of the reservoir in ft. @ conservation pool

$H$  = mean reservoir depth in ft.

$V$  = volume of the reservoir in ft.<sup>3</sup> @ conservation pool

$Q$  = flow through rate in cfs (check mean annual and spring mean monthly)

$g$  = gravitational constant 32.2 ft/sec<sup>2</sup>

$e$  = average normalized density gradient taken as  $0.3 \times 10^{-6}/\text{ft.}$

According to this theory, if the computed value of  $F_D$  is less than  $1/\pi$  a strong stratification pattern will exist in the reservoir.

### MATHEMATICAL FORMULATION

Several approaches to the simulation of reservoir temperatures have been utilized by various Corps offices (2, 11, 16). These methods have been analyzed by Eiker (6) and each was determined to be lacking in one or more areas. The simulation approach outlined below was developed by the **Baltimore** District and has been applied in several analyses of existing and proposed reservoirs. The basis of the analysis is the simultaneous solution of the time varying, one-dimensional equations for conservation of heat and conservation of mass.

The equations describing conservation of heat and mass for the reservoir are derived in the classical manner. The reservoir is idealized and a control volume is established as shown on figure 4. The control volume is of thickness ( $\Delta Z$ ) and has an average area ( $A$ ) which is a function of elevation  $Z$ . Conservation of mass for the control volume is described by:

$$\frac{\partial Q_v}{\partial Z} = \frac{Q_{in} - Q_{out}}{\Delta Z} \quad (2)$$

where:

$\frac{\partial Q_v}{\partial Z}$  = change in vertical flow per unit between the bottom and top of the control volume in cfs/ft.

$Q_{in}$  = inflow to the control volume in cfs.

$Q_{out}$  = outflow from the control volume in cfs.

$\Delta Z$  = thickness of control volume in ft.

The equation to describe the conservation of heat within the control volume is:

$$\frac{\partial T}{\partial t} + \frac{1}{A} \frac{\partial (Q_v \cdot T)}{\partial Z} = \frac{1}{A} \frac{\partial}{\partial Z} K A \frac{\partial T}{\partial Z} + \frac{T_{in} Q_{in}}{A \cdot \Delta Z} - \frac{T_{out} Q_{out}}{A \cdot \Delta Z} + \frac{1}{\rho C_p A} \cdot \frac{\partial H}{\partial Z} \quad (3)$$

where:

$T$  = temperature in  $^{\circ}F$ .

$t$  = time in sec.

$A$  = horizontal area of the control volume in  $\text{ft}^2$   
 $Q_v$  = vertical flow in cfs.  
 $Z$  = elevation in ft.  
 $K$  = diffusion coefficient (molecular and turbulent) in  $\text{ft}^2/\text{sec}$ .  
 $T_{in}$  = temperature of inflow in  $^{\circ}\text{F}$ .  
 $Q_{in}$  = inflow to the control volume in cfs.  
 $T_{out}$  = temperature of outflow =  $T$  in  $^{\circ}\text{F}$ .  
 $Q_{out}$  = outflow from the control volume in cfs.  
 $\rho$  = density of water in  $\text{LBS}/\text{ft}^3$   
 $C_p$  = specific heat of water in  $\text{BTU}/\text{LBS}/^{\circ}\text{F}$ .  
 $\partial H/\partial Z$  = external heat source in  $\text{BTU}/\text{sec}$ .

An examination of equation (3) confirms that all of the pertinent heat transfer mechanisms are included in the formulation. The first term on the left hand side of the equation represents the change in temperature with respect to time. The second term on the left hand side of the equation accounts for the vertical transfer of head due to advective processes. The first term on the right side of equation (3) is the measure of heat transfer related to diffusion. The remaining three terms account for the external heat balance of the reservoir, that is, inflow, outflow, and interfacial heat transfer. Heat transfer at the solid boundaries, if significant, may be included with an additional term having the same form as the external heat source term.

The next step in the simulation is to incorporate the conservation of mass equation into the conservation of heat equation. This is accomplished by expanding the second term (vertical advection) by the product rule and substituting equation (2) into the result as follows:

$$\frac{1}{A} \frac{\partial(Q_v \cdot T)}{\partial Z} = \frac{1}{A} \left[ Q_v \frac{\partial T}{\partial Z} + \frac{T(Q_{in} - Q_{out})}{\Delta Z} \right] \quad (4)$$

Now, when equation (4) is substituted back into equation (3) and simplified the result is:



$$\frac{\partial T}{\partial t} + \frac{Qv}{A} \frac{\partial T}{\partial z} = \frac{1}{A} \frac{\partial}{\partial z} KA \frac{\partial T}{\partial z} + \frac{Q_{in}(T_{in} - T)}{A \cdot \Delta z} + \frac{1}{\rho C A} \frac{\partial H}{\partial z} \quad (5)$$

#### ADDITIONAL CONSIDERATIONS

Before proceeding with the solution of equation (5), functional descriptions for the inflow-outflow relationship, diffusion processes and the external heat source term must be developed.

The vertical outflow distribution used in the model is developed, based on methods presented in WES reports (3, 8). These methods enable an accurate prediction of the vertical variation in outflow to be made for either a weir or an orifice type outlet. The velocity distribution is first computed using the WES procedures. The outflow per foot is then developed by multiplying the velocity at each elevation by the reservoir width. A complete explanation of the application is contained in the above references.

When inflow enters a reservoir it tends to seek residence at a depth of similar temperature (density). Velocity measurements of inflows at Fontana Reservoir, taken by Elder and Wunderlich (7), show that there is a vertical distribution of inflow. This distribution is approximately parabolic and is centered about the elevation where reservoir temperature is equal to inflow temperature. The vertical limits of the inflow distribution are dependent upon the quantity of flow and the degree of thermal stratification existing in the reservoir pool. Orlob (11) has suggested a method for determining the vertical limits of the inflow distribution as a function of densimetric Froude number following Debler's criteria. This relationship is as follows:

$$D = 2.88 \left[ \frac{Q}{W \sqrt{gE}} \right]^{1/2} \quad (6)$$

where:

D = thickness of the inflow distribution in ft.

Q = inflow in cfs.

W = reservoir width in ft.

g = gravitational constant = 32.2 ft/sec<sup>2</sup>

E = stability =  $\frac{1}{\rho} \frac{d\rho}{dz}$

The model uses equation (6) to estimate the thickness of the inflowing layer, fits a parabolic distribution of inflow velocity between the limits and centers this distribution about the point of corresponding density of inflow and reservoir water. If the reservoir surface or bottom restricts the distribution, the center-line is moved up or down as required and the thickness of the inflowing water is kept constant. The inflow quantity distribution is next computed by multiplying the computed velocity distribution by the reservoir width at each elevation. Some mixing of the reservoir inflow occurs as it enters the pool. Based on model studies conducted at WES, this phenomenon is handled by assuming a quantity of water from the top layer of the reservoir is entrained and mixed with the inflow current. A modified volume and volume-weighted temperature for the inflow is computed, based on the assumed quantity of entrainment, prior to placement within the reservoir.

Now, with a knowledge of the inflow and outflow distributions at any point in time, the vertical flows ( $Q_v$ ) at any elevation are uniquely established. The relationship may be written as:

$$Q_v (Z) = \int_{Z_0}^Z [Q_{in} (Z) - Q_{out} (Z)] \cdot dZ \quad (7)$$

where:

- $Q_v (Z)$  = vertical flow at elevation  $Z$  in cfs.
- $Z_0$  = elevation of reservoir bottom in ft.
- $Q_{in} (Z)$  = inflow of distribution function in cfs/ft.
- $Q_{out} (Z)$  = outflow distribution function in cfs/ft.

Relating equation (7) to the control volume the net vertical flow through the control volume ( $Q_v$ ) is evaluated as:

$$Q_v = Q_v (Z + \Delta Z) - Q_v (Z) \quad (8)$$

The external heat sources that are considered in the model are the seven heat exchange processes which operate at the air-water interface and may be written as:

$$H_n = H_s - H_{sr} + H_a - H_{ar} \pm H_c - H_{br} - H_e \quad (9)$$

where:

- $H_n$  = the net heat transfer in BTU/ft<sup>2</sup>/DAY
- $H_s$  = the short wave solar radiation arriving at the water surface in BTU/ft<sup>2</sup>/DAY.
- $H_{sr}$  = the reflected short wave radiation in BTU/ft<sup>2</sup>/DAY.

$H_a$  = the long wave atmospheric radiation in BTU/ft<sup>2</sup>/DAY.

$H_{ar}$  = the reflected long wave radiation in BTU/ft<sup>2</sup>/DAY.

$H_c$  = the heat transfer due to conduction in BTU/ft<sup>2</sup>/DAY.

$H_{br}$  = the back radiation from the water surface in BTU/ft<sup>2</sup>/DAY.

$H_e$  = the heat loss due to evaporation in BTU/ft<sup>2</sup>/DAY.

Complete discussions of the individual terms have been presented by Anderson (1) and in Tennessee Valley Authority report No. 14 (14). All of the heat transfer mechanisms at the water surface, with the exception of short wave solar radiation, affect only the top one or two feet of the reservoir. Short wave radiation, however, penetrates the water surface and may affect water temperatures at great depths. This depth of penetration varies from reservoir to reservoir and is a function of absorption and scattering properties of the water (9).

The method used in the model to evaluate the net rate of heat transfer at the air-water interface has been developed by Edinger and Geyer (5). Their method utilized the concepts of equilibrium temperature and coefficient of surface heat exchange. The equilibrium temperature may be defined as that water temperature at which the net rate of heat exchange between a water surface and the atmosphere will be zero. The coefficient of surface heat exchange is the rate at which the heat transfer process will proceed. The equation to describe this relationship may be written as follows:

$$H_n = K_e (T_e - T_s) \quad (10)$$

where:

$H_n$  = the net rate of heat transfer in BTU/ft<sup>2</sup>/TIME.

$K_e$  = the coefficient of surface heat exchange in BTU/ft<sup>2</sup>/TIME.

$T_e$  = the equilibrium temperature in °F.

$T_s$  = the surface temperature in °F.

Computation of  $T_e$ 's and  $K_e$ 's is dependent solely on meteorological variables and is outlined in the literature (5).

The evaluation of the external heat source term is completed by establishing a relationship for the heating effects of short wave solar radiation penetration. Based on laboratory and analytical studies, Dake and Harlemen (4) have developed an equation to describe the distribution of heat input due to solar radiation penetration below the water surface. Their approach is based on a surface absorption of the longer wave lengths of radiation and an exponential decay with depth for the remaining wave lengths of radiation. The equation to describe this exponential decay is:

$$\phi(Z) = (1 - \beta) \phi_0 e^{-\lambda Z} \quad (11)$$

where:

$\phi(Z)$  = the quantity of radiation arriving at a horizontal plane ( $Z$  feet below the water surface) in BTU.

$\beta$  = the fraction of radiation absorbed by the top 2 feet of water in the reservoir.

$\phi_0$  = total incoming radiation in BTU.

$\lambda$  = the average absorption coefficient of the water in  $\text{ft}^{-1}$

$Z$  = depth below the water surface in ft.

Guidance in the selection of  $\beta$  and  $\lambda$  is provided by Dake and Harlemen and also in TVA Report No. 14 (14).

The final and perhaps the most difficult consideration to be made is with regard to the diffusion term. At this time, there is no adequate functional representation by which the variations over time and space in the diffusion coefficient ( $K$ ) can be computed "a priori". The approach used in the model follows the arguments of Dake and Harleman and Stefan and Ford (13). That is, diffusion of heat in the epilimnion is handled indirectly by a combination of wind induced and convective mixing processes. In the model a coefficient may be used to increase or decrease wind speed effects due to fetch length, sheltering and water surface roughness (see App. B). The result of this procedure is the computation of a uniformly mixed epilimnion. Diffusion in the hypolimnion is considered constant and may be assumed as equal to molecular diffusion in the absence of better data.

#### SOLUTION TECHNIQUE

Analytical solutions of equation (5) have been accomplished, but their practical application is restricted. Numerical methods are the

the only means by which a workable solution to equation (5) may be obtained. The numerical technique used in the model is of the implicit type. The solution requires the stipulation of an initial condition and two boundary conditions. The initial condition may be taken as isothermal at some time during the spring. The lower boundary condition used in the model assumes no heat is transferred across the bottom boundary. The upper boundary condition assumes the heat exchange at the reservoir surface is equal to the net heat transfer at the air-water interface minus the quantity of heat attributable to the short wave solar radiation that penetrates into the water body. The mechanics of the solution are carried out by beginning from a known or assumed initial condition and stepping forward in time, using constant increments for hydrologic and meteorologic input.

In order to effect the solution, the reservoir is first segmented into a finite number of layers along the vertical axis. These layers may be thought of as a number of control volumes stacked vertically between the reservoir bottom and the surface. Each element has a thickness of  $\Delta Z$  and an average horizontal area dependent on the reservoir elevation-area relationship. Heat and mass balances are next developed for each layer using central differences to approximate the derivatives in equation (5). The differences are substituted into equation (5) and a difference equation is developed for each layer. The resulting equations have the following general form:

$$\{A_{i+1}, t+1\} T_{i+1} + \{A_i, t+1\} T_i + \{A_{i-1}, t+1\} T_{i+1} = T_{i, t} + A_v + E_x \quad (12)$$

where:

$A_{i, t+1}$  = coefficient describing internal mixing processes

$T_i$  = temperature of each layer at time  $t+1$

$T_{i, t}$  = temperature of each layer at time  $t$

$A_v$  = temperature rise in layer  $i$  due to inflow

$E_x$  = temperature rise in layer  $i$  due to external heat sources.

When equation (12) is written for each layer, there results  $N$  equations (one for each layer) in  $N$  unknowns. In matrix notation, the equations are written:

$$\begin{bmatrix} A_{ij} \end{bmatrix} \begin{bmatrix} T_j \end{bmatrix} = \begin{bmatrix} C_j \end{bmatrix} \quad (13)$$

where:

$$\begin{aligned} \begin{bmatrix} A_{ij} \end{bmatrix} &= \text{a tri-diagonal matrix of coefficients} \\ \begin{bmatrix} T_j \end{bmatrix} &= \text{a column matrix of temperatures at time } t+1 \\ \begin{bmatrix} C_j \end{bmatrix} &= \text{a column matrix of terms on the right side of equation (12).} \end{aligned}$$

Equation (13) is solved and the result is the temperature profile at time  $t+1$ . A more complete discussion of the numerical technique is presented by Keller (10).

#### COMPUTER PROGRAM

The simulation of reservoir temperatures as described above is accomplished by use of computer programs 722-F5-E1010, Heat Exchange Program and 722-F5-E1011, Thermal Simulation Program. The Heat Exchange Program assembles the meteorologic data needed to describe the interfacial heat exchange mechanism. The program then performs the necessary calculations to determine the climatologic input to the reservoir heat balance. The output from the first program is then used as a portion of the input for actual thermal modeling of the impoundment.

#### HEAT EXCHANGE

The Heat Exchange Program performs all the computations necessary to determine the net rate of heat exchange at the air-water interface. Computations to determine Equilibrium Temperature and Coefficients of Surface Heat Exchange are carried out using the methods of Edinger and Geyer (5), which have been discussed previously. In addition, if no measured values of short wave solar radiation are available the appropriate computations are made, using methods presented in TVA report No. 14 (14). Input to the program consists of measured values of cloud cover, wet and dry bulb temperatures, and wind speed. Also, physical characteristics such as latitude and longitude, and site elevation are furnished. Details of the program including a flow chart, variable definitions, input description and sample output are contained in Appendix A.

#### THERMAL SIMULATION

The Thermal Simulation Program takes the required hydrologic and meteorologic data, assembles it, and performs the calculations necessary to determine the annual temperature cycle for the reservoir under study.

The computations are made, based on methods and assumptions discussed previously. Input requirements of the model may be divided into four categories as site characterization, hydrologic, meteorologic, and water temperature data. Site characterization data are composed of reservoir width-elevation and area-elevation tables for the reservoir, project latitude and longitude, and site elevation. The hydrologic input requirements are daily average reservoir inflow and outflow, and daily pool elevation of the impoundment. Meteorologic data consists of mean daily values of Equilibrium Temperature, wind speed, Coefficient of Surface Heat Exchange and short wave solar radiation from the Heat Exchange Program. Input data for water temperature consists of daily average values of inflow water temperature and the temperature objective of release water. The geometric configuration of the outlet structure is required with reference to the location of various levels available for withdrawal. Details of the program including a flow chart, variable definitions, input description and sample output are contained in Appendix B.

#### CONCLUSION

A mathematical model capable of reservoir temperature prediction that is relatively easy to use has been presented. Consideration has been given to maintaining an accurate representation of the physical characteristics of the reservoir under study while adhering to the principles of conservation of heat and mass. Results of model verification studies are included in Appendix C. It is felt that the model presented offers the best combination of approaches to separate phases of the total problem that have been studied by various investigators.


## REFERENCES

1. Anderson, E. R., Energy budget studies, "Water Loss Investigations: Lake Hefner Studies", Tech. Rept., Proj. Paper 269, eol. Survey, U.S. Dept. of Interior, Washington, D. C., 1954.
2. Beard, L. R., and Willey, R. G., "An Approach to Reservoir Temperature Analysis", Tech. Paper No. 21, Hydrologic Engineering Research Center, Corps of Engineers, Davis, California, 1970.
3. Bohan, J. P. and Grace, J. L., "Selective Withdrawal from Man-made Lakes," Technical Report H-73-4, U.S. Army Engineer Waterways Experiment Station, Corps of Engineers, Vicksburg, Miss., March 1973.
4. Dake, J. M. K. and Harleman, D. R. F., "An Analytical and Experimental Investigation of Thermal Stratification in Lakes and Ponds", Hydrodynamics Laboratory Rept. No. 99, Mass. Inst. of Technology, Cambridge, Mass.
5. Edinger, J. E. and Geyer, J. C., "Heat Exchange in the Environment", Dept. of Sanitary Engineering and Water Resources, Research Project No. 49, The Johns Hopkins University, Baltimore, Maryland, June 1, 1965.
6. Eiker, E. E., "An Evaluation of Reservoir Temperature Prediction Methods," paper presented at seminar on Hydrologic Aspects of Project Planning, HEC, Davis, California, March, 1972.
7. Elder, R. A. and Wunderlich, W. O. , "Evaluation of Fontana Reservoir Field Measurements," Proceedings, 6th Annual Sanitary and Water Resources Conference, Vanderbilt University, 1967.
8. Grace, J. L., "Selective Withdrawal Characteristics of Weirs," Tech. Report H-71-4, U. S. Army Waterways Experiment Station, Corps of Engineers, Vicksburg, Miss. June 1971.
9. Hutchinson, G. E., "A Treatise on Limnology", Volume I, Geography, Physics and Chemistry, John Wiley and Sons, Inc., New York, 1957.
10. Keller, Herbert B., "The Numerical Solution of Parabolic Partial Differential Equations", Chapter No. 12, "Mathematical Methods for Digital Computers," Ed. by Ralston, A. and Wilf, H. S., John Wiley and Sons, Inc., New York, N. Y., 1967.
11. Orlob, G. T., Mathematical Models for Prediction of Thermal Energy Changes in Impoundments," Final Report for FWQA by W.R.E., Inc., Walnut Creek, California, Dec. 1969.



12. Orlob, G. T., and Selna, L. G., "Prediction of Thermal Energy Distributions in Deep Reservoirs," Proceedings, 6th Annual Sanitary and Water Resources Engineering Conference, Vanderbilt University, 1967.
13. Stefan, H. and Ford, D.E., "Temperature Dynamics in Dimictic Lakes," Journal of the Hydraulics Division, Vol. 101, No. HY1, Proc. Paper. 11058, January 1975m pp 97-114.
14. Tennessee Valley Authority, Division of Water Control Planning, Engineering Laboratory, "Heat and Mass Transfer Between a Water Surface and The Atmosphere", Water Resources Research, Lab. Rept. No. 14, Norris Tennessee, July 1967, rev. May 1970.
15. Training Course, Number 27, Water Quality Management, HEC, Davis, California, March 1970.
16. Wunderlich, W. O. and Elder, R. A., "The Influence of Reservoir Hydrodynamics on Water Quality", Proceedings, 6th Annual Sanitary and Water Resources Engineering Conference, Vanderbilt University, 1967.






NOTES:  
 1. STATION 1 IS LOCATED APPROXIMATELY 100 YARDS UPSTREAM OF INTAKE TOWER ALONG CENTER LINE OF LAKE.  
 2. STATIONS IN AND IS ARE APPROXIMATELY 100 YARDS NORTH AND SOUTH OF STATION I ON A LINE PERPENDICULAR TO CENTER-LINE OF LAKE.

LEHIGH RIVER BASIN  
 POMOPOCO CREEK PENNSYLVANIA  
 BELTZVILLE LAKE  
 LATERAL TEMPERATURE VARIATION  
 31 AUGUST 1972

FIGURE 2

10 AUGUST 1972



- NOTES:
1. ALL STATIONS ALONG CENTER LINE OF LAKE.
  2. STATION 1 IS APPROXIMATELY 200 YARDS ABOVE TOWER.
  3. STATION 3 IS APPROXIMATELY 1.3 MILES ABOVE TOWER.
  4. STATION 5 IS APPROXIMATELY 2.3 MILES ABOVE TOWER.
  5. STATION 8 IS APPROXIMATELY 4.2 MILES ABOVE TOWER.
  6. STATION 10 IS APPROXIMATELY 6.0 MILES ABOVE TOWER.

LEMOH RIVER BASIN  
POHOPOCO CREEK PENNSYLVANIA  
BELLEVILLE LAKE

LONGITUDINAL TEMPERATURE PROFILES

FIGURE 3

# CONTROL VOLUME REPRESENTATION




FIGURE 4

A P P E N D I X A

HEAT EXCHANGE PROGRAM

722-F5-E1010


APPENDIX A  
HEAT EXCHANGE PROGRAM

TABLE OF CONTENTS

1. Program Abstract
2. Flow Chart
3. Definition of Variables
4. Input Description
5. Input Set Up
6. Table of Values for RFG
7. Sample Input
8. Sample Output

ELECTRONIC COMPUTER PROGRAM ABSTRACT			
TITLE OF PROGRAM		PROGRAM NO.	
Heat Exchange Program		722-F5-E1010	
PREPARING AGENCY Water Quality Section, Engineering Division, U.S.A.E.D. Baltimore District, P.O. Box 1715, Baltimore, Md. 21203			
AUTHOR(S)	DATE PROGRAM COMPLETED	STATUS OF PROGRAM	
Earl E. Eiker	Dec. 1972	PHASE Revised	STAGE Nov. 1977
<b>A. PURPOSE OF PROGRAM</b> To analyze the day to day variations in meteorologic variables at a given location and using these variables to compute Equilibrium Temperatures and Coefficients of Surface Heat Exchange for use in estimating net heat exchange between a water surface and the atmosphere.			
<b>B. PROGRAM SPECIFICATIONS</b> 1. Language - Fortran IV 2. Input - card only 3. Output- printer and punched card at users option 4. Size of Program - 8500 words 5. External storage - none 6. Restrictions - none			
<b>C. METHODS</b> Reference: Edinger, J. E. and Geyer, J. C., "Heat Exchange in the Environment" Dept. of Sanitary Engineering, Research Project no. 49, The Johns Hopkins University, Baltimore, Md., June 1965.			
<b>D. EQUIPMENT DETAILS</b> Program is written for the Univac 1108 computer but can be adapted to comparable system. Normal configuration of reader/punch and printer required. Program is written for batch mode of time share operation.			
<b>E. INPUT-OUTPUT</b> Input consists of physical data to describe the site and mean daily values of air temperature, wet bulb temperature, wind speed and cloud cover. Output consists of computed values of Equilibrium Temperature and Coefficients of Surface Heat Exchange for any time period from one hour to one day. Punched card output is compatible with input requirements of program no. 722-F5-E1011, "Thermal Simulation Program."			
<b>F. ADDITIONAL REMARKS</b> Complete documentation is available from The Hydrologic Engineering Center. Source deck available upon request.			





APPENDIX A.2  
FLOW CHART

**HEAT  
EXCHANGE  
PROGRAM**  
APPENDIX A.2

Appendix A.3  
HEAT EXCHANGE PROGRAM  
DEFINITION OF VARIABLES

Variables

AL	Constant in S.W. radiation computation.
All	Constant in S.W. radiation computation.
AEV	Constant in wind speed equation.
AIRT (365)	Average daily air temperature in °F.
AMASS	Optical air mass, dimensionless.
AMP	Amplitude of Equilibrium Temperature variation.
BEV	Constant in wind speed equation.
BOTEL	Project elevation in ft. above msl.
CBR	Constant in Bowen Ratio.
CL	Cloud cover function.
CLOUD (365)	Average daily cloud cover in tenths.
DEC	Declination of sun in radians.
DEWT (365)	Average daily dew point temperature in °F.
DSTL	Time difference between local and standard meridians in hrs.
DUST	Constant in S.W. radiation computation.
EA	Atmospheric vapor pressure in inches of Hg.
EK (365)	Coefficient of Surface Heat Exchange in BTU/FT <sup>2</sup> /DAY/°F.
ES	Saturation vapor pressure in inches of Hg.
ETEMP (365)	Equilibrium Temperature in °F.
ETEMP1	Initial Equilibrium Temperature (IDAY) in °F.
FWIND	Wind speed equation.
HA	Atmospheric radiation in BTU/FT <sup>2</sup> /DAY.
HAB	Hour angle at beginning of time period in radians.
HAE	Hour angle at end of time period in radians.
HAN	Net atmospheric radiation in BTU/FT <sup>2</sup> /DAY.
HHS (24)	Hourly solar radiation (hemispheric) in BTU/FT <sup>2</sup> /HR.
HR	Absorbed radiation in BTU/FT <sup>2</sup> /DAY.
HSD (365)	Daily solar radiation in BTU/FT <sup>2</sup> /DAY.
HSDAY	Daily solar radiation in BTU/FT <sup>2</sup> /DAY.
HSN (24)	Hourly solar radiation at site in BTU/FT <sup>2</sup> /HR.
IDAY	First day of computation (Julian).
IPNCH	Eq. 2 if punched card output desired, Eq. 1 otherwise.
ISW	Eq. 1 if S.W. radiation is furnished, Eq. 2 otherwise.
LDAY	Last day of computation (Julian).
NDAY	Day number for computations.
NLAST	Number of bits of meteorologic data furnished.
NPER	Length of one period in hours.
NSW	Number of bits of S.W. data furnished.
PETEMP (24)	Period Equilibrium Temperature in °F.
PHI	Latitude of project in radians.

PHHS (24)	Period solar radiation (hemispheric) in BTU/FT <sup>2</sup> /PERIOD.
PHSN (24)	Period solar radiation (net) in BTU/FT <sup>2</sup> /PERIOD.
RATIO	Relative distance between earth and sun.
RFA	Water surface reflection of atmospheric radiation in hundredths.
RFG	Reflectivity of ground in hundredths.
RFS	Water surface reflection of S.W. radiation in hundredths.
SGDAY	Mean daily solar radiation (hemispheric) in BTU/FT <sup>2</sup> /DAY.
SIG	Stefan-Boltzmann constant.
SLOPE	Slope of temperature vs. saturation vapor pressure curve.
STR	Standard time of sunrise in hours.
STS	Standard time of sunset in hours.
SW (365)	Daily solar radiation in BTU/FT <sup>2</sup> /DAY.
TABS	Absolute temperature - 460 °F.
TIME	Time of day in hours.
WAT	Mean daily precipitable water content in CM.
WIND (365)	Mean daily wind speed in knots.
XDAY	Day number for computations.
XLAT	Latitude of project in degrees.
XLONG	Longitude of project in degrees.
XPER	Length of time period in hours.
XXLONG	Longitude of standard meridian in degrees.

#### WORKING VARIABLES

AL, ALF, ALT, AN, B, ETRY (3), KE, KNT, LE, M, NEX, SIGN, ST, STT, SUMH, SUMQ, X1, X2, X3, XI, XM, XTEM, XX, Y1, Y2, Y3, YM.

Appendix A.4  
HEAT EXCHANGE PROGRAM  
Input Description

Card No.

- 1           FORMAT (2I10)
- NDATA - Number of jobs to be run  
          IHCJ - Output format; 0 for printer, 1 for LARM model input file,  
              -1 for HEC-5Q input file, -2 for WQRRS input file
- 2           FORMAT (20A4)   Job title - one card.
- 3           FORMAT (8F10.0)
- ADDC - constant to be added to cloud cover (default=0)  
          ADDW - constant to be added to wind speed (default=0)  
          ADDT - constant to be added to dry bulb temperature  
              (default=0)  
          ADDD - constant to be added to dew point temperature  
              (default=0)  
          CMULT - factor to be multiplied times cloud cover  
              (default=1)  
          WMULT - factor to be multiplied times wind speed  
              (default=1)  
          TMULT - factor to be multiplied times dry bulb temperature  
              (default=1)  
          DMULT - factor to be multiplied times dew point temperature  
              (default=1)
- 4           FORMAT (6I10)
- NLAST - Number of bits (e.g., days) of meteorological  
              data furnished. Usually 365.  
          ISW - Equals 1 if short wave radiation furnished, equals 2  
              otherwise.  
          NSW - Number of bits of short wave data furnished.  
          IDAY - First day of computation. Usually one.  
          LDAY - Last day of computation. Usually 365.  
          IPNCH - Equals 2 if punched card output desired, equals  
              1 otherwise.
- 5           FORMAT (2F10.2)
- ETEMP1 - Estimated initial Equilibrium Temperature in  
              °F. Usually use air temperature.  
          XPER - Length of computation period and output  
              interval for solar radiation only. Usually 24.

- 6           **FORMAT (4F10.2)**
- AEV - Evaporation formula constant (0 for daily data).
  - BEV - Evaporation formula constant (426 for daily data from Lake Colorado City Studies).
  - RFS - Reflected S.W. radiation in hundredths. Only used if ISW equals 1. (0.05 from Lake Hefner Studies).
  - RFA - Reflected long wave radiation in hundredths (0.03 from Lake Hefner Studies).
- 7           **FORMAT (4F10.2) - omit this card if card 12 is used.**
- BOTEL - Elevation of project in feet above sea level.
  - XLAT - Latitude of project in degrees.
  - XLONG - Longitude of project in degrees.
  - RFG - Reflectivity of ground surrounding the lake. This variable effects refluted solar radiation into the lake. See table on Appendix A.6.
- 8           **FORMAT (12X, 34F2.0)**
- CLOUD           (NLAST) - Mean daily cloud cover in tenths.
- 9           **FORMAT (12X, 34F2.0)**
- WIND (NLAST) - Mean daily wind speed in knots. Can be used in m.p.h. if WMULT on card 3 is equal to 0.8684.
- 10           **FORMAT (12X, 22F3.0)**
- AIRT (NLAST) - Mean daily air temperature in °F.
- 11           **FORMAT (12X, 22F3.0)**
- DEWT (NLAST) - Mean daily dew point temperature in °F.
- 12           **FORMAT (12X, 11F6.1) - OPTIONAL**
- SW (NLAST) - Total daily short wave solar radiation in Langleys/day.
- 13           **FORMAT (12X, 13F5.0) - OPTIONAL**
- BP(NLAST) - Barometric pressure needed if output is for WQRRS model.  
(Card 1.2 is -2)

## INPUT SET UP

## Appendix A.5

Appendix A.6  
HEAT EXCHANGE PROGRAM  
Table of Values for RFG

Meadows and fields	0.14*
Leave and needle forest	0.07 - 0.09*
Dark, extended mixed forest	0.045*
Heath	0.10*
Flat ground, grass covered	0.25 - 0.33
Flat ground, rock	0.12 - 0.15
Sand	0.18
Vegetation early summer, leaves with high water content	0.19
Vegetation late summer, leaves with low water content	0.29
Fresh Snow	0.83
Old Snow	0.42 - 0.70

\*May be too low

Reference:

Tennessee Valley Authority, Division of Water Control Planning, Engineering Laboratory, "Heat and Mass Transfer Between a Water Surface and The Atmosphere," Water Resources Research, Lab. Rept. No. 14, Norris, Tennessee, July 1967, Rev. May 1970.

APPENDIX A.7  
HEAT EXCHANGE PROGRAM  
SAMPLE INPUT

1	1	1974 CHARLESTON / SUTTON LAKE, W. VA. AIR X DEW = 2.5 DEG. F
2	0	0 -2.5 -2.5 1 1 1
3	0	
4	365	2 10 1 365 2
5	33.	24.
6	0.	426. 0. 0.03
7	925.	38.661 80.694 0.25
8*	101	10 4101010101010101010 8 810 710 6 610 710 610101010 710 8 3 2 71010
	102	10 6101010 9 9 4 0 910 010 110 7 9 710 3 5 8 11010 51010101010 8 7 9
	103	91010 1 31010 9 910 710 0 7 8 5 71010 8 8 810 3 91010 6 910 8 3 910
	104	9 810 2 8 7 7 01010 6 8 6 2 5 8 3 5 810 9 810 5 510 7 6 7 8 6 0 9 2
	105	10 7 8 3 4 9 8 8 710 2 810101010 7 210 8 6 4 8 1 6 5 3 4 4 9 7 7 4 8
	106	8 91010 8 9 8 910 7 6 6 1 1 31010 7 81010 8 9 6 1 9 6 4 710 7 3 610
	107	8 910 6 7 8 8 3 3 810 71010 7 7 9101010 8 1 2 7 710 5 8 4 3 4 5 8 7
	108	6 9 9101010101010 5 41010101010 7 9 910 7 9 7 4 11010 7 3 2 8 3 7 710
	109	1 1 7 4 2 0 010 4 2 0 010 9 91010 010 710 0 0 4101010 0 010 9 5 7 6
	110	10 9 9 610 6 3 9 9 9 710 2 6 51010 710 7 0 810 4 5 0 7101010 310 0 2
	111	1010 9 0101010 910 9101010 7 8 3 610 9 51010 910 9
	201	6 6 3 6 3 5 7 5 6 4 8 7 4 61010 8 6 7 6 8 3 6 4 3 412 8 3 210 4 7 5
	202	9 4 6 9 6 6 9 9 8 6 6 5 4 9 3 9 7 716 9 510 7 6 9 5 71010 9 4 5 4 8
	203	8 6 7 7 2 61314 8 6 5 9 4 3 8 5 7 2 4 810 9 8 6 9 910 9 5 7 8 4 5 7
	204	7 911 5 4 5 6 2 61011 8 4 3 2 5 7 9 6 8 9 4 6 7 3 5 8 3 4 6 8 5 7 4
9*	205	6 5 1 3 4 5 4 6 5 4 3 3 7 5 7 5 3 3 5 6 4 7 5 3 9 7 4 2 3 9 7 5 5 6
	206	7 8 6 5 5 4 3 4 4 4 8 6 3 5 5 4 3 3 1 1 6 3 2 3 4 4 2 2 4 7 3 3 3 5
	207	4 3 2 2 2 7 5 3 1 4 6 6 2 3 2 3 3 3 3 4 3 2 3 3 5 2 4 3 4 3 3 2 1 1
	208	4 2 6 8 4 4 4 6 7 4 4 1 2 2 0 3 5 6 4 4 2 3 4 3 3 4 6 4 4 7 3 3 410
	209	9 5 5 3 3 3 1 2 2 1 2 1 1 1 6 6 4 7 4 5 4 1 3 3 2 6 3 0 0 3 3 0 2 3
	210	3 7 9 4 4 1 1 2 6 81110 9 3 6 1 41011 5 3 7 8 3 7 8 4 7 6 8 9 4 2 2
	211	5 7 8 4 2 4 2 3 7 6 6 7 9 1 6 5 8 5 8 3 3 3 2 5 5
	301	30 31 35 30 31 33 33 30 42 44 42 24 23 39 50 56 56 59 60 61 53 52
	302	51 37 39 51 62 49 45 44 50 41 49 34 27 23 41 37 25 22 28 30 43 51
	303	40 35 40 37 40 50 38 45 52 37 34 21 26 37 47 46 59 68 71 58 52 68
	304	67 69 55 43 43 32 34 45 44 37 42 51 48 42 37 51 31 31 46 51 55 59
	305	49 44 67 62 68 68 45 40 49 52 33 41 56 64 68 69 49 52 50 54 54 58
	306	70 66 54 46 48 59 64 71 75 73 63 55 63 55 52 51 45 57 61 59 65 62
	307	59 70 72 73 75 72 72 72 73 71 69 69 60 59 59 60 68 69 72 65 62 66
10*	308	69 70 72 76 76 77 77 68 64 63 68 69 66 58 66 71 78 77 73 64 61 59
	309	62 62 62 62 72 78 76 79 79 76 73 75 76 77 75 73 68 70 74 72 71 72
	310	78 73 72 70 70 70 72 71 73 75 74 74 71 71 71 73 74 72 67 68 72 72
	311	73 73 71 72 75 74 74 73 75 68 72 70 71 71 73 74 75 76 76 73 75 74
	312	73 71 67 63 58 59 59 65 68 67 69 72 72 73 59 58 60 66 66 68 68 59
	313	54 47 50 58 57 61 69 63 54 49 42 37 46 55 57 50 44 48 54 58 62 65
	314	69 57 50 52 48 42 36 34 43 50 58 61 53 47 53 63 63 64 64 66 63 66
	315	55 46 42 39 42 50 58 45 42 40 34 36 39 38 54 53 34 36 44 56 38 28
	316	33 39 34 35 34 32 32 28 26 33 42 42 25 25 34 43 39 38 39 40 32 28
	317	39 30 38 36 50 55 42 29 39 41 44 47 47
	401	27 24 34 28 28 32 29 24 40 43 40 14 14 31 44 44 47 46 55 52 46 41
	402	42 34 37 47 43 42 37 35 31 18 43 32 20 16 33 32 22 15 20 18 20 37
	403	39 26 30 24 24 37 31 30 39 20 26 13 14 17 30 32 48 47 42 47 49 57
	404	54 52 40 35 42 34 15 29 35 27 24 47 38 39 21 29 19 10 29 36 44 47
	405	41 35 40 43 48 56 36 28 26 44 29 28 31 42 52 52 34 30 34 34 40 34
	406	43 51 38 30 28 33 39 46 52 54 47 49 55 40 38 38 30 40 52 47 55 54
	407	40 46 57 60 67 66 65 62 61 65 60 58 46 48 44 48 62 64 66 63 58 56
	408	56 54 62 65 65 66 63 55 51 49 54 61 56 49 51 59 67 68 67 62 54 54
11*	409	54 58 60 58 60 64 67 67 68 67 69 68 69 69 69 66 57 57 60 66 63 64
	410	67 67 64 61 60 65 66 64 68 67 67 67 61 59 59 65 67 62 60 62 65 68
	411	67 67 65 68 68 64 66 68 67 66 64 63 62 63 65 66 68 69 68 69 69 69
	412	68 66 63 60 50 51 57 61 63 65 67 66 66 67 56 54 56 59 60 60 62 57
	413	49 38 41 47 50 56 63 52 41 37 27 27 29 37 42 45 36 36 41 44 49 56
	414	53 50 48 41 37 28 28 24 25 34 47 52 43 31 31 44 55 54 54 55 55 52
	415	47 31 35 32 32 32 31 39 27 29 20 23 32 35 48 44 27 27 27 37 33 17
	416	20 23 20 25 31 30 25 20 19 21 26 37 20 15 23 34 34 34 29 34 26 20
	417	30 25 30 24 28 42 36 18 34 39 39 41 43

\* The first twelve columns of this card have been used for identification.  
They can be left blank if desired.



APPENDIX A.8

HEAT EXCHANGE PROGRAM

SAMPLE OUTPUT

1974 CHARLESTON / SUTTON LAKE, W. VA. AIR & DEW = 2.5 DEG. F

CLOUD COVER	= CLOUD COVER X 1.00 + 0.00
WIND SPEED	= WIND SPEED X 1.00 + 0.00
DRY BULB TEMPERATURE	= DRY BULB TEMPERATURE X 1.00 + -2.50
DEW POINT TEMPERATURE	= DEW POINT TEMPERATURE X 1.00 + -2.50

DAY	EQ TEMP	EX COEFF	SN DAY	LW	LW NET	SKY	WIND	AIRY	DEWT
1	24.8	60.7	318.1	1883.6	1827.1	10	7.	28.	25.
2	28.6	61.0	779.8	1674.1	1623.9	4	7.	29.	22.
3	29.9	40.1	318.1	2002.5	1942.4	10	3.	33.	32.
4	25.1	61.1	322.2	1883.6	1827.1	10	7.	28.	26.
5	25.1	38.4	323.9	1906.9	1849.7	10	3.	29.	26.
6	28.4	55.4	324.1	1954.2	1895.6	10	6.	31.	30.
7	28.0	70.0	327.2	1954.2	1895.6	10	8.	31.	27.
8	24.2	52.4	331.0	1883.6	1827.1	10	8.	28.	22.
9	38.0	70.2	326.0	2179.4	2114.1	10	7.	40.	38.
10	40.3	53.8	326.3	2232.3	2165.4	10	5.	42.	41.
11	38.2	68.5	330.3	2179.4	2114.1	10	9.	40.	38.
12	19.6	63.2	357.9	1657.2	1607.5	8	8.	22.	12.
13	19.2	42.8	362.4	1636.7	1587.6	8	5.	21.	12.
14	33.4	64.7	342.1	2102.1	2039.0	10	7.	37.	29.
15	46.1	117.0	642.7	2219.8	2153.2	7	12.	48.	42.
16	48.7	119.7	340.3	2572.6	2495.4	10	12.	54.	42.
17	51.4	103.8	730.6	2333.4	2263.4	6	7.	54.	45.
18	53.7	82.7	738.7	2416.4	2343.9	6	7.	57.	44.
19	55.8	103.6	340.0	2695.2	2614.4	10	8.	58.	53.
20	56.6	89.3	660.3	2524.6	2448.8	7	7.	59.	50.
21	47.9	99.8	353.4	2483.7	2409.2	10	9.	51.	44.
22	50.6	46.6	774.4	2226.4	2159.6	6	3.	50.	39.
23	45.6	75.1	363.1	2425.9	2353.1	10	7.	49.	40.
24	32.9	49.0	371.4	2051.8	1990.2	10	3.	35.	32.
25	35.4	41.7	373.4	2102.1	2039.0	10	3.	37.	35.
26	47.7	58.1	370.4	2425.9	2353.1	10	5.	49.	45.
27	52.7	144.6	723.1	2553.9	2477.3	7	14.	60.	41.
28	44.2	93.9	381.8	2369.2	2298.2	10	9.	47.	40.
29	43.6	43.6	639.8	2141.0	2076.8	8	3.	43.	35.
30	48.5	34.9	1022.0	1937.2	1879.0	3	2.	42.	33.
31	44.4	105.3	1075.5	2063.0	2001.1	2	12.	48.	29.
32	38.2	46.9	788.8	1993.8	1934.0	7	5.	39.	16.
33	44.8	85.2	402.0	2369.2	2298.2	10	8.	47.	41.
34	30.7	56.1	413.5	1978.2	1918.9	10	6.	32.	30.
35	22.5	79.7	423.5	1815.1	1760.6	10	10.	25.	18.
36	25.8	44.1	929.1	1566.4	1519.4	6	5.	21.	14.
37	36.6	66.7	426.8	2153.4	2088.8	10	7.	39.	31.
38	33.1	89.7	432.2	2051.8	1990.2	10	10.	35.	30.
39	21.5	58.6	441.9	1770.6	1717.5	10	7.	23.	20.
40	19.7	56.6	608.0	1658.5	1608.7	9	7.	20.	13.
41	24.9	80.6	612.5	1786.9	1733.3	9	10.	26.	18.
42	30.1	82.0	1142.9	1653.7	1604.1	4	10.	28.	16.
43	40.9	80.2	1289.6	1885.3	1828.7	0	9.	41.	16.
44	46.5	73.1	620.7	2359.0	2288.2	9	7.	49.	35.
45	38.0	69.8	462.5	2127.6	2063.8	10	7.	38.	37.
46	40.2	57.4	1327.5	1711.5	1660.2	0	6.	33.	24.
47	36.5	48.9	478.8	2127.6	2063.8	10	5.	35.	28.
48	37.7	88.3	1353.4	1756.6	1703.9	1	10.	35.	22.

DAY	EQ TEMP	EX COEFF	SA DAY	LW	LX NET	SKY	WIND	AIRY	DENT
49	36.4	39.6	492.6	2127.6	2063.8	10	3.	38.	22.
50	46.6	101.9	947.9	2219.8	2153.2	7	10.	48.	35.
51	36.1	74.1	675.9	2019.5	1958.9	9	8.	36.	29.
52	43.1	77.2	978.3	2091.8	2029.0	7	8.	43.	28.
53	45.1	169.3	504.8	2454.7	2381.1	10	18.	50.	37.
54	37.5	86.4	1379.3	1780.5	1727.1	3	10.	38.	18.
55	39.2	57.0	1233.9	1762.6	1709.8	5	6.	32.	24.
56	20.6	83.6	889.3	1596.2	1548.3	8	12.	19.	11.
57	32.2	66.9	1511.9	1534.8	1488.8	1	8.	24.	12.
58	32.0	60.2	1545.4	2051.8	1990.2	10	7.	35.	15.
59	40.8	93.2	1544.3	2313.7	2244.2	10	10.	45.	28.
60	49.1	62.9	1294.9	2037.1	1976.0	5	6.	44.	30.
61	54.3	96.0	1540.0	2664.1	2584.2	10	8.	57.	46.
62	57.9	134.0	1546.6	2955.1	2866.4	10	12.	66.	45.
63	58.0	128.7	557.1	3057.7	2966.0	10	12.	69.	40.
64	52.8	116.3	1560.5	2633.3	2554.3	10	10.	56.	45.
65	52.0	60.9	565.4	2454.7	2381.1	10	5.	50.	47.
66	66.2	88.7	924.6	2800.5	2716.5	8	6.	66.	55.
67	67.2	72.9	1098.6	2705.0	2623.9	7	5.	65.	52.
68	62.0	120.5	784.7	2906.5	2819.3	9	9.	67.	50.
69	50.7	97.6	810.9	2472.5	2398.3	9	9.	53.	38.
70	41.0	69.4	609.7	2205.8	2139.6	10	7.	41.	33.
71	42.7	83.2	609.4	2205.8	2139.6	10	8.	41.	40.
72	39.3	69.6	1761.7	1652.7	1603.1	1	8.	30.	12.
73	54.3	33.4	1686.5	1716.6	1665.1	3	2.	32.	13.
74	41.4	67.3	638.2	2259.2	2191.4	10	7.	43.	27.
75	40.1	131.2	639.7	2232.3	2165.4	10	15.	42.	33.
76	34.4	128.0	882.1	1995.1	1935.3	9	16.	35.	25.
77	39.4	81.1	893.3	2119.3	2055.7	9	9.	40.	22.
78	50.5	81.1	646.0	2425.9	2353.1	10	7.	49.	45.
79	52.5	67.0	1284.6	2167.8	2102.8	7	6.	46.	36.
80	41.1	99.0	667.2	2179.4	2114.1	10	10.	40.	37.
81	51.9	51.6	1933.6	1753.7	1701.0	0	5.	38.	19.
82	58.1	46.1	1336.4	2246.2	2178.8	7	3.	49.	27.
83	33.3	76.3	1166.3	1807.1	1752.9	8	9.	29.	17.
84	41.7	54.1	1682.6	1699.1	1648.1	5	6.	29.	8.
85	47.7	79.4	1373.0	2116.9	2053.4	7	8.	44.	27.
86	53.8	36.1	706.6	2425.9	2353.1	10	2.	49.	34.
87	54.6	60.0	703.8	2542.7	2466.4	10	5.	53.	42.
88	57.6	110.0	1176.2	2524.8	2449.0	8	9.	57.	45.
89	49.1	117.4	1198.4	2245.3	2177.9	8	12.	47.	39.
90	45.2	99.4	1218.6	2115.6	2052.1	8	10.	42.	33.
91	57.6	104.0	731.6	2921.5	2833.8	10	9.	65.	38.
92	64.9	90.1	1959.4	2393.6	2321.8	3	7.	60.	41.
93	61.0	127.3	991.1	2873.5	2787.3	9	10.	66.	46.
94	62.7	139.9	725.0	2955.1	2866.4	10	10.	66.	54.
95	42.6	107.3	758.0	2259.2	2191.4	10	12.	43.	34.

DAY	EQ TEMP	EX COEFF	SA DAY	LW	LX NET	SKY	WIND	AIRY	DENT
96	44.5	94.6	1686.6	1929.8	1871.9	6	10.	38.	26.
97	49.2	60.9	1051.7	2303.8	2234.7	9	6.	47.	24.
98	50.8	90.1	764.7	2454.7	2381.1	10	8.	50.	42.
99	38.3	82.7	1311.7	1852.0	1796.4	3	9.	31.	27.
100	58.0	55.9	2120.1	1868.7	1812.6	3	5.	39.	26.
101	54.9	65.4	1074.3	2501.6	2426.5	9	6.	54.	29.
102	57.6	94.4	787.5	2822.7	2738.0	10	8.	62.	40.
103	64.2	109.9	1052.1	2873.5	2787.3	9	8.	66.	50.
104	64.3	137.0	1307.3	2832.6	2747.6	8	10.	67.	50.
105	44.7	116.7	810.8	2369.2	2298.2	10	13.	47.	32.
106	62.6	57.2	2274.0	2112.3	2048.9	2	6.	50.	28.
107	56.6	68.9	1370.8	2272.0	2203.9	8	5.	48.	32.
108	58.9	68.9	1608.7	2326.9	2257.0	7	6.	52.	32.
109	58.3	82.5	1604.6	2326.9	2257.0	7	7.	52.	38.
110	80.4	44.2	2362.5	2250.7	2183.2	0	2.	56.	32.
111	62.5	87.9	827.7	3023.2	2932.5	10	7.	68.	41.
112	60.0	142.0	822.8	2888.2	2801.6	10	12.	64.	49.
113	54.1	130.5	1846.5	2279.4	2211.0	6	13.	52.	36.
114	47.9	89.2	1428.3	2166.7	2101.7	8	9.	44.	28.
115	60.0	56.8	1886.7	2123.6	2059.9	6	5.	46.	26.
116	75.0	54.7	2389.4	2292.5	2223.7	2	3.	57.	31.
117	80.9	45.7	2048.3	2515.1	2439.6	5	2.	62.	37.
118	69.2	83.2	1428.4	2897.8	2810.9	8	6.	69.	44.
119	72.2	120.7	2020.1	2850.6	2765.1	5	8.	73.	50.
120	69.8	149.0	2019.9	2787.0	2703.4	5	10.	71.	52.
121	63.9	92.1	1446.8	2644.4	2563.0	8	7.	61.	45.
122	54.7	108.8	867.8	2542.7	2466.4	10	9.	53.	47.
123	62.2	137.7	1164.0	2713.3	2631.9	9	10.	61.	53.
124	62.1	62.3	1482.9	2409.7	2337.4	8	5.	53.	38.
125	51.2	76.4	894.7	2454.7	2381.1	10	7.	50.	36.
126	58.7	92.6	2136.5	2161.6	2096.7	5	6.	49.	36.
127	65.8	49.3	2166.3	2013.0	1952.6	5	3.	43.	28.
128	56.1	70.0	902.9	2602.8	2524.7	10	6.	55.	38.
129	63.8	122.8	1729.5	2524.6	2448.8	8	9.	59.	50.
130	73.5	59.2	1970.5	2416.4	2343.9	6	3.	57.	45.
131	73.9	78.3	1730.8	2643.7	2564.4	7	5.	63.	53.
132	72.9	100.0	1491.9	2614.0	2535.6	8	7.	60.	52.
133	65.9	107.7	2014.2	2416.4	2343.9	8	9.	57.	38.
134	61.1	107.7	2587.2	2583.9	2506.4	6	8.	68.	44.
135	73.9	90.0	1211.0	3007.2	2917.0	9	8.	70.	55.
136	68.9	121.7	2471.3	2691.5	2610.8	2	5.	71.	56.
137	82.4	125.1	874.7	3199.3	3103.3	10	7.	73.	62.
138	73.5	110.9	1717.1	2863.5	2777.6	8	6.	70.	64.
139	77.4	52.9	1480.3	2930.9	2842.9	3	2.	70.	60.
140	85.8	77.8	2403.7	2683.7	2603.2	3	5.	71.	59.
141	81.7	92.3	2300.2	2746.1	2663.7	4	5.	69.	63.
142	73.8	104.9	1207.0	2973.3	2884.1	9	6.	69.	63.

DAY	EQ TEMP	EX COEFF	SH DAY	LW	LW NET	SKY	WIND	AIRT	DEWT
143	74.8	83.9	1517.5	2832.6	2747.6	8	5.	67.	58.
144	70.8	110.0	1529.1	2832.6	2747.6	8	7.	67.	56.
145	66.8	81.2	1834.5	2495.5	2420.6	7	6.	58.	44.
146	61.3	65.5	1938.5	2664.1	2584.2	10	5.	57.	46.
147	79.0	61.5	2630.6	2292.5	2223.7	2	3.	57.	42.
148	70.7	57.9	1575.8	2554.2	2477.6	8	3.	58.	46.
149	67.6	126.1	1913.4	2955.1	2866.4	10	8.	66.	60.
150	70.6	99.9	909.5	2989.0	2899.3	10	6.	67.	62.
151	71.2	137.6	905.2	3092.6	2999.8	10	8.	70.	64.
152	68.3	96.2	1915.1	2855.3	2769.6	10	6.	63.	61.
153	76.2	66.7	1814.0	2553.9	2477.3	7	3.	60.	56.
154	83.7	71.6	2599.3	2485.0	2410.8	2	3.	64.	54.
155	67.9	89.5	1936.2	2989.0	2899.3	10	6.	67.	54.
156	70.3	105.2	1575.5	2865.1	2779.1	8	7.	68.	52.
157	80.1	91.3	2027.0	2805.0	2720.9	6	5.	70.	60.
158	78.5	149.5	2343.9	2840.6	2755.4	4	8.	74.	63.
159	77.8	110.4	1534.6	3066.2	2974.2	8	3.	74.	63.
160	90.0	85.6	2595.5	2801.4	2717.3	1	3.	75.	64.
161	74.8	174.7	2028.5	2967.8	2878.7	6	10.	75.	61.
162	71.8	123.5	2258.8	2633.0	2554.1	5	8.	66.	53.
163	77.6	80.0	2563.1	2449.4	2376.0	3	5.	62.	49.
164	86.2	51.8	2450.2	2449.4	2376.3	4	2.	61.	47.
165	82.9	69.8	2426.1	2594.8	2516.6	4	3.	66.	52.
166	68.0	156.7	1260.9	2906.5	2819.3	9	10.	67.	59.
167	69.2	120.9	1844.3	2674.2	2594.0	7	8.	64.	54.
168	66.9	83.3	1872.6	2438.2	2365.0	7	6.	56.	47.
169	74.7	92.6	2444.4	2535.7	2459.6	4	6.	64.	49.
170	72.3	113.1	1569.3	2897.8	2810.9	8	7.	69.	57.
171	76.8	149.6	1532.4	3135.9	3041.8	8	8.	76.	65.
172	74.9	166.4	1834.4	3181.7	3086.3	9	9.	75.	66.
173	72.9	124.1	1915.4	3127.8	3034.0	10	7.	71.	65.
174	67.4	94.4	929.5	2822.7	2738.0	10	6.	62.	60.
175	67.7	87.7	1587.1	2584.0	2506.5	8	6.	59.	52.
176	66.2	72.2	1282.5	2590.6	2512.9	9	5.	57.	52.
177	73.3	62.4	1585.6	2614.0	2535.6	8	3.	60.	52.
178	69.0	77.0	1268.9	2682.2	2601.7	9	5.	60.	56.
179	66.8	76.7	1932.4	2758.3	2675.6	10	9.	60.	58.
180	73.3	80.8	1829.2	2553.9	2477.3	7	5.	60.	56.
181	72.8	148.2	2043.5	2805.0	2720.9	6	9.	70.	58.
182	78.9	129.8	2018.3	3001.2	2911.2	6	7.	76.	62.
183	89.8	86.2	2581.4	2770.1	2687.0	1	3.	74.	65.
184	84.6	123.5	2578.6	2864.9	2778.9	1	6.	77.	65.
185	84.3	124.4	2432.5	2903.7	2816.6	3	6.	77.	66.
186	76.6	91.9	906.8	3235.5	3138.4	10	5.	74.	65.
187	77.7	75.3	899.4	3127.8	3034.0	10	3.	71.	67.
188	84.5	61.2	1759.9	2962.2	2873.3	7	3.	73.	66.
189	89.0	57.1	1500.7	3066.2	2974.2	8	2.	74.	67.

DAY	EQ TEMP	EX COEFF	SA DAY	LW	LW NET	SKY	WIND	AIRY	DENY
190	83.9	53.7	895.5	3272.0	3173.9	10	2.	75.	67.
191	74.6	129.7	894.1	3199.3	3103.3	10	7.	73.	67.
192	81.2	76.3	1508.6	2964.2	2875.3	8	3.	71.	64.
193	78.0	50.2	1249.4	2873.5	2787.3	9	2.	66.	55.
194	81.3	70.2	2022.5	2742.1	2659.8	6	3.	68.	53.
195	83.5	93.6	2587.6	2708.3	2627.1	1	5.	72.	58.
196	76.2	90.6	1210.6	3007.2	2917.0	9	5.	70.	64.
197	87.7	58.9	1977.5	2773.4	2690.2	6	2.	69.	61.
198	90.9	61.9	2291.5	2715.2	2633.7	4	2.	70.	62.
199	82.3	98.9	1729.2	3063.7	2971.8	7	5.	76.	63.
200	72.0	140.5	883.9	3127.8	3034.0	10	8.	71.	65.
201	81.8	75.3	1737.2	2863.5	2777.6	7	3.	70.	62.
202	84.8	76.0	2404.2	2623.5	2544.8	3	3.	68.	59.
203	81.5	72.2	1964.7	2742.1	2659.8	6	3.	68.	58.
204	71.3	101.8	880.3	3023.2	2932.5	10	6.	68.	63.
205	77.8	92.3	1462.9	2930.9	2842.9	8	5.	70.	64.
206	83.7	77.2	2094.9	2724.5	2642.8	5	3.	69.	62.
207	79.7	56.1	863.9	3127.8	3034.0	10	2.	71.	66.
208	89.5	62.5	1894.6	2901.8	2814.7	6	2.	73.	65.
209	87.3	60.8	1679.9	2929.0	2841.1	7	2.	72.	65.
210	74.7	145.5	1434.6	2997.9	2908.0	8	8.	72.	65.
211	73.6	100.5	1456.2	2897.8	2810.9	8	6.	69.	59.
212	84.1	74.0	2338.9	2653.4	2573.8	3	3.	69.	57.
213	91.5	54.0	2329.8	2653.4	2573.8	3	2.	69.	57.
214	77.5	91.1	1422.8	2964.2	2875.3	8	5.	71.	63.
215	72.9	124.0	842.9	3163.4	3068.5	10	7.	72.	65.
216	74.0	119.1	1662.0	2863.5	2777.6	7	7.	70.	60.
217	73.4	49.1	834.1	2921.5	2833.8	10	2.	65.	58.
218	71.7	65.8	845.8	2955.1	2866.4	10	3.	66.	60.
219	85.2	58.2	1625.8	2863.5	2777.6	7	2.	70.	63.
220	81.7	78.3	1602.3	3041.5	2950.2	9	3.	70.	66.
221	78.3	74.3	1111.8	3041.5	2950.2	9	3.	71.	65.
222	76.0	72.4	818.3	3127.8	3034.0	10	3.	71.	65.
223	74.2	69.5	820.0	3057.7	2966.0	10	3.	69.	63.
224	74.1	90.2	808.2	3092.6	2999.8	10	5.	70.	66.
225	81.2	77.8	1340.6	3031.9	2941.0	8	3.	73.	66.
226	90.9	61.9	2283.2	2708.3	2627.1	1	2.	72.	62.
227	85.8	80.8	2213.7	2722.1	2640.5	2	3.	72.	64.
228	81.5	78.1	1538.3	2896.1	2809.2	7	3.	71.	66.
229	77.7	112.6	1533.8	2962.2	2873.3	7	6.	73.	65.
230	74.8	52.4	789.5	2955.1	2866.4	10	2.	66.	64.
231	79.2	92.0	1877.7	2755.6	2672.9	5	5.	70.	62.
232	76.8	70.2	1310.8	2865.1	2779.1	8	3.	68.	61.
233	78.8	89.8	1999.5	2684.5	2604.0	4	5.	69.	60.
234	82.7	75.5	2083.1	2653.4	2573.8	3	3.	69.	61.
235	83.2	77.5	1958.9	2746.1	2663.7	4	3.	71.	63.
236	87.4	60.3	1814.4	2818.7	2734.1	5	2.	72.	64.

DAY	EQ TEMP	EX COEFF	SA DAY	LW	LW NET	SKY	WIND	AIRY	DEWT
237	85.1	54.0	1254.0	3031.9	2941.0	8	2.	73.	66.
238	87.6	56.0	1449.4	2995.7	2905.8	7	2.	74.	67.
239	80.6	97.7	1625.1	2934.6	2846.6	6	2.	74.	66.
240	80.6	57.2	993.2	3041.5	2950.2	9	2.	71.	67.
241	74.6	129.7	987.0	3110.9	3017.6	9	7.	73.	67.
242	72.0	162.1	725.0	3163.4	3068.5	10	9.	72.	67.
243	73.8	89.9	722.9	3127.4	3034.0	10	5.	71.	66.
244	71.9	86.1	723.1	3057.7	2966.0	10	5.	69.	64.
245	68.6	80.4	725.3	2921.5	2833.8	10	5.	65.	61.
246	63.4	103.2	726.7	2790.3	2706.6	10	7.	61.	58.
247	62.3	105.8	1760.1	2346.4	2276.0	5	8.	56.	48.
248	69.0	72.5	1865.2	2339.0	2268.8	4	5.	57.	49.
249	61.5	70.6	717.2	2664.1	2584.2	10	5.	57.	55.
250	70.7	43.9	704.1	2855.3	2769.6	10	2.	63.	59.
251	72.4	49.8	694.6	2955.1	2866.4	10	2.	66.	61.
252	72.2	50.6	684.9	2921.5	2833.8	10	2.	65.	63.
253	74.8	47.9	674.9	2989.0	2899.3	10	2.	67.	65.
254	78.0	73.4	1307.3	2863.5	2777.6	7	3.	70.	64.
255	72.2	104.0	901.7	3007.2	2917.0	9	6.	70.	64.
256	72.2	123.0	691.2	3041.5	2950.2	9	7.	71.	65.
257	60.6	69.4	675.3	2664.1	2584.2	10	5.	57.	54.
258	64.6	71.0	1308.0	2438.2	2365.0	7	5.	56.	52.
259	67.1	44.9	898.1	2620.8	2542.2	9	2.	58.	54.
260	72.2	64.4	1268.6	2674.2	2594.0	7	3.	64.	57.
261	72.7	81.8	1633.2	2535.7	2459.6	4	5.	64.	58.
262	77.3	68.7	1793.7	2530.0	2454.1	1	3.	66.	58.
263	69.0	63.9	630.0	2955.1	2866.4	10	3.	66.	60.
264	60.4	69.9	633.1	2664.1	2584.2	10	5.	57.	55.
265	57.3	87.6	1240.1	2326.9	2257.0	7	7.	52.	47.
266	59.1	59.1	1710.0	2007.7	1947.5	3	5.	45.	36.
267	60.1	61.6	1742.9	2063.0	2001.1	2	5.	48.	39.
268	56.6	97.3	1035.8	2495.6	2420.7	8	8.	56.	45.
269	67.5	57.0	1622.0	2258.7	2190.9	3	3.	55.	48.
270	67.2	59.5	1160.9	2524.6	2448.8	7	3.	59.	54.
271	71.6	83.1	1126.6	2767.5	2684.5	7	3.	67.	61.
272	57.4	139.6	593.8	2790.3	2706.6	10	12.	61.	50.
273	54.4	112.4	1668.8	2151.6	2087.0	1	10.	52.	39.
274	55.5	68.2	1663.0	2028.4	1967.6	1	6.	47.	35.
275	44.7	59.3	1157.3	2017.9	1957.4	7	6.	40.	25.
276	49.5	43.0	1488.9	1801.4	1747.3	4	3.	35.	25.
277	56.7	45.6	1599.3	1967.4	1908.3	2	2.	44.	27.
278	63.1	50.1	1602.3	2173.2	2108.0	0	0.	53.	35.
279	70.3	38.6	1574.2	2224.6	2157.9	0	2.	55.	40.
280	51.3	37.2	1553.9	2397.4	2325.5	10	2.	48.	43.
281	57.5	37.0	1400.6	1959.9	1901.1	4	2.	42.	34.
282	62.8	35.4	1506.8	2014.7	1954.3	2	2.	46.	34.
283	65.8	40.3	1513.7	2147.9	2083.5	0	2.	52.	39.

DAY	EQ TEMP	EX COEFF	SH DAY	LW	LA NET	SKY	WIND	AIRY	DENT
284	69.7	38.9	1490.2	2250.7	2183.2	0	2.	56.	42.
285	61.9	37.7	1520.0	2758.3	2675.6	10	2.	60.	47.
286	67.6	41.2	684.7	2776.5	2693.2	9	2.	63.	54.
287	62.9	96.0	682.8	2906.5	2819.3	9	7.	67.	51.
288	53.8	59.6	503.0	2602.8	2524.7	10	7.	55.	48.
289	49.3	59.2	499.9	2397.4	2325.5	10	5.	48.	46.
290	52.7	89.6	1404.3	2098.0	2035.1	0	8.	50.	39.
291	44.7	53.3	499.1	2341.3	2271.1	10	5.	46.	35.
292	42.2	58.7	966.5	2017.9	1957.4	7	6.	40.	26.
293	33.1	47.7	494.2	2027.0	1966.2	10	5.	34.	26.
294	48.5	31.1	1373.1	1690.8	1640.1	0	2.	32.	22.
295	49.9	42.8	1356.4	1885.3	1828.7	0	3.	41.	23.
296	53.9	45.9	1190.0	2104.8	2041.7	4	3.	48.	32.
297	56.4	36.9	459.6	2633.3	2554.3	10	2.	56.	45.
298	56.5	89.2	449.6	2726.6	2644.8	10	7.	59.	50.
299	50.0	47.0	453.2	2483.7	2409.2	10	3.	51.	41.
300	56.2	33.2	1272.8	1977.5	1918.2	0	2.	45.	29.
301	60.1	34.0	1258.3	2122.9	2059.2	0	2.	51.	29.
302	57.6	50.1	437.7	2790.3	2706.6	10	3.	61.	42.
303	61.5	56.0	1571.2	2713.9	2631.9	9	3.	61.	53.
304	67.7	40.7	974.4	2515.1	2439.6	5	2.	62.	52.
305	65.4	43.6	797.8	2613.5	2535.1	7	2.	62.	52.
306	65.4	58.0	884.2	2619.7	2541.1	6	3.	64.	53.
307	60.1	55.3	404.1	2790.3	2706.6	10	3.	61.	53.
308	59.1	104.2	544.9	2809.5	2724.2	9	8.	64.	50.
309	50.4	113.7	543.2	2472.5	2398.3	9	10.	53.	45.
310	44.8	51.6	884.6	2073.7	2011.5	6	5.	44.	29.
311	37.9	50.6	402.8	2179.4	2114.1	10	5.	40.	33.
312	42.9	31.1	864.1	1906.6	1849.4	6	2.	37.	30.
313	47.4	31.8	1027.2	1891.3	1834.5	3	2.	40.	30.
314	46.9	34.1	530.2	2331.3	2261.3	9	2.	48.	30.
315	48.7	71.6	525.4	2560.6	2483.8	9	7.	56.	29.
316	41.2	89.8	514.0	2196.8	2130.9	9	9.	43.	37.
317	36.5	105.3	733.0	2017.9	1957.4	7	13.	40.	25.
318	33.9	96.8	377.7	2127.6	2063.8	10	12.	38.	27.
319	31.4	83.3	1006.1	1702.3	1651.2	2	10.	32.	18.
320	35.6	39.3	802.1	1838.5	1783.4	6	5.	34.	21.
321	37.4	66.7	833.5	1873.0	1816.8	5	7.	37.	30.
322	33.5	30.3	360.5	2076.8	2014.5	10	2.	36.	33.
323	49.9	59.5	349.0	2513.1	2437.7	10	5.	32.	46.
324	48.0	119.0	666.5	2299.7	2230.7	7	12.	31.	42.
325	28.8	100.4	354.9	1978.2	1918.9	10	13.	32.	25.
326	33.1	55.4	671.6	1876.8	1820.5	7	6.	34.	25.
327	43.3	41.5	957.2	1908.0	1850.7	0	3.	42.	25.
328	48.0	83.7	558.3	2438.0	2364.9	8	8.	54.	35.
329	33.2	81.9	341.4	2076.8	2014.5	10	9.	36.	31.
330	27.8	37.4	837.8	1613.4	1585.0	4	5.	26.	15.



DAY	EQ TEMP	EX COEFF	SN DAY	LW	LW NET	SKY	WIND	AIRY	DEWT
331	29.3	67.6	775.5	1741.2	1689.0	5	8.	31.	18.
332	34.8	78.4	921.5	1796.6	1742.7	0	9.	37.	21.
333	30.1	45.5	639.0	1831.6	1776.7	7	5.	32.	18.
334	28.7	68.9	333.0	2002.5	1942.4	10	8.	33.	23.
335	29.2	63.3	328.6	1978.2	1918.9	10	7.	32.	29.
336	27.6	78.0	327.0	1930.4	1872.5	10	9.	30.	28.
337	29.3	84.4	835.5	1675.2	1624.9	3	10.	30.	23.
338	21.4	43.9	326.9	1837.7	1782.5	10	5.	26.	18.
339	27.8	30.3	885.9	1532.2	1486.3	0	2.	24.	17.
340	33.2	31.0	854.6	1681.6	1631.2	2	2.	31.	19.
341	34.4	55.5	320.1	2179.4	2114.1	10	6.	40.	24.
342	37.0	77.3	314.1	2179.4	2114.1	10	8.	40.	35.
343	20.3	71.9	432.0	1721.7	1670.0	9	9.	23.	18.
344	24.2	43.7	870.8	1513.3	1467.9	0	5.	23.	13.
345	26.6	30.5	316.0	1978.2	1918.9	10	2.	32.	21.
346	36.8	50.0	310.8	2205.8	2139.6	10	5.	41.	32.
347	33.0	32.3	309.9	2102.1	2039.0	10	2.	37.	32.
348	33.5	40.8	418.1	2019.5	1958.9	9	3.	36.	32.
349	32.5	71.8	310.4	2102.1	2039.0	10	8.	37.	27.
350	35.2	66.5	416.3	2068.9	2006.8	9	7.	38.	32.
351	26.1	60.8	310.3	1930.4	1872.5	10	7.	30.	24.
352	21.7	65.2	311.8	1837.7	1782.5	10	8.	26.	18.
353	32.7	88.4	308.2	2102.1	2039.0	10	10.	37.	28.
354	27.1	28.7	588.9	1744.0	1691.7	7	2.	28.	23.
355	33.1	64.3	501.7	1968.2	1909.1	8	7.	36.	28.
356	32.7	54.5	796.5	1759.0	1706.2	3	6.	34.	22.
357	41.7	84.1	660.5	2174.5	2109.3	6	9.	48.	26.
358	47.9	66.3	303.4	2542.7	2466.4	6	6.	53.	40.
359	37.2	85.6	415.4	2119.3	2059.7	10	9.	40.	34.
360	26.5	37.3	716.3	1657.8	1608.0	5	3.	27.	16.
361	33.2	40.7	309.4	2102.1	2039.0	10	3.	37.	32.
362	36.2	42.3	307.9	2153.4	2088.8	10	3.	39.	37.
363	40.0	34.0	417.9	2170.7	2105.6	9	2.	42.	37.
364	41.8	63.1	308.9	2313.7	2244.2	10	6.	45.	39.
365	43.1	64.5	417.9	2249.8	2182.3	9	6.	45.	41.

1974 CHARLESTON / SUTTON LAKE, W. VA. AIR & DEW - 2.5 DEG. F

MONTH	EQUILIBRIUM (DEG F)	SURFACE HEAT EXCHANGE (8TL/SQ FT/DAY/DEG F)	SHORT WAVE SOLAR (BTU/SQ FT/DAY)	SHORT WAVE SOLAR (LANGLEYS/DAY)
1	39.0	72.0	496.	135.
2	34.9	74.0	781.	212.
3	49.7	84.5	984.	267.
4	59.5	91.9	1436.	390.
5	69.3	91.9	1581.	429.
6	73.9	102.4	1740.	472.
7	81.5	86.7	1682.	456.
8	79.5	81.3	1398.	378.
9	66.8	76.7	1104.	300.
10	55.9	50.7	1019.	277.
11	41.8	66.5	648.	176.
12	32.3	56.5	460.	125.

A P P E N D I X    B\*

THERMAL SIMULATION PROGRAM

722-F5-E1011

A P P E N D I X    C\*

MODEL VERIFICATION STUDIES

\* NOT INCLUDED WITH THIS MANUAL

EXHIBIT 6


GEDA PROGRAM MANUAL



**US Army Corps  
of Engineers**

The Hydrologic  
Engineering Center

**723-G2-L745B**



**GENERALIZED COMPUTER PROGRAM**

# **GEOMETRIC ELEMENTS FROM CROSS SECTION COORDINATES**

**OCTOBER 1981**

## TABLE OF CONTENTS

	<u>Page</u>
INTRODUCTION	
1. Origin of Program	1
2. Purpose of Program	1
PROGRAM DESIGN	1
1. Capability of This Computer Program	1
2. Program Organization	4
THEORETICAL BASIS	6
1. Computation of Geometric Elements	6
a. Subsection Area	7
b. Wetted Perimeter	8
c. Hydraulic Radius	8
2. Conveyance	9
3. Alpha, the Velocity Distribution Factor	9
4. Composite n-Value	9
5. Volume and Top Width	10
PROGRAM USAGE	10
1. Equipment Requirements	10
2. Input Preparation	10
a. Modeling the Study Reach	11
b. Coding Input Data	11
(1) Cross Section Coordinates	11
(2) Subsection Stations	12
(3) Conveyance Limits	12
(4) Reach Lengths	12
(5) n-Values	12
(6) Elevation Table	12
(7) Section No.	13
c. Computation Grid	13

## TABLE OF CONTENTS (cont'd)

	<u>Page</u>
PROGRAM OUTPUT	13
1. Printed Output	13
2. Punched Card Output	14
EXAMPLE PROBLEM	
3. Tape 95 Output	15
EXHIBITS	
Exhibit 1 -- Input Data	
Exhibit 2 -- Description of Pauses	
Exhibit 3 -- Input Data Description	
Exhibit 4 -- Card Array	
APPENDIXES	
Appendix I - Tape 95 Variable Description	
Appendix II - GEDA - Tape 95	



## GEOMETRIC ELEMENTS FROM CROSS SECTION COORDINATES

### INTRODUCTION

#### 1. ORIGIN OF PROGRAM

This program was developed at the Hydrologic Engineering Center by William A. Thomas.

#### 2. PURPOSE OF PROGRAM

The purpose of this program is to prepare tables of hydraulic elements for use by the computer program "Gradually Varied Unsteady Flow Profiles." It reads data coded in the standard format for "Water Surface Profiles, HEC-2" and produces tables of hydraulic elements for nodal points spaced a constant distance apart. The following hydraulic elements are calculated for each water surface elevation specified in the table: Cross sectional area, hydraulic radius to the  $2/3$  power, top width, average  $n$ -value, and velocity distribution factor. In addition to printing the hydraulic elements as each cross section is processed, the tables of hydraulic elements interpolated for each node are printed and the user may elect to have these tables also punched on cards.

### PROGRAM DESIGN

#### 1. CAPABILITY OF COMPUTER PROGRAM


In water surface profile calculations it is important to model conveyance. This sometimes results in cross sections which end at a flow boundary rather than extending all the way to the high ground,

as illustrated in figure No. 1. In unsteady flow profile calculations it is necessary to also model the conveyance. However, there is the additional requirement that storage in the reach must be modeled also. This dual requirement is fulfilled by assigning limits of flow to any cross section which might not convey flow over its entire cross sectional area. The entire area is available for storage, however.

The elevations in the hydraulic elements table are specified at the downstream end of the study area. These may be projected section by section to the upstream end on a horizontal line, or a sloping line may be used. Oftentimes the number of elevations required to specify the geometric model can be reduced if a sloping computation grid is utilized. The slope may be changed at any cross section in the study area or may be based on the stream's channel bed slope.

Normally, the interpolation to establish computation nodes is done based on the main channel length. However, if another length would be more appropriate, these values may be specified for each cross section. This does not change the reach lengths used in computation of volume or accumulated surface area. Rather, the so-called "weighted" lengths are designed to be more along the center of the flow and are only used in locating nodes.

Ineffective area may be specified just as it is in the data for water surface profile calculations. This area is considered to be ineffective both for conveying and storing water until the water surface rises to a certain minimum elevation. Above this elevation the area is no longer considered to be ineffective. It is utilized both in conveyance and storage calculations.



**Fig.1 Plan View of River and Flood Plain**

The unsteady flow routing model permits  $n$  to vary with elevation but only one value may be specified for the entire cross section at each elevation. However, in most steady flow calculations for water surface profiles, different  $n$ -values may be used in the overbanks and main channel. This program accepts  $n$ -values specified in the normal way and calculates a composite  $n$  for each elevation based on conveyance.

The interpolated values for top width are calculated from accumulated volume in the study reach rather than the cross section width at the water surface. This insures that the correct volume is preserved in the geometric model.

## 2. PROGRAM ORGANIZATION

The functional and organizational flow chart is shown in figure 2. A two pass computation procedure is used. During the first pass, input data is read section by section, and hydraulic element tables of area, hydraulic radius to the  $2/3$  power, water surface width, composite  $n$ -value, the velocity distribution factor, surface area, and volume are calculated, stored and printed out for each cross section. The position of each cross section is located in terms of distance to the downstream boundary using either the channel length or weighted length - if those values are specified. After the final cross section has been processed, the second pass is made through the hydraulic element tables at which time the position of each nodal point is located and the interpolated values for the hydraulic element tables are calculated. All of the second pass calculations are performed in subroutine INTPL.





Figure 2. Functional and Organizational Flow Chart


## THEORETICAL BASIS

### 1. COMPUTATION OF GEOMETRIC ELEMENTS

Each cross section is defined by coordinate points, and for convenience of assigning n-values, reach lengths, etc., each cross section is divided into subsections.



a. Typical cross section



b. Subdivisions of typical cross section

Fig. 3. Typical Cross Section

The cross section is subdivided into left overbank, main channel, and right overbank, and hydraulic elements are computed for each of these subsections, as shown below.

a. Subsection area. The subsection area is computed by summing incremental areas between consecutive coordinates of the cross section. Fig. 4 illustrates the technique by using the Main Channel subsection (3) of the previous figure as an example.




Fig. 4. Incremental Areas in Subsection

$$A_3 = a_1 + a_2 + a_3 + a_4$$

The equation for an incremental area is:

$$a = \frac{(A_1 + B_1) W_{avg}}{2}$$

Normally, where  $A_1$ ,  $B_1$  and  $W_{avg}$  are defined as shown in fig. 5, an incremental area is defined by two consecutive cross section coordinates. However, at the first and last increments in each subsection, a subsection station defines one side of the incremental area. If the subsection station does not coincide with an X coordinate, as below, straight line interpolation is used to compute the length of either  $A_1$ ,  $B_1$ , or both.




Fig. 5. An Incremental Area

b. Wetted perimeter. The wetted perimeter is computed as the length of cross section below the water surface. In the case of Fig. 4 this is:

$$P_3 = P_1 + P_2 + P_3 + P_4$$

The equation for wetted perimeter of each incremental area is:

$$p = \sqrt{D_{ely}^2 + W_{avg}^2}$$

where  $D_{ely}$  and  $W_{avg}$  are defined in fig. 5. Note that only the line between coordinate points and neither  $A_1$  nor  $B_1$  is considered in  $p$ . No energy is transferred between adjacent subsections.

c. Hydraulic radius. The hydraulic radius is calculated for each subsection:

$$R_j = \frac{A_j}{P_j}$$



## 2. CONVEYANCE

The conveyance is computed for each subsection by:

$$K_j = \frac{1.49}{n_j} A_j R_j^{2/3}$$

The total conveyance in the cross section is

$$K_t = \sum_{j=1}^{NSS} K_j$$

where NSS is total number of subsections.

## 3. ALPHA, THE VELOCITY DISTRIBUTION FACTOR

Alpha is a factor to account for the distribution of flow across the flood plain and not the vertical shape of the velocity profile. Large values ( $\geq 2$ ) of Alpha may occur if the depth of flow on the overbanks is shallow, the conveyance small, and the area large.

Alpha is computed as follows:

$$\alpha = \frac{\left(\frac{K_1}{A_1}\right)^2 K_1 + \left(\frac{K_2}{A_2}\right)^2 K_2 + \dots + \left(\frac{K_j}{A_j}\right)^2 K_j + \dots + \left(\frac{K_{NSS}}{A_{NSS}}\right)^2 K_{NSS}}{\left(\frac{K_t}{A_t}\right)^2 K_t}$$

where  $A_t$  is the sum of the subsection areas, and  $K_t$  is sum of conveyances.

## 4. COMPOSITE N-VALUE

The composite n-value is calculated as follows:

$$n = \frac{1.49 \times \text{SUMA} \times \text{COMR}^{2/3}}{\text{SUMK}}$$

SUMA = Total area of cross section (conveying flow)

COMR = Composite hydraulic radius = SUMA/SUMP

SUMK = Total conveyance of cross section (conveying flow)

SUMP = Total wetted perimeter of cross section (conveying flow)

## 5. VOLUME AND TOP WIDTH

Volume beneath the specified elevation is calculated by averaging each subsection end area and multiplying by the subsection reach length. These results are accumulated for each reach and with distance from the downstream end of the study area.

TOP WIDTH (not SUMM) is calculated for each nodal point using the interpolated values of accumulated volume.

$$V_{2DX} = V_0 + B_w \times DH \times 2 \times DX$$

where

$V_{2DX}$  = Volume of water that could be stored between nodal points located a distance of  $2 \times DX$  apart

$V_0$  = Volume corresponding to the elevation  $DH$  below that elevation for  $V_{2DX}$

$B_w$  = TOP WIDTH at elevation  $DH/2$  below that elevation for  $V_{2DX}$

$DH$  = Vertical distance between values in the elevation table

$DX$  = Horizontal distance between nodal points

## PROGRAM USAGE

### 1. COMPUTER EQUIPMENT REQUIREMENTS

This program requires 46000 decimal words of central processor memory on a CDC 7600. Punch file output, when requested, is written on Tape 7.

A tape 95 is always generated for plotting results.

### 2. INPUT PREPARATION

The bulk of input data is required for pass I. Only the  $DX$  value (or the number of nodes) is utilized in subroutine INTPL.

a. Modeling the study reach. With the study reach located on a topographic map, mark the left (upstream) and right (downstream) boundaries and the lateral limits for the geometric model. Mark the location of each cross section in the study reach. Subdivide the flood plain into channel and overbank strips. Determine the reach length for each strip. This will be the distance between cross sections unless a strip ends before reaching the next cross section. Assign n-values to each strip.

It is important to correctly model both volume and conveyance. Therefore, delineate portions of a cross section conveying flow from that portion which just stores water. Special cross section controls are provided for this purpose (see subparagraph 2b (3) below). A sketch of the flow lines is usually sufficient to adequately separate conveyance of water from storage of water in the geometric model.

b. Coding input data. Code the data by starting at the downstream boundary and proceeding to the upstream boundary. A sample listing of the data cards for the problem presented in fig. 6 is shown on page 1, exhibit 1. A detailed description of input variables is given in exhibit 3 and a summary of required cards is shown in exhibit 4.

(1) Cross section coordinates. The station points which define the cross section geometry must be positive values in units of feet (actually, any consistent set of units may be used with this program if n-values are appropriately chosen) and must be entered in increasing order of magnitude. These are coded on GR-cards.

(2) Subsection stations. The left and right sides of the main channel subdivide the cross section into subsections. These do not have to coincide with a coordinate point, but they can.

(3) Conveyance limits. Computations for conveyance can be restricted to any portion of a cross section by specifying limits with either STS, ENST or both on the CL-card. None of these controls have to coincide with a subsection station, but they can. Volume computations are not restricted by these controls. The entire cross section is utilized to compute volume.

(4) Reach lengths. The reach length should be measured in feet and entered on the X1 card for the upstream end of each reach. A value is required for each strip in the reach. This length does not have to extend from one cross section to the next.

(5) n-values. Manning's n-values can either be a constant in each strip or they can vary vertically with either elevation or discharge in the main channel. They should be defined at the first cross section and be redefined only as necessary to change their value.

(6) Elevation table. This program will accept up to 30 different elevation values spaced at random. However, the "Gradually Varied Unsteady Flow Profiles" program will accept only 21 values of elevation and these may not be spaced at random intervals. Only three different intervals may be specified and these intervals must be integer numbers. The elevations may be real numbers but the interval between elevations must be integers.

It is recommended that larger increments be used at the top and bottom of the elevation table so that solutions generated by the unsteady flow program will always remain within the table.

(7) Section no. A cross section identification number is always assigned on the X1-card. River mile is recommended. However, this value is used for identification only -- not for distance between cross sections. Likewise, node numbers, which are interpolated from Section Numbers, are for identification only.

c. Computation grid. It is often desirable to project the values in the elevation table on a slope rather than horizontally. This is permitted by input variable ASEL (JP-card). It is also necessary to establish the distance between interpolated nodes. The routing program requires an odd number of nodes equal to or greater than 5. This can be produced by specifying NODE (JP-4) or DX (JP-3). The computation grid is different from the computation net in the unsteady flow program. This grid is in the (X,Y) plane whereas the computation net is in the (X,T) plane.

#### PROGRAM OUTPUT

##### 1. PRINTED OUTPUT

Printed output is shown in exhibit 1. As each cross section is processed, Average Section Number, Reach Length (channel strip), Elevation, Area,  $P2/3$ , top width of conveyance portion of section, weighted n-value, Coriolis coefficient ( $\alpha$ ) for velocity distribution, accumulated surface area and accumulated volume beneath the water surface are printed.

After the final cross section has been processed, the geometric model being developed for the unsteady flow program is printed. Finally, a table of elevation versus volume is printed. These values are for comparison with the volumes printed at Section No. 3 of page 2, exhibit 1, as a check on the ability of the interpolated geometric data tables to reproduce the actual volume of the study reach.

## 2. PUNCHED CARD OUTPUT

The geometric elements will be punched on cards if that option is exercised (Card JP-10). The default option suppresses the punch. It is always advisable to review the printed results before punching the data.

### EXAMPLE PROBLEM

The following figure shows boundary geometry for a prismatic channel on a slope of .0002.




Figure 6 Annotated Boundary Geometry

The left overbank extends from cross section station 1000 to 1500. The channel extends from station 1500 to 2000, and the right overbank from 2000 to 2500. The n-values and reach lengths are shown on the figure. This example assumes that only the channel portion of the section conveys flow. The locations for STST and ENST are shown. These do not have to coincide with STA values.

The elevations specified for geometric data extend above elevation 535, the highest elevation of the cross section. The program assumes a vertical boundary at each end of the cross section, and it disregards any influence on wetted perimeter. Volume is important in the unsteady flow program; and it may be in error if the cross section coordinates do not extend above the elevation table range.

A listing of the input data is shown in exhibit 1. Only two cross sections are required, since the channel is prismatic, and the interpolation subroutine provides tables for seven nodal points equally spaced at 2640 feet apart.

### 3. TAPE 95 OUTPUT

The GEDA program produced a tape or file which contains 65 different output variables. The 65 variables are temporarily stored in an array called QVAR and written out to tape 95 as each section is processed. Tape 95 can then be used by HEC's Hydraulics Program to plot the variables interactively on a Tektronix 4014 computer display terminal or batch on a Calcomp drum plotter. A list and description of the 65 variables on tape 95 are given in Appendix I and II.

# Input Data

	TEST 1 PREPARED IN AUG 74 ** DATA DECK IN HEC-2 FORMAT **									
	GEOMETRIC ELEMENTS FROM CROSS SECTION COORDINATES, AUXILIARY PROGRAM TO									
	GRADUALLY VARIED UNSTEADY FLOW PROFILES, W A THOMAS, HEC, DAVIS, CA.									
	.00002 2640. 1									
T1	JP	521.	522.	523.	524.	525.	526.			
T2	ET	.08	.04	.03						
T3	NC	0.	6.	1500.	2000.					
	X1	535.	1000.	535.	1500.	520.	1500.	520.	2000.	530.
	GR	535.	2500.							2000.
	GR	3.0	0.	1500.	2000.	15840.	15840.	15840.		
	X1									3.168
	EJ									



VERSION 2.2 19SEPT1974  
 T1 TEST 1 PREPARED IN AUG74 \*\* DATA DFCK IN HEC-2 FORMAT \*\*  
 T2 GEOMETRIC ELEMENTS FROM CROSS SECTION COORDINATES, AUXILIARY PROGRAM TO  
 T3 GRADUALLY VARIED UNSTEADY FLOW PROFILES. W A THOMAS, HEC, DAVIS, CA.

HEADING DATA IN HEC-2 FORMAT.  
 ONLY CARDS NC, VV, XI, X3 AND GR CARDS ARE PERMITTED.

P-CARD ASL JX DX KSW(1) KSW(11) KSW(12)  
 .000200 6 2640.00 1 .00 1

521.000 522.000 523.000 524.000 525.000 526.000  
 ELEVATION TABLE

ELEV AREA M2/3 SUMH ANV ALFA SURFACE VOLUME

SEC NO. 0.000  
 INCREMENTAL AND ACCUMULATED CHANNEL LENGTHS =  
 INCREMENTAL AND ACCUMULATED WEIGHTED LENGTHS =  
 521.00 500.00 1.00 500.00 0 .0300 1.0000 0 0  
 522.00 1000.00 1.58 500.00 0 .0300 1.0000 0 0  
 523.00 1500.00 2.06 500.00 0 .0300 1.0000 0 0  
 524.00 2000.00 2.49 500.00 0 .0300 1.0000 0 0  
 525.00 2500.00 2.89 500.00 0 .0300 1.0000 0 0  
 526.00 3000.00 3.25 500.00 0 .0300 1.0000 0 0  
 0 RATIO OF ACCUMULATED WEIGHT/CHANNEL = 0.0000

SEC NO. 3.000  
 INCREMENTAL AND ACCUMULATED CHANNEL LENGTHS =  
 INCREMENTAL AND ACCUMULATED WEIGHTED LENGTHS =  
 524.17 500.00 1.00 500.00 15840 15840 RATIO OF ACCUMULATED WEIGHT/CHANNEL = 1.0000  
 525.17 1000.00 1.58 500.00 15840 15840 182  
 526.17 1500.00 2.06 500.00 15840 15840 364  
 527.17 2000.00 2.49 500.00 15840 15840 545  
 528.17 2500.00 2.89 500.00 15840 15840 727  
 529.17 3000.00 3.25 500.00 15840 15840 909  
 1091

GEOMETRIC MODEL FOR UNSTEADY FLOW PROGRAMS

SDM	ITM	JM	ASEL	DX	FORMAT
3,00	7	6	.00020	2640,0	8X,F8,0,8X,5F8,0,/(24X,5F8,0)

X-SEC NO	X	ELEV	AREA	R2/3	TOP WIDTH	AVG N-VALUE	ALPHA
3,000	0,000	524,17	500	1,00	500	.0300	1,0000
3,000	0,000	525,17	1000	1,58	500	.0300	1,0000
3,000	0,000	526,17	1500	2,06	500	.0300	1,0000
3,000	0,000	527,17	2000	2,49	500	.0300	1,0000
3,000	0,000	528,17	2500	2,89	500	.0300	1,0000
3,000	0,000	529,17	3000	3,25	500	.0300	1,0000
2,500	.500	523,64	500	1,00	500	.0300	1,0000
2,500	.500	524,64	1000	1,58	500	.0300	1,0000
2,500	.500	525,64	1500	2,06	500	.0300	1,0000
2,500	.500	526,64	2000	2,49	500	.0300	1,0000
2,500	.500	527,64	2500	2,89	500	.0300	1,0000
2,500	.500	528,64	3000	3,25	500	.0300	1,0000
2,000	1,000	523,11	500	1,00	500	.0300	1,0000
2,000	1,000	524,11	1000	1,58	500	.0300	1,0000
2,000	1,000	525,11	1500	2,06	500	.0300	1,0000
2,000	1,000	526,11	2000	2,49	500	.0300	1,0000
2,000	1,000	527,11	2500	2,89	500	.0300	1,0000
2,000	1,000	528,11	3000	3,25	500	.0300	1,0000
1,500	1,500	522,58	500	1,00	500	.0300	1,0000
1,500	1,500	523,58	1000	1,58	500	.0300	1,0000
1,500	1,500	524,58	1500	2,06	500	.0300	1,0000
1,500	1,500	525,58	2000	2,49	500	.0300	1,0000
1,500	1,500	526,58	2500	2,89	500	.0300	1,0000
1,500	1,500	527,58	3000	3,25	500	.0300	1,0000
1,000	2,000	522,06	500	1,00	500	.0300	1,0000
1,000	2,000	523,06	1000	1,58	500	.0300	1,0000
1,000	2,000	524,06	1500	2,06	500	.0300	1,0000
1,000	2,000	525,06	2000	2,49	500	.0300	1,0000
1,000	2,000	526,06	2500	2,89	500	.0300	1,0000
1,000	2,000	527,06	3000	3,25	500	.0300	1,0000
.500	2,500	521,53	500	1,00	500	.0300	1,0000
.500	2,500	522,53	1000	1,58	500	.0300	1,0000
.500	2,500	523,53	1500	2,06	500	.0300	1,0000
.500	2,500	524,53	2000	2,49	500	.0300	1,0000
.500	2,500	525,53	2500	2,89	500	.0300	1,0000
.500	2,500	526,53	3000	3,25	500	.0300	1,0000
.000	3,000	521,00	500	1,00	500	.0300	1,0000
.000	3,000	522,00	1000	1,58	500	.0300	1,0000
.000	3,000	523,00	1500	2,06	500	.0300	1,0000
.000	3,000	524,00	2000	2,49	500	.0300	1,0000
.000	3,000	525,00	2500	2,89	500	.0300	1,0000
.000	3,000	526,00	3000	3,25	500	.0300	1,0000

ELEVATION	AREA	VOLUME, *
524		182
525		364
526		545
527		727
528		909
529		1091

END OF RUN

\*NOTE: The units of volume are acre-feet.

# Input Data \*

```

* TEST 2 PREPARED IN OCT69, MODIFIED MAR71, AUG74
* GEOMETRIC ELEMENTS FROM CROSS SECTION COORDINATES, AUXILIARY PROGRAM TO
* GRADUALLY VARIED UNSTEADY FLOW PROFILES. W A THOMAS, HEC, DAVIS, CALIF.
P .0002 6. 2640. 1
R521. 522. 523. 524. 525. 526.
A0. 1. 6. 1.
B1500. 2000. 2500. 1500. 2000. 2000.
C1. 1. 1.
E0.08 .03 .08
G1000. 535. 1500. 533. 1500. 520. 2000. 530.
G2500. 535.
A3.0 1. 6.
B1500. 2000. 2500. 1500. 2000. 2000.
C15840. 15840. 15840.
G1000. 538.168 1500. 536.168 1500. 523.168 2000. 533.168
G2500. 538.168
A -1.

```

\*NOTE: Test 2 is coded in an alternate input format which is not described in this manual.

VERSION 2.2 19SEPT1974  
 \* TEST 2 PREPARED IN OCT69, MODIFIED MAR71, AUG74  
 \* GEOMETRIC ELEMENTS FROM CROSS SECTION COORDINATES, AUXILIARY PROGRAM TO  
 \* GRADUALLY VARIED UNSTEADY FLOW PROFILES, W A THOMAS, MEC, DAVIS, CALIF.

PROGRAM READING DATA IN ALTERNATE FORMAT.  
 ONLY CARDS R,M,A,B,C,D,E AND G OR GR ARE PERMITTED.

P-CARD ASL JM DX KSM(1) KSM(11) KSM(12)  
 .0002000 6 2640.00 -0 1

R-CARD 521.000 522.000 523.000 524.000 525.000 526.000  
 ELEVATIONS

T-CARD 0 0 0 INITIAL WATER SURFACE AREA IN ACRES  
 0.0 0.0 0.0 INITIAL VOLUME IN ACRE-Feet  
 0.0 0.0 0.0

SEC NO.	ELEV	AREA	R2/3	SUMW	ANV	ALFA	SURFACE	VOLUME	0	0	RATIO OF ACCUMULATED WEIGHT/CHANNELS	0.0000
INCREMENTAL	0.000								0	0		
AND ACCUMULATED CHANNEL LENGTHS =									0	0		
AND ACCUMULATED WEIGHTED LENGTH-Sq									0	0		
521.00	500.00	1.00	500.00	.0300	1.0000	0	0	0	1.0000	0	0	0
522.00	1000.00	1.58	500.00	.0300	1.0000	0	0	0	1.0000	0	0	0
523.00	1500.00	2.06	500.00	.0300	1.0000	0	0	0	1.0000	0	0	0
524.00	2000.00	2.49	500.00	.0300	1.0000	0	0	0	1.0000	0	0	0
525.00	2500.00	2.89	500.00	.0300	1.0000	0	0	0	1.0000	0	0	0
526.00	3000.00	3.25	500.00	.0300	1.0000	0	0	0	1.0000	0	0	0

SEC NO.	3.000								15840	15840	15840	1.0000
INCREMENTAL									15840	15840	15840	1.0000
AND ACCUMULATED CHANNEL LENGTHS =									15840	15840	15840	1.0000
AND ACCUMULATED WEIGHTED LENGTH-Sq									15840	15840	15840	1.0000
524.17	500.00	1.00	500.00	.0300	1.0000	182	182	182	1.0000	182	182	182
525.17	1000.00	1.58	500.00	.0300	1.0000	364	364	364	1.0000	182	364	364
526.17	1500.00	2.06	500.00	.0300	1.0000	545	545	545	1.0000	182	545	545
527.17	2000.00	2.49	500.00	.0300	1.0000	727	727	727	1.0000	182	727	727
528.17	2500.00	2.89	500.00	.0300	1.0000	909	909	909	1.0000	182	909	909
529.17	3000.00	3.25	500.00	.0300	1.0000	1091	1091	1091	1.0000	182	1091	1091

GEOMETRIC MODEL FOR UNSTEADY FLOW PROGRAM

SOM	ITM	JM	ASEL	DX	FORMAT
3.00	7	6	.00020	2640.0	8X,F8.0,8X,5F8.0,/(24X,5F8.0)

X-SEC NO	X	ELFV	AREA	W2/3	TDP WIDTH	AVG N-VALUE	ALPHA
3.000	0.000	524.17	500	1.00	500	.0300	1.0000
3.000	0.000	525.17	1000	1.58	500	.0300	1.0000
3.000	0.000	526.17	1500	2.06	500	.0300	1.0000
3.000	0.000	527.17	2000	2.49	500	.0300	1.0000
3.000	0.000	528.17	2500	2.89	500	.0300	1.0000
3.000	0.000	529.17	3000	3.25	500	.0300	1.0000
2.500	.500	523.64	500	1.00	500	.0300	1.0000
2.500	.500	524.64	1000	1.58	500	.0300	1.0000
2.500	.500	525.64	1500	2.06	500	.0300	1.0000
2.500	.500	526.64	2000	2.49	500	.0300	1.0000
2.500	.500	527.64	2500	2.89	500	.0300	1.0000
2.500	.500	528.64	3000	3.25	500	.0300	1.0000
2.000	1.000	523.11	500	1.00	500	.0300	1.0000
2.000	1.000	524.11	1000	1.58	500	.0300	1.0000
2.000	1.000	525.11	1500	2.06	500	.0300	1.0000
2.000	1.000	526.11	2000	2.49	500	.0300	1.0000
2.000	1.000	527.11	2500	2.89	500	.0300	1.0000
2.000	1.000	528.11	3000	3.25	500	.0300	1.0000
1.500	1.500	522.58	500	1.00	500	.0300	1.0000
1.500	1.500	523.58	1000	1.58	500	.0300	1.0000
1.500	1.500	524.58	1500	2.06	500	.0300	1.0000
1.500	1.500	525.58	2000	2.49	500	.0300	1.0000
1.500	1.500	526.58	2500	2.89	500	.0300	1.0000
1.500	1.500	527.58	3000	3.25	500	.0300	1.0000
1.000	2.000	522.06	500	1.00	500	.0300	1.0000
1.000	2.000	523.06	1000	1.58	500	.0300	1.0000
1.000	2.000	524.06	1500	2.06	500	.0300	1.0000
1.000	2.000	525.06	2000	2.49	500	.0300	1.0000
1.000	2.000	526.06	2500	2.89	500	.0300	1.0000
1.000	2.000	527.06	3000	3.25	500	.0300	1.0000
.500	2.500	521.53	500	1.00	500	.0300	1.0000
.500	2.500	522.53	1000	1.58	500	.0300	1.0000
.500	2.500	523.53	1500	2.06	500	.0300	1.0000
.500	2.500	524.53	2000	2.49	500	.0300	1.0000
.500	2.500	525.53	2500	2.89	500	.0300	1.0000
.500	2.500	526.53	3000	3.25	500	.0300	1.0000
.000	3.000	521.00	500	1.00	500	.0300	1.0000
.000	3.000	522.00	1000	1.58	500	.0300	1.0000
.000	3.000	523.00	1500	2.06	500	.0300	1.0000
.000	3.000	524.00	2000	2.49	500	.0300	1.0000
.000	3.000	525.00	2500	2.89	500	.0300	1.0000
.000	3.000	526.00	3000	3.25	500	.0300	1.0000

ELEVATION	AREA	VOLUME, *
524		162
525		364
526		545
527		727
528		909
529		1091

END OF JOB

\*NOTE: The units of volume are acre-feet.

# DESCRIPTION OF PAUSES

Pause No.	Cause	Action
0	End of job	
1	Negative value in input data.	Check Q(N), IDF, MEID, NCH, KXY, KOCH, n-values, NMD, ISXY.
2	one or more reach lengths either zero or blank. One or more STA(I) values are negative.	
3	Negative value in the n-value table.	
4	Logical error in program code.	Requires program debugging.
5	STA(I) is larger than the largest X coordinate on the GR cards.	
6	Sill length or sill elevation is negative.	Positive values required.
10	STST is negative	Positive value is required.
11	STST is larger than the largest X coordinate on the GR cards.	
12	STST is larger than the largest STA(I) value.	Change the data so at least 1 STA(I) value is greater than STST.
13	Logical error in sub-routine HYDLMT.	Requires program debugging.
14	Either STST or the first STA(I) value is larger than the largest X coordinate on the GR card.	
15	An X coordinate is smaller than the previous one coded on the GR card.	



Pause No.	Cause	Action
16	Logical error in sub-routine HYDLMT.	Requires program debugging.
17	Logical error in sub-routine HYDLMT. Variable LOST is one and should not be.	Same as 16.
18	Similar to 17 except LOST = 2.	Same as 16.
19	Similar to 17 except LOST = 3.	Same as 16.
20	A bridge section has been entered, but there are not enough discharge coefficients.	Check data and eliminate bridge sections.
21	Starting water surface elevation is below critical depth.	This pause should be eliminated. Check the program logic.
22	Submerged flow exists at a weir and no submergence coefficients were provided.	Eliminate weir sections.
23	Submerged flow exists and 2 submergence coefficients are the same.	Same as 22.

## GEOMETRIC ELEMENTS PROGRAM

### INPUT DATA DESCRIPTION

Version 3.0 January 1976

This input description presents a "value" or "range of values" for each variable. The code "+" under the "Value" column means any positive number. Zeroes are not recommended except where indicated in the "Value" column. Avoid negative numbers unless that option is specifically stated as a value. Blanks are read as zero except where otherwise noted. Parentheses denote footnotes. All numeric variables are read as floating point numbers and integer variables are converted immediately after being read. Numbers may be coded either left or right justified.

HEC-2 Data Cards T1, T2, T3, NC, NV, X1, X3, X4 and GR are permitted. However, only a portion of the data on cards NC, X1, and X3 are utilized in this program (see pages for each card type).

## INPUT DATA DESCRIPTION

TITLE CARDS - REQUIRED CARDS

CARDS T1, T2, T3

a. CARD T1

Title card for output title. This card is required for each job.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0		T1	Card identification characters.
1-10	None		Numbers and alphabetical characters for title.

b. CARD T2

Title card for output title. This card is required for each job.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0		T2	Card identification characters.
1-10	None		Numbers and alphabetical characters for title.

c. CARD T3

Title card for output title. This card is required for each job.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0		T3	Card identification characters.
1-10	None		Numbers and alphabetical characters for title.

Note: Columns 9-32 on card T3 are not saved for subsequent use on plots, and this differs from the T3 card in HEC-2.

## JOB PARAMETERS - REQUIRED CARD

### CARD JP

The geometric elements may be calculated for the same elevation at each cross section or they may be calculated on a sloping grid. The latter usually results in fewer elevation points for jobs covering long distances of the river. In any case, using a sloping grid is only a matter of convenience and the slope does not impact on routing calculations in the unsteady flow model.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
0	ICG	JP	Card identification characters.
1	AVGS	0,+,-	The downstream cross section identification (i.e., if cross section locations are identified by River Mile (X1-i), use the mile for the first sections here).
2	ASEL	+,-	The change in elevation between cross sections is calculated by multiplying the slope ASEL times the channel reach length.
		1000	ASEL will be based on the downstream channel slope.
		2000	ASEL will be based on the downstream minimum channel bank elevation slope.
3	NODE	0	The program will calculate the number of nodes from DX and the total model length.
		+	The program will calculate the distance between nodes from total model length and interpolate tables of geometric elements at those points.
4	DX	0	The value for NODE should be positive so the program will calculate DX and the resulting tables of geometric elements.

<u>FIELD</u>	<u>VARIABLE</u>	<u>VALUE</u>	<u>DESCRIPTION</u>
		+	Tables of geometric elements will be interpolated on the constant interval, DX, however, if both NODE and DX have been specified the value for NODE will override the value for DX.
5	LFA	0	Program calculates the velocity distribution factor ALPHA.
		1	The program assigns 1 to the velocity distribution factor.
6	NOSC	0	The largest identification number that can be printed or punched out by this program is 9999.999. The largest cross section area is 9,999,999. The program will test the size of section identification numbers and cross section areas and calculate a factor to scale down numbers which are too large. An appropriate note is printed giving the resulting scale factor.
		+	A scale factor of 1.0 is assigned.
7-8			Not used.
9	KSW(11)	0	Suppresses printout of subsection areas, wetted perimeters, conveyances, etc.
		1	Print the intermediate values of conveyance, area, hydraulic radius, n-value and reach length for each subsection in each cross section.
10	KSW(12)	0	The geometric elements are interpolated from adjacent input cross-sections and printed.
		1	Punch cards of the above geometric elements for subsequent use in the routing calculation.
		2	The geometric elements are interpolated by weighting the values at all input cross-sections within $\pm \frac{1}{2}DX$ of the node and printed.
		3	Punch cards of the above geometric elements for subsequent use in the routing calculation.

ELEVATION TABLE - REQUIRED CARDS

## CARD ET

The table of geometric elements may contain from 3 up to 21 values of elevation. The difference between two successive elevation values on this card, called the elevation interval, must be an integer amount for the routing program. Up to three different intervals may be utilized. Values must be entered from lowest to highest elevation for the routing program.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	ICG	ET	Card identification characters.
1 - 10	WS	0,+	Elevations may be zero or positive. Enter 10 values across the card and use as many cards as are required. The program will count the number of values internally using a zero or blank field to signify the end of elevations.

WEIGHTED REACH LENGTH - OPTIONAL CARDS

## CARD WL

Frequently, the channel distance is not representative of the length of flow when extremely large flood events are to be analyzed. This card permits the user to enter a length between cross sections that reflects the flow length for the floods that he plans to analyze. The weighted reach length is not used in calculating area and volume, only in establishing the location of cross sections for subsequent calculations as the geometric elements are interpolated for each Node.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	ICG	WL	Card identification characters.
1-10	XRL	0	At the first cross section only.
		+	The weighted distance from the second to the first cross section is entered in field 2. Field 3 goes with the third cross section, ETC. Enter one value of weighted reach length for each cross section. The program will count the number of values entered using 0 or blank to identify the end.

# NC

## REQUIRED CARD FOR FIRST CROSS SECTION

### CARD NC

Manning's n-values are entered for starting each job, or for changing values previously specified. Manning's n-values apply at a cross section and halfway to the cross section on either side. The values on this NC card apply to the cross section described on the following X1 card and apply until changed by a future NC card.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	IA	NC	Card identification characters.
1	XNL	0	No change in Manning's "n" value for the left overbank.
		+	Manning's "n" value for the left overbank.
2	XNR	0	No change in Manning's "n" value for the right overbank.
		+	Manning's "n" value for the right overbank.
3	XNCH	0	No change in Manning's "n" value for the channel.
		+	Manning's "n" value for the channel.

Note: Other HEC-2 variables on NC-card are not used in this program.



OPTIONAL CARD FOR ROUGHNESS DESCRIPTION

## CARD NV

Used to vary the channel n-values in the vertical based on water surface elevations. Straight line interpolation is used between points.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	IA	NV	Card identification characters.
1	NUMNV	+	Total number of Manning's "n" values entered on NV cards (maximum five). If more than one NV card is used, field 1 on the other cards would contain an ELN(N) value.
2,4,6.. .....	VALN(N)	+	Manning's "n" coefficient for area below ELN(N). The overbank "n" values specified on CARD NC will be used for the overbank roughness regardless of the values in this table.
3,5,7.. .....	ELN(N)	+	Elevation of the water surface corresponding to VALN(N) in increasing order.

Note: HEC-2 permits 20 n-value points. This program permits only 5.

## SLOPE CHANGE - OPTIONAL CARD

## CARD SC

The slope ASEL (JP-2) is changed at any cross section with this card. The slope will remain at this new slope until it is changed again. The specified set of closely spaced elevations follow approximately along the top bank elevation of the channel.

<u>Field</u> ,	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	ICG	SC	Card identification characters.
1	AVGS	0,+	The cross section identification number for the first cross section where the new slope was used.
2	ASEL	+, -	The change in elevation between cross sections is calculated by multiplying the slope ASEL times the channel reach length.
		1000	ASEL will be based on the downstream channel slope.
		2000	ASEL will be based on the downstream minimum channel bank elevation slope.

REQUIRED CARD FOR EACH CROSS SECTION

## CARD X1

This card is required for each cross section, and is used to specify the cross section geometry and program options applicable to that cross section. This program differs from HEC-2 in that it does not read Field 10 and only 100 cross sections may be specified.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	IA	X1	Card identification characters.
1	SECN0	+	Cross section identification number
		-	(Tributaries in HEC-2). Not used in this program.
2	NUMST	0	<u>Previous</u> cross section is used for current section. Next GR cards are omitted.
		+	Total number of stations on the next GR cards.
3	STCHL	0	May be omitted if NUMST (X1.2) is 0.
		+	The station of the left bank of the channel.
4	STCHR	0	May be omitted if NUMST (X1.2) is 0.
		+	The station of the right bank of the channel. Must be equal to or greater than STCHL.
5	XLOBL	+	Length of reach between current cross section and next downstream cross section of the left overbank.
6	XLOBR	+	Length of reach between current cross section and next downstream cross section for the right overbank.
7	XLCH	+	Length of reach between current cross section and next downstream cross section for the channel.

CARD X1 (cont.)

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
8	PXSECR	0	Cross section stations will not be changed by the factor PXSECR.
		+	A ratio which will be multiplied times all cross section stations, except the first station, to increase or decrease cross section width. The ratio can apply to a repeated cross section or a current one. A 1.1 would increase the width by 10 percent.
9	PXSECE	0	Cross section elevations will not be changed.
		+	Constant to be added (+) or subtracted (-) from all cross section elevations. A repeated cross section is handled in the same manner as one just entered. Elevation changes are permanent; therefore, changes accumulate with successive, repeated sections.

OPTIONAL PLOTS OF CROSS SECTION

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
10	IPLOT	0	<u>Not recognized by this program</u>

SPECIFICATION OF INEFFECTIVE FLOW AREAS

## CARD X3 - OPTIONAL CARD

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	IA	X3	Card identification characters.
1	IEARA	0	Total area of cross section described on GR cards below the water surface elevation is used in the computations.
		10	Only the cross sectional area confined by levees below the water surface elevation is used in the computations, unless the water surface elevation is above the top of levee (elevations corresponding to STCH(X1.3) and STCHR(X1.4), in which case flow areas outside the levee will be included.
2	ELSE0	0	NA
		+	NA
3	ENCFP	0	Width between encroachments is not changed or is not specified.
		+	Width between encroachments is centered in the channel, midway between the left and right overbanks. Flow areas outside this width are not included in the computations. This width will be used for all cross sections unless changed by a positive ENCFP on Card X3 of another cross section or unless overridden by the use of STENCL(X3.4).
4	STENCL	0	Encroachments by specifying station and/or elevation will not be used on the left overbank.
		+	Station of the left encroachment. Flow areas to the left of (less than) this station and below ELENCCL are not included in the computations. This option will override the option using ENCFP when both are used.

CARD X3 (cont)

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
5	ELENCL	0	An encroachment elevation on the left side is not applicable and is therefore assumed very high.
		+	Elevation of the left encroachment. Flow areas below this elevation and less than STENCL are not included in the computations.
6	STENCR	0	An encroachment station on the right is not used.
		+	Station of the right encroachment. Flow areas to the right of (greater than) this station and below ELENCR are not included in the computations.
7	ELENCR	0	An encroachment elevation on the right side is not applicable and is therefore assumed very high.
		+	Elevation of the right encroachment. Flow areas below this elevation and greater than STENCR are not included in the computations.
8	ELLEA	0	NA
		+	NA
9	ELREA	0	NA
		+	NA
10			NA

## ADDITIONAL GROUND POINTS

## CARD X4 - OPTIONAL CARD

An additional input card X4 may be inserted following cards X1, X2, or X3 in order to add additional points to describe the ground profile of the cross section. Stations of X4 data points must fall within the range of GR stations. The X4 data point is an added point and cannot be used to replace any GR data point. This option is useful when modifying data cards for a proposed obstruction as it allows points to be added anywhere in the cross section.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	IA	X4	Card identification characters.
1	NELT	+	Number of additional points to supplement the current set of GR cards read in describing the ground profile of the cross section. A maximum of 20 points may be used.
2	ELT(1)	+	Elevation of first additional ground point.
3	STAT(1)	+	Station of first additional ground point. All stations must be less than the maximum station on the GR cards. The pairs of elevations and stations do not have to be in any particular order.
4,5, etc.			Additional pairs of elevation and station values.

CONVEYANCE LIMITS - OPTIONAL CARD

## CARD KL

The geometric model for unsteady flow calculations must describe both volume and conveyance. Satisfying the volume requirement often causes cross sections to extend up tributaries. This is an area that does not contribute to conveyance of the mainstem discharge, however, and conveyance limits can be established for affected cross sections.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	ICG	KL	Card identification characters.
1	AVGS	0,+	Cross section identification number.
2	STST	0	The entire cross section is used for both volume and conveyance on the left overbank.
		+	The cross section station separating storage from conveyance on the left overbank. This value does not have to coincide with a coordinate point.
3	ENST	0	The entire right overbank of the cross section is used to convey flow.
		+	The cross section station beyond which only volume is calculated.



GROUND PROFILE

## CARD GR

This card specifies the elevation and station of each point in a cross section used to describe the ground profile, and is required for each X1 card unless NUMST (X1.2) is zero. The points outside of the channel determine the subdivision of the cross section which corrects for the nonuniform velocity distribution.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	IA	GR	Card identification characters.
1	EL(1)	+ -	Elevation of cross section point 1 at station STA(1). May be positive or negative.
2	STA(1)	+	Station of cross section point 1.
3	EL(2)	+ -	Elevation of cross section point 2 at STA(2).
4	STA(2)	+	Station of cross section point 2.

Continue with additional GR cards using up to 100 points to describe the cross section. Stations should be in increasing order and positive.

# EJ

## END OF JOB CARD

### CARD EJ - REQUIRED

Required following the last cross section for each job. Each group of cards beginning with Card T1 is considered a job.


<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0		EJ	Card identification characters.
1-10			Not used.

END OF RUN

## CARD ER - REQUIRED CARD

Required at the end of a run consisting of one or more jobs in order to end computation on stop command. Three blank cards after the EJ card of the last job are optional.

<u>Field</u>	<u>Variable</u>	<u>Value</u>	<u>Description</u>
0	IA	ER	Card identification characters
1 - 10			Not used



- (1) Identifies HEC-2 cards that may be used in this program.
- (2) Identifies cards in HEC-2 Format which are slightly changed for use in this program. See Detailed Description of Input Data.

## APPENDIX I

### Tape 95 Variable Description

# TAPE95 VARIABLES

HEC2

GEDA

<u>Variable Name</u>	<u>Description</u>	<u>Code Number</u>	<u>Variable Name</u>	<u>Description</u>
CWSEL	Computed water surface elevation.	1	ECOM	Water surface elevation.
CRIWS	Critical water surface elevation.	2	SCHL	Accumulated channel length.
EG	Energy gradient elevation for a cross section which is equal to the computed water surface elevation CWSEL plus the discharge-weighted velocity head HV.	3	XRL(NST)	Incremented weighted length.
TOPWID	Cross section width at the calculated water surface elevation.	4	SUMW	Total top width.
SLOPE (10K*S)	Slope of the energy grade line for the current section (times 10,000).	5	ASEL	Projection slope.
TIME	Travel time from the first cross section to the present cross section in hours.	6	SDM	Accumulated weighted length.
VOL	Cumulative volume of water in the stream from the first cross section (in acre-feet for English units or 1000 cubic meters in Metric units).	7	AV	Cumulative volume of water in the stream from the first cross section (in acre-feet).
DEPTH	Depth of flow.	8	QVAR	Depth of flow in the channel.
WSELK	Known water surface elevation.	9	RWC	Ratio of accumulated weight/channel.
HV	Mean velocity head across the entire cross section.	10	STST	Left overbank station separating storage from conveyance.
HL	Energy loss due to friction.	11	ENST	Right overbank station separating storage from conveyance.

# TAPE95 VARIABLES

HEC2

GEDA

<u>Variable Name</u>	<u>Description</u>	<u>Code Number</u>	<u>Variable Name</u>	<u>Description</u>
OLOSS	Energy loss due to expansion or contraction.	12	SUMP	Total wetted perimeter
QLOB	Amount of flow in the left overbank.	13	RTS	Hydraulic radius to the 2/3 power.
QCH	Amount of flow in the channel.	14	QVAR	Profile number.
QROB	Amount of flow in the right overbank.	15	QVAR	Cross section counter.
XNL (K*XNL)	Manning's 'n' for the left overbank area (times 1,000).	16	SUBK(1)*.01	Sub-conveyance value.
XNCH (K*XNCH)	Manning's 'n' for the channel area (times 1,000).	17	SUBK(2)*.01	Sub-conveyance value.
XNR (K*XNR)	Manning's 'n' for the right overbank area (times 1,000).	18	SUBK(3)*.01	Sub-conveyance value.
WTN (K*WTN)	Weighted value of Manning's 'n' for the channel based on the distance between cross sections and channel flow from the first cross section. Used when computing Manning's 'n' from high water marks (times 1,000).	19	ANV	Average 'n' value.
CASE	A variable indicating how the water surface elevation was computed. Values of -1, -2, -3, and 0 indicate assumptions of critical depth, minimum difference a fixed change (X5 card) or a balance between the computed and assumed water surface elevations.	20	SUBK(4)*.01	Sub-conveyance value.

# TAPE95 VARIABLES

HEC2

GEDA

<u>Variable Name</u>	<u>Description</u>	<u>Code Number</u>	<u>Variable Name</u>	<u>Description</u>
STCHL	Station of the left bank	21	QVAR	Left bank station.
STCHR	Station of the right bank.	22	QVAR	Right bank station.
XLBEL	Left bank elevation.	23	QVAR	Left bank elevation.
RBEL	Right bank elevation.	24	QVAR	Right bank elevation.
AREA	Cross section area.	25	SUMA	Cross section area.
VCH	Mean velocity in the channel	26	SUBK(5)*.01	Sub-conveyance value.
STENCL	The station of the left encroachment.	27	STENCL	The station of the left encroachment.
STENCR	The station of the right encroachment.	28	STENCR	The station of the right encroachment
CLSTA	The centerline station of the trapezoidal excavation.	29	SUBK(6)*.01	Sub-conveyance value.
BW	The bottom width of the trapezoidal excavation.	30	SUBK(7)*.01	Sub-conveyance value.
ELENCL	Elevation of left encroachment.	31	ELENCL	Elevation of left encroachment.
ELENCR	Elevation of right encroachment.	32	ELENCR	Elevation of right encroachment.
CHSLOP (K*CHSL)	Channel slope (times 1,000).	33	QVAR	Channel slope.
.01K	The total discharge (index Q) carried with $S^{1/2} = .01$ (equivalent to .01 times conveyance).	34	SUMK*.01	Total conveyance.
QLOB%	Percent of flow in the left overbank.	35	SA(1)	Sub-area value.



# TAPE95 VARIABLES

HEC2

GEDA

<u>Variable Name</u>	<u>Description</u>	<u>Code Number</u>	<u>Variable Name</u>	<u>Description</u>
PERENC	The target of encroachment requested	36	SA(2)	Sub-area value.
TWA	The cumulative topwidth area (acres or 1000 square meters).	37	ASA	Cumulative topwidth area (in acres).
SECNO	The cross section identification number.	38	AVGS	The cross section identification number.
XLCH	Channel reach length.	39	CHL	Incremented channel length.
ELTRD	Minimum elevation for top of road profile.	40	SA(3)	Sub-area value.
ELLC	Maximum low chord elevation.	41	SA(4)	Sub-area value.
ELMIN	Minimum elevation in cross section.	42	QVAR	Minimum elevation in the channel strip.
Q	Discharge.	43	SA(5)	Sub-area value.
EGPRS	Energy elevation assuming pressure flow.	44	SA(6)	Sub-area value.
EGLWC	Energy elevation assuming low flow.	45	SA(7)	Sub-area value.
QWEIR	Total weir flow at the bridge.	46	R(1)	Sub-hydraulic radius value.
QPR	Total pressure or low flow at the bridge.	47	R(2)	Sub-hydraulic radius value.
H3	Change in water surface elevation from Yarnell's equation.	48	R(3)	Sub-hydraulic radius value.

# TAPE95 VARIABLES

HEC2

GEDA

<u>Variable Name</u>	<u>Description</u>	<u>Code Number</u>	<u>Variable Name</u>	<u>Description</u>
CLASS	Controlling flow type for bridge solution.	49	R(4)	Sub-hydraulic radius value.
DIFWSP	Difference in water surface elevation for each profile.	50	R(5)	Sub-hydraulic radius value.
DIFWSX	Difference in water surface elevation between sections.	51	R(6)	Sub-hydraulic radius value.
DIFKWS	Difference between known and computed water surface elevations.	52	R(7)	Sub-hydraulic radius value.
SSTA	Starting station where the water surface intersects the ground (on the left side of the cross section).	53	QVAR	Starting station where the water surface intersects the ground (on the left side of the cross section).
ENDST	Ending station where the water surface intersects the ground on the right side.	54	QVAR	Ending station where the water surface intersects the ground on the right side.
VLOB	Average velocity in the left overbank area.	55	XNV(1)	Sub-n value.
VROB	Average velocity in the right overbank area.	56	XNV(2)	Sub-n value.
ALPHA	Velocity head coefficient.	57	ALFA	Velocity head coefficient.
KRATIO	Ratio of the upstream to downstream conveyance.	58	XNV(3)	Sub-n value.
QROB%	Percent of flow in the right overbank.	59	XNV(4)	Sub-n value.
QCH%	Percent of flow in the channel.	60	XNV(5)	Sub-n value.

# TAPE95 VARIABLES

HEC2

<u>Variable Name</u>	<u>Description</u>	<u>Code Number</u>	<u>Variable Name</u>	<u>Description</u>
DIFEG	Difference in energy elevation for each profile.	61	XNV(6)	Sub-n value.
INLEQ	Friction loss equation index.	62	XNV(7)	Sub-n value.
TELMX	Elevation of the lower of the two end points of the cross section.	63	QVAR	Elevation of the lower of the two end points of the cross section.
NA		64	QVAR	Minimum channel bank slope.
NA		65	QVAR	Minimum channel bank elevation.

APPENDIX II

GEDA --Tape 95

## TAPL 95

First record on tape 95:

Z ITAPE JM Z Z KVAR Z Z Z

Z - a zero value is used

ITAPE - This is set to 94 to identify it as a GEDA tape 95

JM - is set equal to the total number of profiles

KVAR - is set to 65, which is the number of variables written  
out to tape 95

Second record on tape 95:

TITLE(1) - TITLE (6)

TITLE - Title on title card based on A4 format

Third record on tape 95:

X(1) - X(100), Z, Z

X and Z - are set to zero

Fourth record on tape 95:

X(1) - X(100)

X - is set to zero

Fifth and all other records on tape 95:

QVAR(1) - QVAR(65)

Last record on tape 95:

QVAR(1) is set equal to  $-1.E + 0.5$

QVAR(1) - QVAR(65)

Total records = 4 + total number sections X total number of profiles + 1